CITY OF NEWTON, MASSACHUSETTS

PURCHASING DEPARTMENT

purchasing@newtonma.gov Fax (617) 796-1227

April 6, 2010

ADDENDUM #2

INVITATION FOR BID #10-52

ANNUAL – WATER MAIN REHAB AT VARIOUS LOCATIONS

THIS ADDENDUM IS TO: 1. Make changes to the specifications

2. Answer Questions

3. Provide REVISED Item Sheets for Item Sheet-Page 2; Item Sheet Page 3 &

Item Sheet - Page 13

SPECIFICATIONS

1. Reference Specification SECTION 00300 – BID FORM #10-52: **Delete Page 21 and insert attached Page 21.**

2. Reference Specification SECTION 01025 – MEASUREMENT AND PAYMENT:

A. Paragraph 1.18, add the following paragraphs after Item No. 72:

Item No. 73: Temporary Trench Pavement

Payment shall be made at the price bid per ton under Bid item No. 73 in the Bid Form. Payment shall be full compensation for all preparatory work and furnishing, placing and compacting the asphaltic concrete pavement as required by the Contract Documents. The price shall include the cost of the bituminous material placement and maintenance of the construction to include additional materials and labor required due to settlement and/or maintenance over a winter shut down, tack coat, cutting or keying of the pavement, removal and resetting of all manhole frames, gate boxes, catch basins, etc.; and the repair of traffic loop detectors.

- 3. Reference Specification SECTION 02513 ASPHALTIC CONCRETE PAVEMENT:
 - A. Paragraph 3.04, add the following:
 - E. TEMPORARY TRENCH PAVEMENT
 - 1. Place after underground facilities have been installed.
 - 2. Pavement shall be the type as specified in this Section except that "cold-mix" will be acceptable for repairs during seasonal closure of the asphalt concrete supplier.
 - 3. Compacted thickness shall be 2 inches.

- 4. Reference Specification SECTION 02611 DUCTILE IRON PIPE AND FITTINGS:
 - A. Paragraph 1.03B, replace this paragraph with the following:
 - B. All ductile iron pipe and fittings shall be of domestic manufacture or an approved equal..
 - Q1. We would like to know where item #11 800 CY for concrete encasement will be used?
 - A1. Delete Page 10 and insert attached Page 10. Revised quantity will be used at the discretion of the Field Engineer.
 - Q2. We would like to know where item #13 4000 lf reset existing curb will be used?
 - A2. Delete Page 11 and insert attached Page 11. Revised quantity will be used at the discretion of the Field Engineer.

All other terms and conditions of this bid remain unchanged

PLEASE ENSURE THAT YOU ACKNOWLEDGE THIS ADDENDUM ON YOUR BID FORM

Thank you.

Re Cappoli

Chief Procurement Officer

ITEM SHEETS REVISED PAGE 2

ITEM DESCRIPTION & BID PRICE

Est.	Unit	Total
Qty.	Measure	Cost

ITEM: 6 - ROCK REMOVAL					
THE SUM OF:					
AND		DOLLARS CENTS			
(\$			250	C.Y.	\$
					Ψ
ITEM: 7 - GRAVEL BORROW					
THE SUM OF:		DOLLARS			
AND		CENTS			
(\$) PER	TON	2,500	TON	\$
ITEM: 8 - DENSE GRADED CRUS	SHED STON	E			
THE SUM OF:					
AND		DOLLARS CENTS			
			800		ф
(\$) PEK	TON	000	TON	\$
ITEM: 9 - SAND FOR WATER PIF	'E BEDDING				
THE SUM OF:					
AND		_ DOLLARS CENTS			
(\$) PER	TON	1,000		\$
(1				TON	
ITEM: 10 - 3/4" FRACTURED CRU	SHED STON	1E			
THE SUM OF:		DOLLARS			
AND					
(\$) PER	TON	30	TON	\$
				ION	
ITEM: 11 - CLASS B CEMENT CO	NCRETE FO	R ENCASEMENT			
THE SUM OF:		DOLLARS			
AND					
(\$) PER	CUBIC YARD	80	C.Y.	\$

Est.

Unit

Total

ITEM DESCRIPTION & BID PRICE

TIEM DESCRIPTION & BID PRICE		Qty.	Measure	e Cost
ITEM: 12 - DUST CONTROL (CHEMICAL TR	REATMENT)			
THE SUM OF:				
AND	DOLLARS CENTS			
(\$) PER	POUND	7,500	LB.	\$
ITEM: 13 - RESET EXISTING CURB				
THE SUM OF:				
AND				
(\$) PER	LINEAR FOOT	400	L.F.	\$
ITEM: 14 - 4" BITUMINOUS CONCRETE TYI PERMANENT TRENCH RESURFACING (PLA COURSES)				
THE SUM OF:	DOLLARS			
AND		1 000	TON	
(\$) PER	TON	1,000	TON	\$
ITEM: 15 - SEAM & CRACK SEALING (APPLIED AFTER THE PERMANANET PATCH C	DPERATION)			
THE SUM OF:				
AND	DOLLARS CENTS			
(\$) PER	GALLON	400	GAL.	\$
ITEM: 16 - 2" BITUMINOUS CONCRETE WADRIVEWAYS (PATCHING PRIVATE PROPERTY)	LKS &			
THE SUM OF:	5011.150			
AND	DOLLARS CENTS			
(\$) PER	SQUARE YARD	75	S.Y.	\$
ITEM: 17 - 3" BITUMINOUS CONCRETE WADRIVEWAY APRONS (PATCHING PUBLIC PROP				
THE SUM OF:	DOLLARS			
AND				
(\$) PER	SQUARE YARD	700	S.Y.	\$

ITEM SHEETS	REVISED				PAGE 13
		Est.	Unit	Total	
ITEM DESCRIPTION & BID PRICE		Qty.	Measure	Cost	
		1	<u> </u>		
ITEM: 71 – 1-INCH FULL WIDTH OVERLAY	// 2-INCHES				
TEMPORARY TRENCH PAVEMENT					
(LONGWOOD ROAD ONLY)					
THE SUM OF:					
	DOLLARS				
AND	CENTS				
		150	TON	\$	
(\$) PER	TON				
ITEM: 72 – SLURRY FILL EXISTING AC WA	TER MAINS				
THE SUM OF:	DOLL IDG				
ANTO	DOLLARS				
AND	CEN1S				
(\$) PER	CURIC YARD	150	C.Y.	\$	
(Ψ	CCDIC TIME	100	0.1.	Ψ	
TOTAL 52 TEMPODADY EDENICH DAVISM					
ITEM: 73 – TEMPORARY TRENCH PAVEMI	EN I				
THE SUM OF:					
	DOLLARS				
AND	CENTS				
(\$) PER	TON	400	TON	\$	

TOTAL BID ITEMS 1-73 \$____

The total bid amount must be placed in paragraph "C" of the bid form.

END OF SECTION