SEWER HOUSE CONNECTION FORCE MAIN AT QUINOBEQUIN & EAST QUINOBEQUIN RD.

THIS WORKSHEET IS PROVIDED AS A COURTESY. THE CONTRACTOR IS RESPONSIBLE FOR CORRELATING THE INFORMATION SHOWN HERE WITH THE CONTRACT DOCUMENTS.

ITEM	DESCRIPTION	QUAN.	UNIT	EST UNIT COST	EXTENSION
1	MOBILIZATION (LAYOUT SERVICES, VIDEO FILE, NOTIFICATIONS, MEETINGS, ETC.)	1	LS		
	MANUFACTURED SILT SACK FOR CATCHBASIN (SEDIMENTATION CONTROL)	6	ΕĀ		
3	TREE PROTECTION	8	EA		
4	SAW-CUTTING OF PAVEMENT	600	LF		
5	GENERAL EXCAVATION & DISPOSAL OF MATERIAL(S)	NA	NA	NA	NA
6	EXPLORATORY EXCAVATION	40	CY		
7	EXCAVATION & DISPOSAL OF UNSUITABLE SOIL MATERIAL(S) (INCLUSIVE OF EXTRA-DEPTH WORK)	10	CY		
8	REMOVAL & DISPOSAL OF ROCK	5	CY		
9	SHEATHING, SHORING AND/OR PLATING OF TRENCHES & EXCAVATIONS	1	LS		
10	DEWATERING OPERATION	3	DAY		
11	F&I HAY BALES & PRE-FABRICATED SILT FENCE (FOR DEWATERING & STORAGE CONTAINMENT)	75	LF		
12	5' INSIDE DIAMETER PRE-CAST H20-RATED SEWER MANHOLE FOR GRINDER/PUMP ASSEMBLY (WITH FLEXIBLE BOOTS) (EXCLUDING FRAME & COVER)	13	VF		
13	STANDARD 4' INSIDE DIAMETER PRE-CAST H20-RATED SEWER MANHOLE FOR HOUSE CONNECTIO1N (WITH FLEXIBLE BOOTS) (EXCLUDING FRAME & COVER)	18	VF		
14	F&I A NON-STANDARD OVERSIZED SPECIALTY SEWER MANHOLE FRAME & COVER	1	SET		
15	F&I A STANDARD SIZE SEWER MANHOLE FRAME & COVER	1	SET		
	FIELD ASSEMBLED DUPLEX SEWER GRINDER/PUMP SYSTEM (COMPLETE-IN-PLACE)	1	LS		
16.1	REPLACEMENT GRINDER/PUMP (TO BE PLACED IN STORAGE)	2	EA		
17	DUPLEX '4 FLOAT/4 POSITION' CONTROL PANEL (INCLUSIVE OF CONNECTION TO PUMP STATION SERVICE PANEL)	1	LS		
18	1 1/2" SCHEDULE 80 PVC CONDUIT (WITH TAPE) FOR ELECTRICAL & COMMUNICATION END USE	375	LF		
19	1 1/2" SCHEDULE 80 PVC CONDUIT '90 DEG. LONG SWEEP' FOR ELECTRICAL & COMMUNICATION END USE	8	EA		
20	1 1/2" SCHEDULE 80 PVC CONDUIT (WITH TAPE) FOR SEWER FORCE MAIN	575	LF		
21	PRE-CAST CONCRETE HANDHOLE /'PULL BOX' WITH COVER	2	EA		
	F-T-L 6" SDR 35 P.V.C. SEWER PIPE (FOR SEWER SERVICE/HOUSE CONNECTION)	140	LF		
	STRONG-BACK' FLEXIBLE COUPLING @ 5" PIPE x 6" SDR35 P.V.C. PIPE (FOR SEWER SERVICE/HOUSE CONNECTION TRANSITION)	2	EA		
	SAND FOR THE BEDDING OF PIPES & CONDUITS	185	TON		
	3/4" FRACTURED CRUSHED STONE	5	TON		
	GRAVEL FURNISHED FROM OUTSIDE THE SITE FOR GENERAL USE	20	TON		
	DENSE GRADED CRUSHED STONE	100	TON		
	2" BITUMINOUS CONCRETE FOR TEMPORARY PATCH	25	TON		
	4" TYPE I-1 BITUMINOUS CONCRETE FOR PERMANENT PATCH TRENCH RESURFACING (PLACED IN TWO COURSES)	60	TON		
	ADJUST A PRE-EXISTING SERVICE OR UTILITY GATE BOX	2	EA		
	RESET CURB	10	LF		
	CEMENT CONCRETE WITH LAMPBLACK (@ 2POUNDS/C.Y.) FOR PANEL REPAIR	8	CY		
	LOAM BORDER & LAWN RESTORATION	10	SY		
	DUST CONTROL (CHEMICAL TREATMENT)	500	LB		
	MATERIALS TESTING ALLOWANCE	\$500	ALL	\$500	\$500
	MISCELLANEOUS WORK ALLOWANCE (ENGINEERS DISCRETIONARY FUND)	\$2,000	ALL	\$2,000	\$2,000
	ALLOWANCE FOR PAYMENT OF POLICE OFFICERS (MONIES TO BE PAID THRU AN INTER-DEPARTMENTAL BILLING PROGRAM)	\$10,000	ALL	\$10,000	\$10,000
	FURNISH & MOUNT SAFETY & SPECIALTY SIGNBOARDS (INCLUDING THE POST SYSTEM)	60	SF		
39	WARNING AND/OR SAFETY DEVICES FOR THE CONTROL OF CONSTRUCTION OPERATIONS	1	LS		

TOTAL

TOTAL +	%	

PROCESS AND CONSTRUCTION NOTES:

- 1. THE CONTRACTOR IS REQUIRED TO PROVIDE A SUPERINTENDENT OF OPERATIONS, A QUALIFIED INDIVIDUAL WHO WILL BE ON—SITE AT ALL TIMES TO ADDRESS THE CRITICAL NEEDS OF THE PROJECT. IN ADDITION, A 7 DAY/24 HOUR PHONE NUMBER MUST BE LISTED WITH THE CITY TO ADDRESS ALL PROJECT BUSINESS AND/OR EMERGENCY CALLS.
- 2. HOURS OF OPERATIONS ARE SET BY LAW. NO MACHINES OR EQUIPMENT ARE TO BE ACTIVATED BEFORE 7:00 A.M. & NO WORK IS TO EXTEND BEYOND 4:30 P.M.. NO WEEKEND OR HOLIDAY WORK, OR OTHER OFF HOUR WORK, IS ALLOWED WITHOUT SPECIAL PERMISSION. 3. THE CONTRACTOR IS RESPONSIBLE FOR MAKING ARRANGEMENTS WITH ALL ABUTTERS FOR THE PURPOSE OF ACCESSING THE PROJECT ZONE, OR HE SHALL OTHERWISE CONFINE HIS ACTIVITIES TO THE EASEMENT LIMITS.
- 4 THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING, COMMUNICATING DIRECTLY WITH, AND SUBSEQUENTLY ADDRESSING THE NEEDS OF THE VISUALLY IMPAIRED, AND/OR THE PHYSICALLY CHALLENGED WHO RESIDE IN OR ABOUT THE PROJECT ZONE.
- AREAS DISTURBED BEYOND THE LIMIT OF THE CONTRACT SHALL BE REPAIRED AND/OR RESTORED AT THE CONTRACTORS OWN EXPENSE AND LEFT IN A CONDITION COMPARABLE TO THE ORIGINAL, ALL OF WHICH IS SUBJECT TO THE ENGINEERS APPROVAL.
- 5. THE CONTRACTOR SHALL MAKE A VIDEO AND/OR PHOTOGRAPHIC RECORD OF EXISTING CONDITIONS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION ACTIVITIES PROGRESS. THE CONTRACTOR IS RESPONSIBLE FOR DEFENDING AND/OR RESPONDING TO ALL DAMAGE CLAIMS. A COPY OF THE VIDEO AND ANY SUPPLEMENTAL PHOTOGRAPHS SHALL BE SUBMITTED TO THE CITY ENGINEER UPON REQUEST.
- 6. THE FINAL DETERMINATION OF THE SCOPE OF PROJECT, AS WELL AS THE PROJECT LIMIT(S), SHALL BE ESTABLISHED IN THE FIELD BY THE ENGINEER.
- 7. THE UNDERGROUND PIPES & STRUCTURES SHOWN ON THESE PLANS ARE TAKEN FROM THE BEST AVAILABLE DEPARTMENTAL SOURCES. THE CITY DOES NOT GUARANTEE EITHER THE ACCURACY, OR THE COMPLETENESS, OF THIS INFORMATION. THE CONTRACTOR MUST MAKE HIS OWN INVESTIGATIONS OF THE AREA(S) PRIOR TO MOBILIZATION.
- 8. THE CONTRACTOR IS RESPONSIBLE FOR THE VERIFICATION OF ALL EXISTING CONDITIONS AND IS OBLIGATED TO IMMEDIATELY NOTIFY THE ENGINEER OF ANY DISCREPANCIES OF PLAN VERSUS ACTUAL FIELD CONDITIONS, AS WELL AS ANY SUBSTANTIAL DIFFERENCES IN ESTIMATED QUANTITIES. 9. THE CONTRACTOR SHALL CONTACT DIG SAFE @ 1—888—344—7233 AND SHALL NOT OCCUPY ANY AREA(S) UNTIL THE AUTHORIZATION DATE HAS BEEN ATTAINED.
- 10. FOR FURTHER UTILITY SUPPORT. AND EMERGENCY RESPONSE REQUESTS, THE CONTRACTOR IS ADVISED TO CONTACT AND ESTABLISH PROTOCOL WITH ALL ORGANIZATIONS HAVING UTILITIES IN THE PUBLIC WAY INCLUSIVE OF; KEYSPAN GAS, N-STAR ELECTRIC, VERIZON, AT&T CABLE, NEWTON WATER, NEWTON SEWER & DRAIN. 11. ANY UTILITY RELOCATIONS, AND/OR UTILITY ISSUES, ARE TO BE DIRECTLY ADDRESSED AND COORDINATED BY THE CONTRACTOR WITH THE RESPECTIVE UTILITY COMPANY AND ANY ADJOINING CITY OR TOWN WHENEVER APPLICABLE.
- 12. ANY DAMAGE TO THE EXISTING SEWER, DRAIN AND/OR WATER SYSTEMS WHICH IS NOT SPECIFICALLY DUE TO THE REMOVAL OF IMPACTED ROCK, IS TO BE REPAIRED AND/OR REPLACED BY THE CONTRACTOR AT HIS OWN EXPENSE UNLESS OTHERWISE NOTED. IMPACTED ROCK CONDITIONS ARE TO BE VERIFIED BY THE ENGINEER PRIOR TO ROCK REMOVAL.
- 13. IT IS THE RESPONSIBILIY OF THE CONTRACTOR TO COMPLY WITH U.S OCCUPATIONAL HEALTH AND SAFETY ADMINISTRATION (OSHA) STANDARDS, AND MASSACHUSETTS DEPARTMENT OF LABOR OCCUPATIONAL SAFETY STANDARDS IN THE PERFORMANCE OF THIS WORK. 14. THE CONTRACTOR IS RESPONSIBLE FOR ALL SAFETY ASPECTS OF THIS PROJECT, AND COMPLIANCE WITH THE MOST CURRENT OSHA REGULATIONS.
- 15. THE SEWER LINE GRADES, ONCE ADJUSTED, SHALL BE INSTALLED WITH USE OF A TRANSIT/LEVEL, AND THE CONTRACTOR IS FURTHER RESPONSIBLE FOR THE LAYOUT, LINE AND GRADE OF ALL OTHER MANHOLES, PIPES AND APPURTENANCES.
- 16. THE CONTRACTOR IS REQUIRED TO TAKE AS-BUILT TIES AS THE WORK PROGRESSES. THIS ACTIVITY IS TO TAKE PLACE UNDER THE ENGINEER AND ALL RECORDS ARE TO BE SUBMITTED ON A DAILY BASIS. IN ADDITION, THE CONTRACTOR IS TO SUBMIT A FINAL AS-BUILT PLAN ON A FORMAT ACCEPTABLE TO THE ENGINEER.
- 17. THE CONTRACTOR IS RESPONSIBLE FOR THE COORDINATION, POSTING AND SUBSEQUENT REMOVAL OF ALL TEMPORARY PARKING BANS. SIGNS SHALL NOT BE POSTED ON TREES. THE CONTRACTOR IS TO APPRISE THE CITY OF NEWTON TRAFFIC DIVISION OF EACH POSTING. 18. ALL EXCESS EXCAVATION MATERIAL AND/OR WASTE ITEMS, , OF ANY TYPE OR MATERIAL, INCLUSIVE OF SATURATED SOILS, ARE TO BE DISPOSED OF AT A LEGAL DUMPING SITE AT THE CONTRACTORS OWN EXPENSE. NO DISPOSAL SITE SHALL BE PROVIDED BY THE CITY.
- 19. ALL SITE GENERATED DEBRIS AND REFUSE IS TO BE REMOVED FROM THE SITE ON A DAILY BASIS. AT NO TIME SHALL PASSAGE ALONG ANY SIDEWALK AND/OR DRIVEWAY BE IMPEDED/BLOCKED BY STOCKPILED MATERIAL(S).
- 20. THE STAGING AND STOCKPILING AREA, EVEN THOUGH ARRANGED BY THE CONTRACTOR, IS TO BE KEPT IN A CONDITION ACCEPTABLE TO THE ENGINEER. THE CONTRACTOR IS RESPONSIBLE FOR ALL SAFETY ASPECTS RELATIVE TO THIS AREA.
- 21. ALL EXCAVATIONS ARE TO BE BACKFILLED IN LIFTS, WITH EACH SUCCESSIVE LIFT BEING COMPACTED ONLY WITH APPROVED COMPACTORS AND/OR PNEUMATICALLY POWERED TAMPING BITS, UNTIL SUCH TIME AS THE OPTIMUM 95% DENSITY COMPACTORS AND/OR PNEUMATICALLY POWERED TAMPING BITS, UNTIL SUCH TIME AS THE OPTIMUM 95% DENSITY COMPACTORS AND/OR PNEUMATICALLY POWERED TAMPING BITS, UNTIL SUCH TIME AS THE OPTIMUM 95% DENSITY COMPACTORS AND/OR PNEUMATICALLY POWERED TO ENSURE LONG-TERM STRUCTURAL INTEGRITY OF THE WORK 22. FOR FURTHER DETAILS NOT SHOWN ON THESE PLANS SEE CITY OF NEWTON GENERAL CONSTRUCTION DETAILS @ www.ci.newton.ma.us/dpw/engin/General Construction Detail.pdf
- 23. ALL 'SHORT-TERM' STEEL TRENCH PLATES, (UP TO FIVE CALENDAR DAYS OF USE), ARE TO BE SECURED IN SUCH A MANNER SO AS TO PREVENT MOVEMENT AND/OR 'RATTLING'. ALL 'LONG-TERM' PLATES ARE TO BE RECESSED INTO THE EXISTING ROADWAY.
- 24. THE CONTRACTOR IS TO MAINTAIN AND/OR PROVIDE EMERGENCY VEHICLE ACCESS THROUGHOUT EACH PROJECT AREA. IN ADDITION, NO TRAFFIC DELAYS AND/OR CONFUSION. 25. IF DETOURING IS ALLOWED OR DIRECTED BY THE ENGINEER ALL SECONDARY ROADS MUST BE APPROPRIATELY DETOURED, MARKED, OR ADDITIONALLY SIGNED TO PREVENT DELAYS AND/OR DIRECTIONAL CONFUSION.
- 26. BITUMINOUS CONCRETE APPLIED TO THE ROADWAY SHALL ONLY BE APPLIED IN BRIGHT SUNSHINE OR PARTLY CLOUDY WEATHER WITHOUT THE CONTRACTOR IS NOT TO SCHEDULE BITUMINOUS ROADWAY APPLICATION UNLESS SUCH FAVORABLE WEATHER CONDITIONS ARE
- PROFESSIONALLY FORECAST BY A RECOGNIZED WEATHER AGENCY. FURTHER, NO BITUMINOUS CONCRETE SHALL BE APPLIED UPON A RESIDUALLY WET SURFACE, AND NO BITUMINOUS CONCRETE WHICH HAS BEEN PRE-MATURELY COOLED BY RAIN, EITHER ON THE TRUCK OR ON THE ROADWAY, WILL BE ACCEPTED.
- 27. THE CONTRACTOR IS TO EXERCISE DUE CARE WHEN WORKING IN THE PROXIMITY OF STREET TREES. NO SCUFFING OF THE TRUNK WILL BE ALLOWED. THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR TREE TRUNK AND/OR EXCESSIVE ROOT SYSTEM DAMAGE. • TREE PROTECTION MEASURES WILL BE ORDERED IF TREE TRUNK DAMAGE IS IN EVIDENCE. THE COST OF THESE PROTECTIVE MEASURES ARE TO BE BORNE BY THE CONTRACTOR. PROTECTIVE MEASURES SHALL BE PERFORMED IN A MANNER ACCEPTABLE TO THE ENGINEER.
- EXISTING TREE ROOTS ARE NOT TO BE DISTURBED UNLESS AUTHORIZED BY THE ENGINEER AND/OR THE SUPERINTENDENT OF FORESTRY/TREE WARDEN. THE CONTRACTOR IS RESPONSIBLE FOR CAREFULLY EXCAVATING IN AND ABOUT EXISTING ROOT SYSTEMS.
- . NO TREES ARE TO BE REMOVED, NOR SHALL ANY TAP ROOTS LARGER THAN 2" IN DIAMETER BE REMOVED, UNTIL SUCH WORK HAS BEEN DIRECTLY AUTHORIZED BY THE CITY OF NEWTON TREE WARDEN OR HIS DESIGNEE. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING THIS WORK 28. POLICE DETAILS ARE TO BE COORDINATED BY THE CONTRACTOR.

OPERATIONAL NOTES:

BEFORE THE COMMENCEMENT OF ANY SITE ACTIVITIES THE CONTRACTOR SHALL INSTALL TREE PROTECTION TO EACH TREE LOCATED WITHIN 50' OF THE PROPOSED (FORCE MAIN) SMH, AND TO ALL OTHER TREES WHERE THE EXCAVATION AND/OR CONSTRUCTION RELATED. ACTIVITIES ARE TO BE PERFORMED WITHIN THE DRIP-LINE OF ANY GIVEN TREE HAVING A TRUNK DIAMETER OF 6" OR MORE. FURTHER, THE CONTRACTOR TO DIRECT THE CONTRACTOR TO PROTECT ANY OTHER TREE AS FIELD CONDITIONS MAY NECESSITATE. HOWEVER, THE CONTRACTOR SHALL ALWAYS BE RESPONSIBLE FOR ANY DAMAGE CAUSED TO ANY TREE DUE TO HIS OPERATIONS.



• AN EXPLORATORY EXCAVATION, TO VERIFY ACTUAL INTERCEPT GRADE OF THE SHC'S, MUST BE PERFORMED PRIOR TO THE COMMENCEMENT OF OPERATIONS. THE PROPOSED GRADES SHALL BE ADJUSTED ACCORDINGLY.

• NOTE A: THE EXISTING SEWER HOUSE CONNECTIONS (SHC'S) SHALL NOT BE CUT AND PLUGGED UNTIL THE PROPOSED SEWER PUMP/GRINDER SYSTEM HAS BEEN FULLY INSTALLED, TESTED, IS COMPLETELY OPERATIONAL, AND HAS BEEN ACCEPTED BY ALL CONCERNED PARTIES

SUITABLE BACKFILL MATERIAL COMPACTED IN 1' LIFTS 'JUMPING JACK' RECIPROCATING COMPACTION IS STRICTLY ENFORCED. NO PLATE COMPACTORS ARE TO BE USED IN TRENCHWORK OPERATIONS 95% DENSITY REQUIRED THROUGHOUT

TYPICAL ROADWAY TRENCH REPAIR & PAVEMENT SECTION (NOT TO SCALE)

TREE PROTECTION (TRUNK BANDING

PLAN FOR THE INSTALLATION

SEWER HOUSE CONNECTION FORCE MAIN AT THE INTERSECTION OF QUINOBEQUIN RD.

CITY OF NEWTON MASSACHUSETTS

EAST QUINOBEQUIN RD.

SCALE: AS NOTED

APRIL 23, 2012

Louis. M. Taverna, P.E. CITY ENGINEER

TRAFFIC CONTROL INFORMATION


DETOURING ALONG THE QUINOBEQUIN ROAD CORRIDOR WILL NOT BE ALLOWED

SIGN REQUIREMENTS & LEGEND:

- * SIGNS ARE TO BE FIRMLY FASTENED TO THE RESPECTIVE SUPPORTS AND OR DRUMS AND ARE TO COMPLY WITH THE DIRECTIVES OUTLINED IN THE GENERAL CONSTRUCTION DETAILS. • POST MOUNTED SIGNS ARE TO BE SET IN FULL VIEW WITH THE BOTTOM OF THE SIGN NOT LESS THAN 7' NOR MORE THAN 10' ABOVE THE ADJACENT GRADE.
- SIGNS ARE TO BE PROFESSIONALLY MADE OF 3/4" EXTERIOR PLYWOOD. THE FIELD IS TO BE REFLECTORIZED ORANGE BEARING A BLACK LEGEND 6" IN HEIGHT AND A BLACK SOLID 1" BORDER SET 1 1/4" IN FROM THE EDGE.
- · ANY SIGN WHICH IS DAMAGED FOR ANY REASON DURING THE TERM OF THE
- ANY MISSING SIGN SHALL REDUCE THE PAYMENT AT THE RATE OF THE PRO-RATED VALUE FOR THE LENGTH OF TIME THAT THE SIGN IS OUT OF SERVICE
- TEXT IS TO BE 'SCOTCHCAL' OR EQUIVALENT PRESSURE SENSITIVE LETTERS OVER WHITE HEAT ACTIVATED ENGINEERING GRADE BACKGROUND OF SIMILAR MATERIAL. ALL TEXT IS TO BE 4" HIGH OR AS OTHERWISE NOTED.
- ° SIGNS AND SIGN POSTS ARE TO BE MOUNTED AND ESTABLISHED SO AS TO BE BOTH STURDY AND WIND RESISTANT. ONLY ADEQUATELY SIZED NUT, BOLT & WASHER FASTENERS SHALL BE USED. NO NAILS ARE TO BE USED TO FASTEN ANY SIGN, NOR SHALL ANY SIGN BE MOUNTED ON ANY TREE. THE SIGN LOCUS ON THESE PLANS REPRESENT THE MOST LIKELY LOCATIONS, HOWEVER, FINAL LOCATIONS AND/OR SUPPLEMENTAL SIGNS AND DRUMS SHALL BE LOCATED, RELOCATED, AND/OR PLACED AS THE OPERATIONAL PROCESS MAY NECESSITATE AND/OR AS DIRECTED BY THE ENGINEER.
- SIGNS SHALL BE PLACED IN THE MOST CONSPICUOUS LOCATIONS AS A MEANS FOR BOTH VEHICULAR AND PEDESTRIAN WARNING, HOWEVER, IN NO CASE SHALL ANY SIGN IMPEDE THE SIGHT LINE NOR INTERFERE WITH EITHER PEDESTRIAN AND/OR VEHICULAR TRAFFIC.

SPECIALTY SIGNS:

• SITE-MADE SIGNS: 'BLANKS' ARE TO HAND LETTERED ON SITE WITH EXTRA LARGE WATER PROOF PERMANENT FELT TIP MARKERS AND ARE TO BE WIRED TO BARRELS AND POSTED AS DIRECTED BY THE ENGINEER. THESE SIGNS ARE ONLY TO BE USED FOR MESSAGES WHICH ARE SITE SPECIFIC. AFTER EACH USE THE SIGN FIELD IS TO BE CLEANED WITH A SOLVENT AND PLACED AT THE READY.



L'ORANGE FIELD LORANGE FIELD BLACK BORDER


ROAD

CLOSED

ROAD UNDER REPAIR

USE AT YOUR OWN RISK |

2 @ 3/8" DRILLED HOLE



DRUM REQUIREMENTS: 'RC' & 'D' TYPE (SEE ACCOMPANYING NOTES REGARDING THESE DEVICES)

STANDARD TYPE ARE TO COMPLY WITH BOTH THE FOLLOWING DIRECTIVES AND

THEY ARE TO BE PLASTIC DRUMS, COMPLYING WITH M.U.T.D. AND EQUIPPED WITH OPERATING TYPE 'C' FLASHERS.

. DRUMS ARE TO BE U.V. RESISTANT, LOW DENSITY, IMPACT RESISTANT POLYETHYLENE.

O THE WRITTEN CONTRACT SPECIFICATIONS:

STANDARD (LOCUS NOT SHOWN. QUANTITY & LOCATIONS AS REQUIRED)

IN ADDITION TO THE FOLLOWING SPECIAL INSTRUCTIONS:

· DRUMS ARE TO BE ESTABLISHED FOR EACH PHASE AT EACH INTERSECTION PER TI THE DESIGNATED INTERSECTIONS FOR THE ENTIRE TERM OF THE PHASE BUT ARE TO BE LEFT 'AT THE READY' FOR IMMEDIATE ACCESS AND USE.

THE REMOVABLE BOTTOMS OF SUCH DRUMS ARE TO BE PERMANENTLY
ATTACHED TO THE DRUM ITSELF SUCH THAT THE BASE WILL NOT SEPARATE FROM THE DRUM
WHEN IT IS DRAGGED BUT YET WILL BREAK FREE IF HIT. FASTENERS ARE TO BE LIGHT DUTY. 'TIRE TYPE' WEIGHTS MAY BE USED IN LIEU OF FASTENED BOTTOMS.

· DRUMS ARE TO BE MOVED INTO AND OFF OF THE ROADWAY AS NECESSARY AND/OR AS DIRECTED, WHILE FULL SITE REMOVAL WILL BE AT THE DISCRETION OF THE ENGINEER.

ONE SIGN IS TO BE PERMANENTLY FASTENED TO THE DRUM.

• SIGNS ARE TO BE ATTACHED TO THE DRUM WITH 3/8" HEAVY DUTY NUT, BOLT, AND FENDER WASHER FASTENERS WITH A MINIMUM OF FOUR EQUALLY SPACED FASTENERS PER SIGN.

• THE CONTRACTOR IS SOLELY RESPONSIBLE FOR ESTABLISHING DAILY DETOURS TO THE SATISFACTION OF THE ENGINEER.

WATERTOWN MASS PIKE PROJECT ZONE LOCATION OF PROJECT ZONE

N84 - 38907 SHEET 1 OF 3

PROTECTIVE MEANS

" X 4" X 8' RECYCLED 'TREX' PLASTIC

MANUFACTURED PVC SAFETY FENCE WITH 'CABLE' TIES

ADEQUATELY TENSIONED METAL BANDS WITH CRIMP CLIPS

(MINIMUM OF THREE BANDS PER TREE)

HEAVY DUTY NYLON CINCH ('CABLE') TIES

(MINIMUM OF 9 @ 1' ON CENTER)

FITTED 'SURROUND' OF SDR35 PVC PIPE SECTIONS

