

**CITY OF NEWTON, MASSACHUSETTS
PURCHASING DEPARTMENT
COMPARISON OF BIDS**

INVITATION #13-09

Replacement of a Portion of the Newtonville Ave 12" Sewer & 6" Underdrain (Harvard St. to Westerly)

**Bid Opening: August 2, 2012 - 10:30 AM
Public Works/Engineering - Lou Taverna**

Bidders

**Replacement of a Portion of the Newtonville Ave 12" Sewer & 6" Underdrain (Harvard St. to
Westerly)**

Aqua Line Utility
\$119,989.00

Award Recommended To:

Chief Procurement Officer

Date

Department Head

Date

Mayor or his designee

Date

NOTES REGARDING BID
Total corrected by Excel

Bidders	QTY	Aqua Line Utility	
ITEM DESCRIPTION & BID PRICE		Unit Price	Annual
1 - MOBILIZATION (LAYOUT SERVICES, VIDEO FILE, NOTIFICATIONS, MEETINGS, ETC.)	1	\$10,000.00	\$10,000.00
2 - MANUFACTURED SILT SACK FOR CATCHBASIN SEDIMENTATION CONTROL	6	\$100.00	\$600.00
2.1 - TREE PROTECTION	5	\$1.00	\$5.00
3 -SAWCUTTING OF PAVEMENT	450	\$4.00	\$1,800.00
4 -SEWER & UNDERDRAIN BYPASS SYSTEM(S) (INCLUSIVE OF 'SILENT-PAC' PUMP)	1	\$5,000.00	\$5,000.00
5 - GENERAL EXCAVATION & DISPOSAL OF MATERIAL(S)			
6 - EXPLORATORY EXCAVATION	10	\$1.00	\$10.00
7 - EXCAVATION & DISPOSAL OF UNSUITABLE SOIL MATERIAL (INCLUSIVE OF EXTRA-DEPTH WORK)	50	\$1.00	\$50.00
8 - EXCAVATION & DISPOSAL OF ROCK	1	\$1.00	\$1.00
9 - SAND FOR THE BEDDING OF PIPES & FITTINGS (AS DIRECTED)	5	\$1.00	\$5.00
10 - FURNISH & PLACE ¾" FRACTURED CRUSHED STONE (PRIMARILY FOR PIPE BEDDING)	175	\$20.00	\$3,500.00
11 - GRAVEL FURNISHED FROM OUTSIDE THE SITE (FOR GENERAL USE)	20	\$15.00	\$300.00
12 - DENSE GRADED CRUSHED STONE .	20	\$15.00	\$300.00
13 - TYPE I-E CONTROLLED DENSITY FILL ('FAST SET' & EXCAVATABLE) (AS DIRECTED)	5	\$110.00	\$550.00
14 - FURNISHING,TRENCHING, LAYING 12" SDR 35 PVC SEWER PIPE	220	\$225.00	\$49,500.00
15 - FURNISHING,TRENCHING, LAYING 6" SDR 35 PVC SEWER PIPE FOR SERVICE CONNECTIONS AND UNDERDRAIN	280	\$60.00	\$16,800.00
16 - FURNISH & INSTALL - 12" x 6" SDR 35 PVC TEE-WYE	2	\$250.00	\$500.00
17 - FURNISH & INSTALL 6" x 6" SDR 35 PVC 45 DEGREE BEND	8	\$250.00	\$2,000.00
18 - FURNISH & INSTALL 6"x 6" SDR 35 PVC 90 DEGREE LONG	6	\$250.00	\$1,500.00
19 - PRECAST CONCRETE SEWER MANHOLE (EXCLUDING COVER & FRAME)	10	\$250.00	\$2,500.00
20 - 'STRONG-BACK' FLEXIBLE COUPLING @ 5" V.C. PIPE x 6" SDR 35 P.V.C. PIPE	2	\$100.00	\$200.00
21 - 'STRONG-BACK' FLEXIBLE COUPLING @ 6" V.C. PIPE x 6" SDR 35 P.V.C. PIPE	2	\$100.00	\$200.00
22 - 'STRONG-BACK' FLEXIBLE COUPLING @ 12" V.C. PIPE x 12" SDR 35 PVC PIPE	1	\$100.00	\$100.00
23 - FURNISH, TRENCH & LAY 10" DUCTILE IRON DRAIN PIPE (CLASS 52)	20	\$1.00	\$20.00
24 - FURNISH & INSTALL A MANHOLE COVER & FRAME	1	\$1,000.00	\$1,000.00
25 - ADJUST A PRE-EXISTING UTILITY CASTING (EXCLUDING GATE BOXES)	1	\$150.00	\$150.00
26 - 1" TYPE-K COPPER WATER SERVICE PIPE	30	\$1.00	\$30.00
27 - 1" CORPORATION COCK	1	\$1.00	\$1.00
28 - 1" CURB STOP WITH BOX	1	\$1.00	\$1.00
29 - NOMINAL 1" - 1 ½" COUPLING FOR WATER SERVICE PIPE	1	\$1.00	\$1.00
30 - DUST CONTROL (CHEMICAL TREATMENT)	500	\$1.00	\$500.00
31 - 2" BITUMINOUS CONCRETE FOR TEMPORARY PATCH	30	\$100.00	\$3,000.00
32 - 4" TYPE I-1 BITUMINOUS CONCRETE FOR PERMANENT (PATCH) TRENCH RESURFACING (PLACED IN TWO COURSES)	60	\$100.00	\$6,000.00
33 - CEMENT CONCRETE WITH LAMPBLACK(@ 2 POUNDS / CY)FOR PANEL REPAIR	2	\$120.00	\$240.00
34 - LOAM BORDER & LAWN RESTORATION	5	\$25.00	\$125.00
35 - MATERIALS TESTING ALLOWANCE	1	\$500.00	
36 - MISCELLANEOUS WORK ALLOWANCE (ENGINEERS DISCRETION)	1	\$2,000.00	
37 - ALLOWANCE FOR THE PAYMENT OF POLICE OFFICERS (MONIES ARE PAID DIRECTLY THRU AN INTER-DEPARTMENTAL BILLING PROGRAM)	1	\$4,000.00	
38 - WARNING AND/OR SAFETY DEVICES FOR THE CONTROL OF CONSTRUCTION OPERATIONS	1	\$5,000.00	\$5,000.00
39 - FURNISH & MOUNT SAFETY & SPECIALTY SIGNBOARDS (INCLUDING THE POST SYSTEM	40	\$50.00	\$2,000.00
Total Base Bid		\$119,989.00	