

CITY OF NEWTON
Department of Public Works
ENGINEERING DIVISION

MEMORANDUM

To: Council Rick Lipof, Land Use Committee Chairman

From: John Daghlian, Associate City Engineer

Re: Special Permit – 2 - 4 Auburndale Avenue

Date: March 16, 2022

CC: Barney Heath, Director of Planning
Jennifer Caira, Deputy Director
Lou Taverna, PE City Engineer
Jennifer Breslough, Committee Clerk
Michael Gleba, Sr. Planner
Katie Whewell, Sr. Planner

In reference to the above site, I have the following comments for a plan entitled:

Certified Plot Plan
Showing Proposed Conditions Located at 2-4 Auburndale Avenue
Prepared by: Boston Survey Inc.
Dated: 2/2/2022

Executive Summary:

This permit entails an attached new dwelling unit onto the existing two-family dwelling on the rear portion of the house. The site has approximately 80 feet of frontage along the north, and residential homes along the east, south and western property lines on a 11,702 square foot [0.26 acre] lot.

The site has a high point of elevation of 52-feet near Auburndale Avenue and slopes gently down towards the back yard to an existing retaining wall. At the time of this review no proposed drainage system is shown, the applicant will need to engage a professional engineer to design a stormwater collection and on-site infiltration system consistent with the City's Stormwater policy along with associated details of the system & an Operations & Maintenance Plan.

Based on a site visit there are no existing stormwater collection and infiltration systems. Additionally, a grading and landscape plan(s) will be needed.

Construction Management:

1. A construction management plan is needed for this project. At a minimum, it must address the following: staging site for construction materials and equipment, parking for construction workers vehicles, phasing of the project with anticipated completion dates and milestones, safety precautions, emergency contact personnel of the general contractor. It shall also address anticipated dewatering during construction, site safety & stability, siltation & dust control and noise impact to abutters.
2. Stabilized driveway construction entrance(s) will be required for the duration of the construction which will provide a truck wash to prevent tracking of mud and silt onto City streets.
3. Catch basins within and downstream of the construction zone will be required to have siltation control installed for the duration of the project and must be identified on the site plan.

Drainage:

1. A Pre & Post Construction drainage analysis is required. All stormwater runoff from the site shall be captured on-site and infiltrated in accordance with the Massachusetts Department of Environmental Protection standards and the City of Newton Department of Public Works policy. This policy states that stormwater runoff shall be retained from the 100-year storm event of 8.78-iches over a 24-hour period and shall be infiltrated to the maximum practicable extent. Pre & Post watershed maps (at a proper scale that is legible) are required that delineate control points and limits of the sub-basins.
2. On-site soil evaluation is required to determine the seasonal high groundwater elevation, soil types and to identify any and all unsuitable soils (such as ledge, clay, peat, fill and others). On site soil testing that will include test pit(s) within 25 -feet of each proposed system and percolation test(s) must be schedule and witnessed by a representative of the Engineering Division. Soil logs shall be submitted on the site plan or drainage report and shall be certified by a Massachusetts Licensed Soil Evaluator and/or Professional Civil Engineer.

3. An Operations and Maintenance (O&M) plan for the long-term maintenance of the proposed stormwater management facilities needs to be drafted and submitted for review. Once approved the O&M must be adopted by the applicant/property owner, incorporated into the deeds; and recorded at the Middlesex Registry of Deeds. A copy of the recording instrument shall be submitted to the Engineering Division.
4. It is imperative to note that the ownership, operation, and maintenance of the proposed drainage system and all appurtenances including but not limited to the drywells, catch basins, trench drains, and pipe(s) are the sole responsibility of the property owner(s).

Environmental:

1. Has a 21E Investigation and report been performed on the site, if so, copies of the report should be submitted to the Newton Board of Health and Engineering Division.
2. Are there any existing underground oil or fuel tanks? Have they been removed, if they have been, evidence of the proper removal should be submitted to the Newton Fire Department and the Board of Health.

Sanitary Sewer & Domestic Water Service(s):

1. Depending upon any renovations to the existing dwelling the existing water service(s) maybe required to be updated if they are not copper water services. The sanitary sewer connection(s) need to be investigated to determine the integrity of pipe(s) to ensure no infiltration is occurring nor tree root intrusion.
2. Section 29-59, which states "A separate and independent building sewer shall be provided for every building on which construction begins after July 17, 1981."
3. The Fire Department may require a fire suppression system for this development, the applicant needs to verify with the NFD for this requirement.

General:

1. 5 Year Moratorium – if at time of construction the roadway is under a 5-year moratorium, the roadway must be milled and paved gutter-to-gutter for a distance of 25 feet in each direction from the outermost trenches.

2. All trench excavation shall comply with Massachusetts General Law Chapter 82A, Trench Excavation Safety Requirements, and OSHA Standards to protect the general public from unauthorized access to unattended trenches or excavations. Trench Excavation Permit is required prior to any construction. This applies to all trenches on public and private property. *This note shall be incorporated onto the final plans.*
3. All tree removal shall comply with the City's Tree Ordinance.
4. The contractor of record is responsible for contacting the Engineering Division and scheduling an appointment 48-hours prior to the date when the utilities will be made available for an inspection of water services, sewer services and drainage system installation. The utility in question shall be fully exposed for the Inspector to view, backfilling shall only take place when the City Engineer's Inspector has given their approval. *This note shall be incorporated onto the final plans.*
5. The applicant shall apply for a Building Permit with the Inspectional Services Department prior to ANY construction.
6. Before requesting a Certificate of Occupancy, an As Built plan shall be submitted to the Engineering Division in both digital and paper format. The plan shall show all utilities and final grades, any easements and improvements and limits of restoration. The plan shall include profiles of the various new utilities including but not limited to rim & invert elevations (City of Newton Datum), slopes of pipes, pipe materials, and swing ties from permanent building corners. The as built shall be stamped by both a Massachusetts Registered Professional Engineer and Registered Professional Land Surveyor. Once the as built plan is received the Engineering Division shall perform a final site inspection and then make a determination to issue a Certificate of Occupancy. *This note shall be incorporated onto the final plans.*
7. All site work including trench restoration, sidewalk, curb, apron, and loam border (where applicable) shall be completed before a Certificate of Occupancy is issued. *This note shall be incorporated onto the final plans.*
8. If any changes from the final approved design plan that are required due to unforeseen site conditions, the contractor of record shall contact the design engineer of record and submit revised design and stamped full scale plans for review and approval prior to continuing with construction.

9. The engineer of record shall add the following attestation to the plans when applying for a building permit:

I certify that the construction so shown was inspected prior to backfill and that all work conforms with the Approved Plan and meets or exceeds the City of Newton Construction Standards.

Signature

Note: If the plans are updated it is the responsibility of the applicant to provide all City Departments [ISD, Conservation Commission, Planning and Engineering] involved in the permitting and approval process with complete and consistent plans.

If you have any questions or concerns, please feel free to contact me at 617-796-1023.