The project remains on budget at the Design Development Phase

- Two full independent cost estimates were reconciled to within \$100 K
 (on a budget of \$26.2 M)
- The drawings, specifications and cost estimates were reviewed by:
 - ✓ Architect and Engineers
 - **✓** Owner's Project Manger
 - **✓** Construction Manager
 - √ Commissioning Agent
 - ✓ Newton Public Buildings
 - ✓ Design Review Committee
 - ✓ Newton Public Schools
 - ✓ Executive Committee
 - ✓ Angier Working Group



A comprehensive list of Value Engineering opportunities were identified

- No cuts to programs
- No impact on the energy efficiency
- No reduction in the quality, durability, or life expectancy of building components
- No significant changes to the layout or design of the school



Value Engineering, cont.

- Certain design elements and systems were more costly than on typical school projects and were adjusted accordingly
- Some redundant functionality or unnecessary systems capacity was eliminated
- Life cycle cost and payback periods were analyzed for all items which impacted operating expense
- The recommended VE list was unanimously approved by NPS, NPB, DRC, the Angier Working Group and the Executive Committee



Value Engineering Summary

Site

Building

Building Energy Efficiency

Interior Finishes

Exterior Materials

MEPFP

Subtotal DD Phase Budget Adjustment Items

\$73,571

\$454,415

\$172, 211

\$203,241

\$122,119

\$637,655

\$1,663,212



Angier Elementary School: Newton, MA		
Design Development Phase Value Engineering Summary		2/3/2014
SITE	\$	73,571
Simplify materials/detailing for trellis at front plaza, dimensions and function will not change: design target	\$	20,000
Substitute chainlink for PVC fence at abutter	\$	4,290
Delete redundant exterior stair at Gym ramp	\$	6,971
Shift some site benches to Alternates: Concrete benches at overhang, wood benches at cafeteria and bench at gym/plaza	\$	29,708
Reduce width of concrete pavement border at playground	\$	8,848
Relocate future charging station for electric cars closer to building, reduce conduit length	\$	1,609
Delete power and data to trellis at front plaza, not necessary for educational purposes	\$	2,145
BUILDING	\$	454,415
Use crushed foundations instead of imported material as structural fill	\$	6,435
Substitute concrete for stone below grade: not visible, no impact	\$	3,604
Increase gym width 16" for full length instead of center bump out, use continuous bench instead of bleachers	\$	57,739
Do not increase parapet height as proposed, leave it as designed at SD	\$	26,813
Reduce height of mechanical penthouse screenwall by 12", will still screen equipment from view	\$	12,773
Do not add light wells and clerestory, leave design as it was at SD	\$	91,876
Substitute 4 fixed for retractable back boards at gym	Ś	19,305
Delete upper window into gym from stair	\$	10,725
Substitute stock wood cubbies for proposed custom cubbies and simplify detailing	\$	91,967
Redesign and simplify classroom storage with sliding marker boards: design target	\$	125,000
Use manual overhead doors at servery and simplify instead of proposed electric doors	\$	8,178
	<u> </u>	
BUILDING ENERGY EFFICIENCY	\$	172,211
Do not increase spray foam wall insulation by 1" as was proposed: minimal impact on energy model	\$	23,798
Delete all exterior solar shading devices; minimal impact on energy model	\$	148,413
INTERIOR FINISHES	\$	203,241
Substitue linoleum for porcelain tile at first floor cafeteria and corridor	\$	68,785
Reduce area of rated glass in stairwells: design target	\$	100,000
Substitute standard (Armstrong) wood ceiling product for ipe wood	\$	6,571
Reduce painted wood ceiling trim by 50%	\$	13,406
Substitute painted hollow metal for factory pre-finished storefront framing	\$	14,479
EXTERIOR MATERIALS	\$	122,119
Substitute larger brick shapes (jumbo, economy, panel) for small area of remaining modular (standard) brick	\$	19,833
Substitute ground faced masonry for brick at entire gym	\$	23,166
Substitute acoustic tile for ipe wood ceiling at exterior overhangs	\$	54,968
Delete window safety film at ground floor admin area	\$	24,153
MEPFP	\$	637,655
Make HVAC Controls, Security System, PA System and IPTV System open bid rather than proprietary	\$	238,095
Delete radiant ceiling panels and piping: this would offer no real benefit for operations	\$	150,150
HVAC system engineering simplification: target design savings	\$	125,000
Down size Diesel Generator (& distribution) to 75 KW: appropriate for schools of this size, will carry all desired load	\$	107,250
Reduce the number of data drops from 6 to 4 in each classroom: coverage will remain appropriate	\$	17,160
· · · · · · · · · · · · · · · · · · ·		

ANGIER ELEMENTARY SCHOOL - NEWTON, MA

2/10/2014

DESIGN DEVELOPMENT TOTAL PROJECT BUDGET SUMMARY

	M	MSBA BUDGET	
Feasibility Study (currently funded)	\$	717,659	
Administration (includes OPM fees for DD through Closeout)	\$	970,000	
Architecture and Engineering (DD through Closeout)	\$	2,491,100	
CM at Risk Pre-Construction Services (DD through Closeout)	\$	123,600	
Construction Costs	\$	26,231,698	
Off-Site Improvements (MSBA Excluded)	\$	3,948,259	
Miscellaneous Project Costs (Utility Fees, Testing, Moving)	\$	230,000	
Furnishings and Educational Technology	\$	1,116,000	
Potentially Eligible Construction Contingency	\$	1,311,474	
Potentially Eligible Owner's (soft cost) Contingency	\$	360,210	
Total Project Budget	\$	37,500,000	
Key Project Metrics			
Design Enrollment (Planned Number of Students)		465	
Total Building Gross Floor Area (Square Feet)		74,960	
DD Estimated Construction Costs (WT Rich, CM)	\$	26,222,990	
DD Construction Costs: Favorable Variance to Budget	\$	8,708	
Note: Estimate includes recommended value engineering adjustments, see attached			
Budgeted Construction Cost per Gross Square Foot	\$	349.94	
Estimated Construction Cost per Gross Square Foot	\$	349.83	