

**CITY OF NEWTON**  
**ENGINEERING DIVISION**

MEMORANDUM

To: Alderman Ted Hess-Mahan, Land Use Committee Chairman

From: John Daghlian, Associate City Engineer

Re: Special Permit – #75-77 Auburn Street

Date: July 24, 2013

CC: Lou Taverna, PE City Engineer  
Linda Finucane, Associate City Clerk  
Alexandria Ananth, Chief Planner  
Katy Holmes, Sr. Planner  
Stephen Pantalone, Planner

---

In reference to the above site, I have the following comments for a plan entitled:

*Topographic Site Plan*  
*Newton, MA*  
*Showing Proposed Conditions at*  
*#75 & 77 Auburn Street*  
*Prepared by: VTP Associates Inc.*  
*Dated: May 28, 2013*  
*Revised: July 15, 2013*

*Executive Summary:*

This project has five residential units on a 31,437 square foot lot. The proposed drive of 16' does not meet the standard 18' requirement of the Fire Department for access.

A drainage study was submitted, however it is based on assumed infiltration rates, actual on site soil testing is required. Since there are three independent systems; 3- test pits and 3- percolation teats are required before the system design can be approved.

Construction Management:

1. A construction management plan is needed for this project. At a minimum, it must address the following: staging site for construction equipment, construction materials, parking of construction worker's vehicles, phasing of the project with anticipated completion dates and milestones, safety precautions, emergency contact personnel of contractor. It shall also address any anticipated dewatering during construction, site safety & stability, and impact to abutting properties.
2. Stabilized driveway entrances are needed during construction that will provide a tire wash and mud removal to ensure City streets are kept clean.

Drainage:

1. An Operations and Maintenance (O&M) plan for Stormwater Management Facilities needs to be drafted and submitted for review. Once approved the O&M must be adopted by applicant, incorporated into the deeds; and recorded at the Middlesex Registry of Deeds. A copy of the recording instrument shall be submitted to the Engineering Division.
2. It is imperative to note that the ownership, operation, and maintenance of the proposed drainage system and all appurtenances including but not limited to the drywells, catch basins, and pipes are the sole responsibility of the Homeowners Association.
3. Based on the size of the proposed system, a minimum of \$10,000.00 should be funded as seed money by the developer in an account held by the Homeowners Association. This fund will be utilized so that proper inspections, maintenance and cleaning of the drainage system and driveway are performed biannually.
4. Since the proposed systems are less than 10-feet from the property line, impervious barriers are needed along each system.
5. There is an error in the hydrocad report where the routing diagram should be

Environmental:

1. Has a 21E investigation & report been performed on the site, if so copies of the report should be submitted the Newton Board of Health and the Engineering Division.

2. Are there any existing underground oil or fuel tanks, are they to be removed, if they have been evidence should be submitted to the Newton Fire Department, and Newton Board of Health.

Sewer:

1. The proposed service connection of 6" is inadequate and shall be enlarged to an 8" collector pipe, from which the 6" service connections can be installed.
2. The existing water & sewer services to the building shall be cut and capped at the main and be completely removed from the site and properly back filled. The Engineering Division must inspect this work; failure to having this work inspected may result in the delay of issuance of the Utility Connection Permit.
3. With the exception of natural gas service(s), all utility trenches with the right of way shall be backfilled with Control Density Fill (CDF) Excavatable Type I-E, detail is available in the city of Newton Construction Standards Detail Book.
4. All new sewer service and/or structures shall be pressure tested or video taped after final installation is complete. Method of final inspection shall be determined solely by the construction inspector from the City Engineering Division. All sewer manholes shall be vacuum tested in accordance to the City's Construction Standards & Specifications. The sewer service will NOT be accepted until one of the two methods stated above is completed. All testing MUST be witnessed by a representative of the Engineering Division. A Certificate of Occupancy will not be recommended until this test is completed and a written report is received by the City Engineer. ***This note must be added to the final approved plans.***
5. All sewer manholes shall be vacuum tested in accordance to the City's Construction Standards & Specifications. The sewer service will NOT be accepted until one of the two methods stated above is completed. All testing MUST be witnessed by a representative of the Engineering Division. A Certificate of Occupancy will not be recommended until this test is completed and a written report is received by the City Engineer.

Water:

1. Fire flow testing is required for the proposed fire suppression system. The applicant must coordinate this test with both the Newton Fire Department and the Utilities Division; representatives of each department shall witness the testing, test results shall be submitted in a write report. Hydraulic calculation shall be submitted to the Newton Fire Department for approval.

2. For water quality issues a fire hydrant will be required at the end of the proposed water main. This hydrant will be utilized for flushing out the main as required.
3. All water connections shall be chlorinated & pressure tested in accordance to AWWA and the City of Newton Construction Standards and Specifications prior to opening the connection to existing pipes.
4. Approval of the final configuration of the water service(s) shall be determined by the Utilities Division, the engineer of record should submit a plan to the Director of Utilities for approval

General:

1. As of January 1, 2009, all trench excavation contractors shall comply with Massachusetts General Laws Chapter 82A, Trench Excavation Safety Requirements, to protect the general public from unauthorized access to unattended trenches. Trench Excavation Permit required. This applies to all trenches on public and private property. *This note shall be incorporated onto the plans*
2. All tree removal shall comply with the City's Tree Ordinance.
3. The contractor is responsible for contacting the Engineering Division and scheduling an appointment 48 hours prior to the date when the utilities will be made available for an inspection of water services, sewer service, and drainage system installation. The utility is question shall be fully exposed for the inspector to view; backfilling shall only take place when the City's Inspector has given their approval. *This note should be incorporated onto the plans*
4. The applicant will have to apply for Street Opening, Sidewalk Crossing, and Utilities Connecting permits with the Department of Public Works prior to any construction. *This note must be incorporated onto the site plan.*
5. The applicant will have to apply for a Building Permits with the Department of Inspectional Service prior to any construction.
6. Prior to Occupancy Permit being issued, an As-Built Plan shall be submitted to the Engineering Division in both digital format and in hard copy. The plan should show all utilities and final grades, any easements and final grading. *This note must be incorporated onto the site plan.*
7. If a Certificate of Occupancy is requested prior to all site work being completed. *This note must be incorporated onto the site plan.*

Note: If the plans are updated it is the responsibility of the Applicant to provide all City Departments [Conservation Commission, ISD, and Engineering] involved in the permitting and approval process with complete and consistent plans.

If you have any questions or concerns please feel free to contact me @ 617-796-1023.