

## Consolidated List of Councilor Questions and Responses

### Councilor Susan S. Albright

1. Have you road tested your drive times at rush hour - actually by driving the route?

*Response:*

*128 Business Council has road tested each and every stop-to-stop timing several times throughout the route planning process, beginning in 2017 and then again, each time a major change has been made to the planned routing. One of 128BC's shuttle vendors also road tested the routes on our behalf using an actual shuttle in order to test the differences in timing between using a standard-sized car and a 32-passenger bus. 128 Business Council also compared (and re-compared at approximately 6-month intervals) their results against Google's traffic data, as well as their 32 years of operations experience more generally.*

*The schedule tables shown on p. 2, p. 4, and p. 6 of the slides from Monica G. Tibbits-Nutt's statement before the LUC on 4/9/19 (attached – Exhibit G) reflect 128 Business Council's most up-to-date assessment of all of this data. We therefore consider these schedules to be accurate and achievable based upon today's traffic conditions. However, all routes will be retimed in the months leading up to commencement of shuttle service.*

2. Newton is about to discuss city and citizens Climate Action Plans and we are trying to reduce the greenhouse gas emissions. The shuttles are positive and negative. Positive because it is ride share negative because it operates on gas. To be good citizens you should try to use electric vehicles. Can you?

*Response:*

*We agree. Unfortunately, electric buses are not viable for most shuttle systems at this time. 32-passenger buses such as the ones we will employ must be charged at more frequent intervals than must an electric car and would require charging at irregular intervals when sitting in dense traffic. The Commonwealth currently lacks the electric charging infrastructure to use electric vehicles on longer trips (such as the Boston and Cambridge Express routes), and frequent charging would also reduce service frequency and prevent schedule reliability on the shorter Newton Local route. It is our hope that alternate fuel vehicles will become more viable in time. 128 Business Council is well-apprised of state and national standards and projections in this regard and will make fleet upgrade recommendations as they become feasible.*

3. Have you thought about on-demand local service on Needham St that would at least go to Newton Center and back? You can use those wonderful 8-seater electric golf carts like the ones in Key Biscayne (and I guess also in Aspen).

*Response:*

*We believe that there are many options to expand shared transit service, and we are particularly interested in the opportunity to expand the Newton circulator route. However, we must first establish the success of our three core routes before exploring other options.*

*On-demand routing was actually something we discussed in depth at the very beginning of the planning phase. However, 128 Business Council has recommended (and we have followed this*

*recommendation) that on-demand models be explored as an option for future expansion, rather than as a backbone of the service. In terms of building daily ridership, the problem with on-demand routing is that, from a daily commute (rather than single trip) perspective, it is not predictable. Shuttle availability, pick-up times, and on-board duration would vary from day to day, making on-demand routing an unreliable solution for riders who are commuting to and from work, or for other repetitive, time-sensitive trips. More in general, 128BC has yet to see a model anywhere in the nation for an on-demand public transportation service that has proven itself successful in terms of financial viability or in terms of meeting rider needs.*

*That said, 128BC has been actively exploring options for using on-demand solutions for expanding or altering the schedule for off-peak and less frequent trips.*

4. With respect to the parking garage - can you use a system like the one at the Natick mall which not only tells you what level has the spaces but by red and green lights tells you where the vacant spaces are. It feels like - if you run at full capacity often because of reducing parking - a system of lights could really help - and make it more believable that it could work.

*Response:*

*Technology such as the system in the Natick Mall has changed the dynamics of garage parking operations, significantly improving efficiency and customer convenience. Smart garage technology will continue to evolve rapidly with tracking applications, vehicle integration, and data analytics. NND will employ the latest technology, which will be more effective than current systems being used by the Natick Mall.*

5. Beta mentioned certain tracker (which i guess was mentioned by Leon based on where this appears in my notes). Have you considered using this tracker? why? why not?

*Response:*

*We are not aware of a specific tracker recommended by Beta. However, Beta made recommendations for signal coordination and signal priority capability along the Needham Street corridor in conjunction with the MassDOT improvements. These improvements will be coordinated with the City and funded through a mitigation fund established for NND.*

6. have you studied how waze would affect traffic in the neighborhoods around needham st? Can we do anything to help this problem - if it is a problem?

*Response:*

*Commuter cut-through traffic has been a challenge to Needham Street and other feeder roads to Route 9 long before the use of GPS traffic tracking software. The problem will continue to get worse without greater reliance on alternate transit modes. This is what NND is committed to accomplishing with a concrete goal of reducing single occupancy vehicle trip generation. NND's traffic impact and access study has captured peak traffic volumes that reflect technology-aided traffic behavior, and these results have been incorporated into our planning and mitigation.*

7. What examples can you provide that ridership will appear - this is a subset of another question i had - will you let people from upper falls use the shuttle?

**Response:**

*Yes, the shuttles will be fully open to the public. Members of Upper Falls, and in fact, all members of the public, are invited and encouraged to use the shuttles and take advantage of the convenience. We expect that they will, particularly the environmentally conscious millennials and the empty nesters.*

*As for examples that we can point to in order to confirm that ridership will appear: As Monica Tibbits-Nutt stated: "There is no other system like this in the United States. We have looked, we have asked, we have called. No one has built anything of this scale." As such, there are no examples to point to as a true comparison to the NND Shuttle System. That said, 128 Business Council has 32 years of experience building ridership among suburban populations with high rates of single-occupancy vehicle dependency. They currently have successful routes running throughout Waltham, Bedford, Lexington, and Needham. However, these routes are different from what is being proposed here for two major reasons:*

*(1) Almost all of 128BC's current public routes are either built primarily for a work commuter population or primarily for a residential population. This means that they've had to build ridership without guaranteeing the possibility of car-free living, without the ability to have the shuttles 'multitask' across trip types, and without the ability to expand service beyond extended commuting hours. The fact that NND's Shuttle System will operate out of a mixed-use site, provide two-directional trips, and continue service beyond normal commuting hours means that building ridership should actually be easier than it has been with 128BC's current shuttles—all of which have been successful for the length of their operation.*

*(2) All of 128BC's current public routes are shared routes co-financed by a group of organizations who "opt in" each year. As a result, the specific routing may vary from year to year as participants join or drop out. In contrast, the shuttle system proposed here is the result of a major commitment by one entity in perpetuity—meaning that public riders can count on routes only changing thanks to established rider need (or an established lack thereof). Again, this means that building (and maintaining) ridership should be easier than it has been with 128BC's preexisting shuttles.*

*Moreover, the fare structure is cheaper than parking in Boston/Cambridge and cheaper-to-comparable to the MBTA service into Boston/Cambridge, yet offers much more comfortable and amenitized service.*

8. What percent do you think will both live and work on the same site? Leon's presentation had a large number - was that correct?

**Response:**

*Mr. Schwartz's information was dated, based upon the prior programming of NND, and error filled. It is difficult to accurately predict the number of NND residents that will also work at NND. However, we estimate that 20% to 25% of residents will work in the office building, in co-working space, or the stores and restaurants. This will include Larry Gottesdiener and other Northland personnel. This estimate, though, is not scientific.*

9. Leon's chart on the number of cars by category added up to more than 1550 spaces - which was explained by shared parking which i get across office and retail. What about the number of cars across residential and office/retail - is 1550 the right number? Should it be 50 cars bigger? Happy to hear that 1550 is the right number i just need a better explanation.

**Response:**

*In order to bridge the divide between parking minimalist and parking maximalists, we have developed a creative response that should appeal to both. The revision will reduce striped spaces to 1450. This will be the parking count in the ordinary course. That reduction will also free up a 200-space valet pod which will create the excess capacity to accommodate the peak holiday season. This plan is responsive to the marketplace (peak demand) and our commitment to reducing single occupancy vehicles (lowered number of parking spaces).*

*It should be noted that Mr. Schwartz's lay parking analysis was inaccurate, ignored the concept of shared parking, and inflated the number of employees on-site. Beta, on the other hand conducted a professional analysis and concluded that Northland got the parking just about right. However, the complementary nature of the uses allows extra daytime office parking to spill over into vacated residential parking during the weekday and retail parking to spill over into vacated office parking in the evenings and on weekends. Shared parking is a widely accepted concept in the real estate industry and our plan is aligned with generally accepted metrics endorsed by national trade organizations such as the Urban Land Institute and the Institute of Transportation Engineers.*

10. One more on the parking garage - I know that in December you will be above planned occupancy - but how often will you be close to maximum capacity in an average day/month?

**Response:**

*Parking demand will be greater during the weekday than on the weekend. At peak times during the week, the garage will operate at 97% to 98% occupancy. On weekends, peak demand will reach 86% to 88%. The additional parking program referenced above will provide expanded capacity to efficiently manage event-related or seasonal surges.*

Councilor Marc C. Laredo

1. What is the source of the base numbers for current traffic counts on Needham Street being used by the developer and when and how the information was gathered?

**Response:**

*The traffic counts were conducted in May 2017 and October 2017. The May 2017 traffic counts were conducted for the Functional Design Report for MassDOT's reconstruction project of Needham Street and were used by NND to be consistent with the roadway reconstruction project. Locations not included in the roadway reconstruction project were counted in October 2017. These counts are consistent with the MassDOT TIA guidelines. All turning movement counts were conducted with cameras and all daily automatic traffic recorder (ATR) counts were conducted with tubes across the roadway. The base counts for all locations were included in the Appendix to the TIA filed in October 2018.*

2. Do the current base numbers being used by the developer include traffic counts for a fully occupied Marshall's plaza and Piano building? If so, what are the actual traffic counts today given that much of the site is unoccupied?

**Response:**

*The traffic counts were conducted in May and October 2017, at the time Northland filed an Environmental Notification Form for this project under MEPA and reflect the occupancy rates at those times. Marshalls Plaza was at 92% occupancy at the time of the traffic counts, while the office space was mostly empty, and the former manufacturing space was completely empty.*

*Traffic counts have not been taken since May and October 2017. However, measuring traffic at this time does not accurately characterize the traffic impact of NND, as space has been purposely left vacant because of our special permit application and could be re-tenanted at any time if we elected. The future "No Build" scenario in the traffic impact study assumed the existing office space would be fully occupied in the future without the project and therefore the "No Build" analyses includes traffic generated by the office. As of April 2019, Marshall Plaza remains 87% occupied.*

3. Using current traffic counts as they exist today with the site essentially empty, what will the total traffic increase be if the project is fully built as proposed?

**Response:**

*The projected weekday morning peak hour volume would be 396 vehicles, the weekday evening peak hour volume would be 487 vehicles and the Saturday midday peak hour volume would be 558 vehicles. This data is presented in Table 8 of VHB's March 28 Expanded Revised Building Program Traffic Generation Memorandum, which shows the projected peak hour traffic generation under the "Robust Shuttle" mode share without existing vehicle trips.*

4. Have there been traffic increases due to the opening of the grocery store, the Nexus site, and any other recent developments and, if so, have those numbers been included in the current base numbers the developer is using? If not, why not and what are those numbers?

**Response:**

*The Planning Department has not made us aware of any post development traffic assessment data for the Nexus development, including the grocery store. Traffic projections for recently completed projects were incorporated into the future No-Build and Build traffic assessments for NND in accordance with standard MassDOT TIA guidelines.*

5. Have the addition of the buses been included in traffic counts as projected on Needham Street? If so, how are the buses being counted – as the equivalent of a single car or multiple cars (and if the latter, how many) and why is that particular standard being used?

**Response:**

*While not called out specifically, traffic projections for the project were based on standard methodology includes all vehicle types, so the expected activity is essentially covered. As outlined in the 128 BC shuttle plan, the peak hour of operations will see 4 shuttles entering the site and 5 shuttles leaving the site during the weekday morning peak hour. The same is true during the weekday evening peak hour period where 4 shuttles will enter and 5 will exit over the course of the peak hour. This amount of activity is not significant. No adjustments were made or included in the traffic projections that replace multiple vehicles with buses.*

6. What are the planning department's specific proposals for remedies in a Council order if the developer's projections on bus usage are incorrect and there is more traffic than anticipated?

**Response:**

*[Note – this is a question directed to the Planning Department to respond. The Planning Department's specific proposal outlined in its April 5<sup>th</sup> memo is to require Northland to return to the City Council to amend the special permit and establish alternative mitigation strategies if it has not met the performance goal for two consecutive years and there continues to be no improvement.]*

*Northland is committed to doing what is necessary to achieve the performance goal recommended by the Planning Staff, if actual vehicle trips exceed the goal for a sustained period, then further measures would be implemented to reduce vehicle trips, including: additional MBTA and shuttle incentives; modification of shuttle routes, schedule, or capacity; improved marketing and community awareness; or introduction of additional transit options.*

7. How does the planning department envision that post-construction travel to and from the site be determined (I very much doubt that there could be any survey that tracks the travel practices of all residents)?

**Response:**

*Post-development traffic monitoring will be conducted annually that will include formal traffic counts at each site driveway during peak hours. Additional data will be collected from shuttle*

*riders, residents and office workers through surveys. While the surveys may not provide exact travel data of everyone within NND, they will be effective in identifying transit use patterns and preferences.*

8. Is the developer willing to commit to the bus service at the proposed levels in perpetuity and, if so, how will pricing be determined? If there is not that commitment, what assurances will we have about alternate transit in the future and how will that be enforced?

*Response:*

*Northland will comply with the performance goal recommended by the Planning Department in perpetuity. The goal can be achieved “regardless of what tools, systems and/or approaches implemented by the petitioner”, as the Department stated in its April 5 memo. While the shuttle is an integral part of the plan today, the tools, including the shuttle, may shift in the future as transportation trends change. “The transportation field is rapidly changing and evolving and there will likely be more tools available as this project progresses” according to the Planning Department memo.*

*Regarding shuttle fares, please see p. 9 of the slides from Monica G. Tibbits-Nutt’s statement before the LUC on 4/9/19 (attached - Exhibit G). If the program were put into effect today, the rates would be \$2.50 per ride on the Newton Local (serving Newton Highlands and Newtonville) and \$7.00 per ride on the Boston and Cambridge express routes, which is competitive with MBTA services while providing a superior rider experience (greater predictability, comfortable seats, WIFI, real-time shuttle tracking, in-app pay options, etc.). The pricing will change from time to time to reflect changes in the market and to stay on-scale with MBTA service.*

9. What specific measures is the planning department proposing to ensure that if parking is limited on site it does not spill over onto neighboring streets?

*Response:*

*[Note: This is a question directed to the Planning Department to respond]*

*Northland is not aware of any specific proposals for parking restrictions on neighborhood streets. We will put in place a provision in residential leases to restrict parking on neighborhood streets and void incentives for violators. However, the most effective means of controlling spill-over parking is to impose a neighborhood resident parking sticker program for the time period outside the November 15<sup>th</sup> to April 15<sup>th</sup> winter parking ban.*

10. Have any shadow studies been done on the proposed buildings on site?

*Response:*

*An updated shadow study is shown on Exhibit E. Based on the revised program of NND and the fact that the height is concentrated in the center of the site and 232 feet from the west property line, no shadows are cast on any buildings in the Upper Falls beyond 9:00 am on the winter solstice, the most impactful period.*

11. Why is having 40% of residents using alternative transit an acceptable number to the planning department?

**Response:**

*Transportation is changing and there are underlying trends shifting away from traditional commuting relating to the target cohorts for NND, millennials, empty-nesters and seniors. These include greater corporate opportunities for remote officing and working from home, more prevalent use of alternate transit modes as part of a growing green consciousness, and a greater desire for live/work/play experiences.*

12. What are the specific reasons that the planning department is willing to rely on the transit-oriented development calculations in assessing this project when it is not near transit? Is it solely the proposed bus service or are there other factors that are being relied upon? Has any other project in Newton or elsewhere in eastern Massachusetts applied transit-oriented standards in this manner?

**Response:**

*[Note: this is a question directed to the Planning department to respond]*

*The breadth of service of the NND Shuttle System will provide an equal or better-quality TOD experience than typical suburban TOD developments. Unlike other developments that may rely on a single mode of public transit, NND will offer both door-to-workplace transit service and 20-minute frequency service to both commuter rail and T service. For instance, The NND Shuttle System will provide transit to downtown Boston, The Seaport, Kendall Square and Central Square within 60 minutes or less during peak commuting times and will also provide convenient and timely transit access for commuters traveling to the LMA, Boston Landing, Fenway and Back Bay.*

*Several factors enable NND to achieve a higher concentration of alternate transit use. The mix of residential, retail and office within NND and the immediate neighborhood allows greater reliance on pedestrian and bike travel, supported by the connections to Greenway, a network of bike paths, and on-site bike storage and bike-share. The shuttle program will provide reliable door-to-workplace commuting options as well as 20-minute frequency access to the T system.*

13. If the planning department will be doing post-construction review and enforcement, who will be doing that work and what will be the cost to the city?

**Response:**

*The post development monitoring and reporting will be provided by a qualified engineering firm engaged and paid for by Northland. The City will bear no cost.*

**Councilor Alison M. Leary**

1. Can we include other conveniences, like making it easy to pay with apps and integrating your payment options with the T's automated fare collection system upgrades that are coming soon?

***Response:***

*The NND Shuttle System will offer a wide variety of conveniences, both in keeping with 128 Business Council's current fleet and surpassing it. This will include mobile in-app payment options, real-time shuttle tracking on desktop and mobile, real-time shuttle alerts, comfortable seating, in-seat mobile device charging, reading-optimized lighting, and WIFI. Based upon Ms. Tibbits-Nutt's deep experience in the field and resulting from her combined duties at 128 Business Council, the MBTA, and MassDOT, the shuttle system is proactively designed to "fill in the gaps" and complement MBTA service rather than compete with it.*

*As for AFC 2.0, specifically: The completion timeline for this project currently extends into 2021, but 128 Business Council will be ready to integrate their operations with these and other MBTA technological upgrades as soon as those options become available.*

2. One way to attract ridership is to reduce fares. Would that be something that could be considered?

***Response:***

*If necessary, yes, we would reduce fares to ensure robust ridership.*

*However, the fare structure recommended by 128 Business Council and accepted by Northland (see p. 9 of the slides from Monica G. Tibbits-Nutt's statement before the LUC on 4/9/19, attached Exhibit G) are competitive with current MBTA fares, while still allowing for a superior rider experience (greater predictability, comfortable seats, WIFI, real-time shuttle tracking, in-app pay options, etc.). As a point of reference, 128 Business Council has studied the effects of fare raises on ridership and has not found that measure increases reduced shuttle participation among most populations, as long as the fares are within range of other public transportation options. That said, shuttle riders and non-riders alike will be surveyed regularly as part of the Project's metrics commitment, and the effects and perceptions of shuttle fares can be included in this surveying. If fares emerge as a barrier to ridership, they will absolutely be adjusted. We will also provide financial incentives that will further reduce transit costs for riders, including multi-ride shuttle passes and T discounts.*

3. Could we consider incentivizing residents who choose not to pay for a parking spot a reduced shuttle service fare and/or offer free shuttle service for the first year?

***Response:***

*Residents that commit to living car-free at NND will be offered a free annual T pass and a shuttle discount.*

4. I would explore reducing onsite parking even further if the goal is to truly market this project as a TOD.

*Response:*

***We worked very diligently to reduce the number of parking spaces at NND down to 1,550, the lowest parking ratio of any existing development in the Greater Boston suburbs (a level that maximizes shared parking and yet provides a base number satisfactory to finance and lease NND).***

***That being said, we have prepared and submitted a revised plan that we hope will appeal to both parking minimalists and parking maximalists. The new plan reduces striped spaces from 1,550 to 1,450 AND creates a 200-car valet pod (total of 1,650) that will accommodate overflow in the peak holiday season.***

***This plan is responsive to the marketplace (peak demand) and our commitment to reducing single occupancy vehicles (lowered number of parking spaces). We agree that any further reduction of parking should be done in concert with parking restrictions or resident parking policy on neighborhood streets. We will include a lease provision to restrict parking on neighborhood streets and void incentives for violators. However, that may be difficult to enforce without a neighborhood resident parking sticker program (although the City of Newton winter parking ban will resolve the issue from November 15<sup>th</sup> to April 15<sup>th</sup> each year).***

Follow Up Questions (4/17.19 via N Khan):

1. I am not clear how the shared parking program will work. I understand the basic concepts of shared uses, but the details are murky. I also know the City's shared parking program is not faring well at all. I would like more information.

*Response:*

***In order to bridge the divide between parking minimalist and parking maximalists, we have developed a creative response that should appeal to both. The revision will reduce striped spaces to 1,450. This will be the parking count in the ordinary course. That will also free up a 200-space valet pod which will create the excess capacity to accommodate the peak holiday season. This plan is responsive to the marketplace (peak demand) and our commitment to reducing single occupancy vehicles (lowered number of parking spaces). That being said, we have tried to communicate how it works very clearly in our revised submission. The City's shared parking program is informal and voluntary. NND's is neither. Please see attached Exhibit B shared parking analysis***

2. Peter describes the transportation management plan as "radically aggressive". While it is robust, I am not convinced that it is aggressive enough. Peter mentions the financing may be jeopardy if they lower parking too much, but transportation is transforming before our eyes, and if they have a commitment to getting people out of their cars and into shuttles then I believe they can reduce parking even further. I also believe there a lot of people ready to live car free and families who can function well with one vehicle who would love to live in Newton.

**Response:**

*We completely agree and that is why we programmed the lowest parking ratios of any existing development in the Greater Boston suburbs why we have reduced striped parking even further, and (in part) why we placed the parking underground (if it is underutilized, at least it will not be an above grade multi-level eyesore for decades to come – as will be the case for many “comparable” developments). While we agree on the future, we will still need the buy-in of the construction lender and the Commercial and retail tenants in the present. It is our professional opinion that current NND parking programming pushes them as hard as they will accept.*

3. The Upper Falls Greenway ends at National Lumber. Is the plan to connect to the Newton Highland's Green Line? If so, I would like more information about this plan.

**Response:**

*Northland has not dug in on the access issues behind National Lumber. We are committed to make every effort to help create this critical link.*

4. 800 units is a lot, but I am concerned if the project size drops too much it will could jeopardize the robust shuttle bus service. We could very well end up with a smaller project that could end up causing even more traffic.

**Response:**

*800 units represents the lowest density of all the comparable Newton developments, including Avalon Newton Highlands, Avalon Chestnut Hill, Washington Place, Austin Street, Village Falls Condominiums and Chestnut Hill Towers. NND's 22.6 acres comprises three large individual parcels, 156 Oak Street, 55 Tower Road, and Marshalls Plaza, which could each be a development project in their own right, with access onto only one street. We have worked patiently over 40 years to assemble the three parcels, and it is this assemblage that allows for the permeability, connectivity, and open space of NND's landmark design.*

*Further, Northland has nearly 50 years of national experience, and we have never seen a mixed used development with 43% open space, nor have we ever witnessed NND's level of neighborhood permeability including the fact that NND is accessible on all four sides by parks.*

**Regarding smaller programming, it is the 677 market rate units that provide the financial underpinning to fund the Shuttle, create 9.8 acres of open space, place 900 parking spaces underground, and build the community amenities.**

**Please see Exhibit F for a comparison of density.**

Councilor Andreae Downs

1. She sees that in the ENR DOT recommended “banking” some spaces, i.e. there could be spaces built and not programmed for use and then used when necessary. It is a workaround – and it could allow us to have 2 numbers out there and get where we need to be

*Response:*

*We agree.*

*In order to bridge the divide between parking minimalist and parking maximalists, we have developed a creative response that should appeal to both. The revision will reduce striped spaces to 1450. This will be the parking count in the ordinary course. That will also free up a 200-space valet pod which will create the excess capacity to accommodate the peak holiday season. This plan is responsive to the marketplace (peak demand) and our commitment to reducing single occupancy vehicles (lowered number of parking spaces).*

2. She wants the shadow study

*Response:*

*Attached for your review is an updated shadow study (Exhibit E) for NND based on the revised programming we presented at the March LUC hearing. We are pleased to note that, based upon the revised programming of NND 2.0, no shadows attach to ANY Upper Falls buildings beyond 9:00 am on the winter solstice.*

3. She is struggling with why density is good. She gets the green argument, and she thinks density is good, but she's not sure why.

*Response:*

*On the merits of density, we firmly believe density is critical to enlivening NND’s streets and open spaces to create a sense of place. NND will be the heart of activity along the corridor and the N-Squared District and will achieve the over-arching goals of the Needham Street Vision Plan, most importantly the vision for land use. We cannot achieve this with lower density. We have put our parking underground to create a more desirable pedestrian environment. We have dedicated 43% of development to open space, and are providing a dedicated community building, a playground and several large green spaces for public benefit. Density is the financial engine necessary to provide these critical place-making ingredients. Finally, it enables us to add critically needed housing inventory to the City, including 123 affordable housing units and a dedicated building designed to allow seniors to age in-place.*

***128 Business Council’s contribution:** Higher density can be good for both environmental and social justice reasons. Beginning with the social justice reasons, the Greater Boston Area is experiencing a major housing crisis, and the deleterious effects of this crisis fall disproportionately upon those without the means to pay “whatever it takes” to find convenient housing. We cannot increase housing stock within the Greater Boston Area itself without increasing residential density. This ends up being closely related to the environmental reason, since those with less financial means must move to further-flung locations and/or to areas with poor-to-no alternative transportation options, and therefore end up dependent upon single-occupancy vehicles. Higher-density developments (if they contain a diverse mix of multi-use tenants, which this development is definitely designed to do) further promote*

*environmental goals by not only counteracting suburban expansion but also reducing local trips thanks to a wider range of destinations being located within walking or biking range.*

Follow Up Questions (4/17.19 via N Khan):

1. One of the mitigation measures mentioned initially was a connection of the Greenway spur to Christina Street and help negotiating the eventual connection to the Needham side of the Charles River, and parks and pathways there. Is that still part of the discussion?

**Response:**

*The potential Greenway spur that would connect the Upper Falls Greenway to the myriad of recreational opportunities across the Charles river for pedestrians and bicyclists of Newton was an important motivation in our decision to acquire 56 Christina Street. It is only due to our patient assemblage and thoughtful design that this spur is possible. We are 100% committed to try to make that connection a reality.*

2. Another transportation enhancement—building a better-than-average bus shelter with benches and real-time bus arrival information—has been floated for the stop on the northbound side of Needham Street. Can that be added to the developer's mitigation mix?

**Response:**

*Northland intends to build a state-of-the-art bus shelter on northbound side of Needham Street, integrated with the Mobility Hub so that commuters can have comfortable options on both sides of the street, while waiting for the MBTA Route 59 bus.*

3. Whom is the Oak Street entrance/exit meant to serve? Can traffic there be restricted to that population?

**Response:**

*The four means of ingress/egress currently programmed are required to adequately operate NND. The Oak Street curb cut, which currently exists (and would handle an order of magnitude more traffic in the “as of right” build scenario) is essential to minimize impact on key intersections along the corridor. Beta thoroughly studied alternatives for the Oak Street entrance and arrived at the same conclusion.*

4. If not, can the Oak Street entrance/exit be trialed at full build out and closed to some or all traffic in the event that neighbors' fears of Oak/Chestnut/Eliot street gridlock prove correct?

**Response:**

*The four means of ingress/egress currently programmed are required to adequately operate NND. The Oak Street entrance is essential to minimize impact on key intersections along the corridor. Beta thoroughly studied alternatives for the Oak Street entrance and arrived at the same conclusion.*

5. What is the Transportation Alternatives Analysis and what will it allow Newton to do?

**Response:**

*The Transportation Alternatives Analysis is proposed by the Planning Department to study the feasibility of improved or faster MBTA service and to identify future priorities. The Planning Department can respond to the specifics of the analysis.*

6. How many peak hour trips are we talking about total?

*Response:*

*The Planning Department recommended a performance goal be established for limiting NND trip generation based upon the "Robust Shuttle" model mode share projection in VHB's traffic impact study, which assumes 60% vehicle usage and 40% other usage (including transit) by residents and office workers during the weekday morning and evening peak hour. Based on the updated traffic projections reviewed and accepted by the City's peer reviewer, the goal would be set at 396 total vehicle trips in the weekday morning peak hour and 487 total vehicle trips in the weekday evening peak hour. If actual vehicle trips exceed this amount for a sustained period, then further measures would be implemented to reduce vehicle trips, including additional MBTA and shuttle incentives, modification of shuttle routes or capacity, or improved marketing and awareness, or introduction of additional transit options. Northland agrees with the performance goal for NND and will abide by the requirement as long as the special permit is in effect*

7. Can the parking be "banked," that is, not built unless shown to be needed as the project is completed?

*Response:*

*Thank you for this suggestion. We have prepared and submitted a revised parking program and operations plan that we hope will bridge the divide between the parking minimalists and the parking maximalists. Please see Exhibit B for the revised parking plan. This plan is responsive to the marketplace (peak demand) and our commitment to reducing single occupancy vehicles (lowered number of parking spaces).*

8. I have heard that real-time trip counts are possible and can be set up to be monitored remotely and transparently. Can we require this to ensure project trip generation remains below target, particularly for rush hour(s)?

*Response:*

*Continuous and real-time traffic counting devices are typically built into traffic signal systems. Since NND trip generation data must be recorded at all driveways, having continuous count/real-time count at only one location will not be productive in measuring overall site-generated traffic. Traffic counts will be conducted by Northland's traffic engineer at each NND driveway during the peak hours each year to determine the level of NND trip generation as part of its compliance obligation.*

Councilor Deborah J. Crossley

4.17.19 via N Khan

1. Which buildings, uses and public outdoor spaces would come on line first, second, etcetera?

*Response:*

*NND will not be phased. It will be financed and built as one project. The actual development of the buildings will be sequenced to efficiently manage construction and allow for orderly lease-up of the apartments. Based on our current planning, the first sequence of construction will include blocks 5 and 6, and buildings 2, 3, and 7. Also included with the first sequence will be the renovation of 156 Oak Street and the construction of the Village Green, the Community Park & Playground, the Community Building, the Mill Park, the Mobility Park, and the restoration of South Meadow Brook. The second sequence will include Buildings 4, 8, the townhouses, and the Oak Street Park. The first sequence will comprise 498 units and the second sequence will include 302 units.*

2. Will the shuttle be a fully operational system at that [C of O first 400 Units] point?

*Response:*

*The NND Shuttle System (meaning all three of the routes shown in the slides from Monica G. Tibbits-Nutt's statement before the LUC on 4/9/19, attached Exhibit G, and running on the complete schedules shown on the included time tables) will start with 100% service once NND has received a certificate of occupancy for 400 units. We will hit this point in the first sequence of construction. The shuttle program will be an integral part of our marketing program – meaning that we believe that many tenants will move to the development because of the shuttle options – so it is essential that it be operational in this first sequence.*

3. I see that some opinions we are seeing in letters from the public, try to relate the intensity of use proposed for this site to others they can see - particularly Avalon at Newton Highlands and Chestnut Hill. I believe both of those projects have more square foot of building relative to site area, and far less usable open space relative to the amount of building on each sites, although Avalon at Newton Highlands may be more comparable to Northland. I believe that both Austin Street and Washington Place were permitted with a higher proportion of building area to open space a well. **It would be helpful if the Planning Department could verify the numbers.**

*Response:*

*800 units represents the lowest density of all the comparable Newton developments, including Avalon Highlands, Avalon Chestnut Hill, Washington Place, Austin Street, Village Falls Condominiums and Chestnut Hill Towers. None of the comparables in Newton or in Greater Boston, for that matter, have anything resembling 43% open space. 43% sets a new standard.*

*NND's 22.6 acres comprises three large individual parcels, 156 Oak Street, 55 Tower Road, and Marshalls Plaza, which could each be a development project in their own right, each with access onto only one street. We have worked patiently over 40 years to assemble the three parcels, and it is this assemblage that allows for the permeability, connectivity, and open space of NND's landmark design.*

*It is also important to recognize the type of density. For example, Newton Highland's unit mix is comprised of 67.3% two- and three-bedroom apartments (which generally generate more traffic, requires more parking, and attracts more families), whereas NND's unit mix is comprised of 40% two-bedroom apartments and 5% three-bedroom apartments.*

*Further, we have never seen, anywhere in the country, the permeability of NND, particularly for pedestrians and bicyclists, given that NND is accessible on all four sides by parks (a design which we have never seen).*

*Please see Exhibit F for a comparison of density.*

4. I also heard at the meeting that the intersection of the Avalon Bay drive and Needham Street works at a level of service LoS A. There are 294 units there on less than eight acres, and now the Nexus lot is connected directly to Avalon, providing another egress from their site. **It would be helpful if the Planning Department would confirm this data.**

*Response:*

***Planning Department to Respond***

5. I understand that given the investments made so far - two layers of underground parking, more open space, a subsidized shuttle serve, and more we'll hear about with stormwater management, affordability and building design... that there is proposed a cap on other mitigation spending of five million. This is related to the list of investments we'd like to make in alternative transit options including a 275K comprehensive feasibility study including a look at a Greenline extension, accessible access to the Elliot and Highlands T stops, extending the bikeway to Needham over the Christina bridge, etcetera. Some of these ideas have been kicking around for a few years. **Can the Planning Department help us understand what each of these projects would entail, where they stand - and identify the challenges to achieving each one.**

*Response:*

*Planning Department to respond. Northland is passionately interested in ALL of these initiatives, Green line extension, Elliot/HIGHLAND T access, Christina Bridge access, etc. We would very much welcome an update and status report.*

6. Finally, the public comment went so late that the committee did not have a chance to hold a constructive conversation the same night. Although we are invited to put forward our questions in this forum, it would be more helpful - given how managed transit is critical to the success of the project - if we could have a conversation in committee to make sure we all understand the intricacies of this very new approach to transit. It would be my **preference to hold such a meeting completely separately** from the final design, stormwater and sustainability meeting coming up in May.

*Response:*

*Our understanding is that time has been set aside for April 30 without public comment. After the issues involving the last LUC hearing, Northland will need to confirm that any public comment will be in writing not in session.*

**Councilor Maria Scibelli Greenberg**

1. Regarding proposed shuttles- Will there be an age restriction for shuttle use? Can students use them? Will stops to the Library, YMCA, NewCAL senior center and Boys and Girls Club be included?

***Response:***

***The NND Shuttle System will be open to all, including students.***

***In the future, the Newton Local could be expanded or included in a broader system that would include the YMCA, the new senior center, the Boys and Girls Club and others. However, we are first going to establish the success of the initial four destinations included in our initial three routes before contemplating expansion. As an aside, the specific stops in any future expansion can be informed by the surveying of shuttle riders and local non-riders in order to determine demand.***

2. The number of announced affordable units is still listed at 123, I would like that increased to 145 as the Planning dept recommended to follow our proposed IZ ordinance.

***Response:***

***Northland may have made a mistake in agreeing to make changes worth tens of millions of dollars so early, particularly the undergrounding of parking. This may have given the false impression that the development could afford more concessions. NND is now on the cusp of financial viability. Upon a final Order of Conditions meeting, we will be prepared to address incremental increases in mitigation.***

3. In the planning memo dated April 9th BETA analyzed the 4 alternatives for Oak street access and recommend that removing or restricting access from Oak would result in negative impacts on the remaining intersections. Planning also agreed. However, is Alternative #4 "where No left turns allowed to exit site driveway onto Oak" still a consideration? It would make practical sense that left turns would cause delays in traffic flow.

***Response:***

***Following Beta's analysis and recommendation, no restrictions will be placed on ingress and egress at the Oak Street entrance.***

**Councilor David Kalis questions:**

1. If the key issue surrounding traffic on Needham St is the high rate of (70%) pass through traffic, what can we do in the short run and long run to reduce this traffic?

**Response:**

*Commuter cut-through traffic has been a challenge to Needham Street and other feeder roads to Route 9 long before the use of GPS traffic tracking software. The problem will continue to get worse without greater reliance on alternate transit modes. This is what NND is committed to accomplishing with a concrete goal of reducing single occupancy vehicle trip generation.*

2. Given the long list of mitigation that has been listed and the potential tremendous costs of these, has there been discussion with the developer and to what extent are they on board?

**Response:**

*Thank you for understanding our extraordinary commitment to newton. We are very proud of our plans for NND that honor this once in a life time opportunity. Northland is fully committed to NND and will begin the development immediately upon obtaining permits. We plan to move our corporate headquarters to the historic Saco Pettee Mill.*

3. A second traffic study was done by Ward 8 constituents who hired TEPP LC. One of their key findings was a need for a city-wide traffic study that incorporate not only Northland, but other developments that are in process. Have you seen this report? What are we doing to address this key finding? How can we better understand the complete nature of potential buildout vs one off developments?

**Response:**

*Planning Department to Respond*

4. Auto ownership in Needham and Newton has been high at 1.5+ cars per HH for some time (since 2010) indicating a low probability of people using transit. How realistic is it to expect new tenants to own just one car?

**Response:**

*This statistic reflects predominantly single-family households and therefore is not indicative of the targeted population of NND.*

*Northland Is totally committed to reducing automobile reliance at NND by providing the lowest parking ratio of any existing development in the suburbs, offering both door-to-workplace and 20-minute last mile frequency shuttle service, and agreeing to an aggressive performance goal for trip generation reduction. In addition, parking will be charged separately and will be expensive. And further, millennials are increasingly gravitating away from car ownership.*

*Finally, 128 Business Council has established and run successful shuttle routes for three decades in Waltham, Bedford, Lexington, and Needham – communities that have similarly high rates of car ownership. The combination of the introduction of viable alternative transportation options, route planning and monitoring by a team of dedicated professionals, in-house public outreach and consistent marketing, and shifting generational attitudes can both (a) invite new residents*

*open to relying on alternative transportation, and (b) produce a shift in behavior among some preexisting residents.*

5. Given people can find lower priced housing and more convenient mass transit in Cambridge, Somerville or Medford, why would people move to Newton and then take a shuttle? Do we really need a shuttle to Cambridge?

**Response:**

*The NND Cambridge shuttle not only serves residents commuting to Cambridge, it also serves Cambridge residents that work at NND. The Cambridge shuttle will provide door-to-door express service to Kendall Square and Central Square in comfort with WiFi service and dependable scheduling. If, after time, it is determined that the Cambridge route is not building ridership, then a route adjustment would be considered.*

*It is also worth noting that the stock of lower-priced housing in Cambridge, Somerville, and Medford is rapidly disappearing.*

6. Given the location of the Northland project, it appears perfect for someone who works on 128. Why are there no plans for shuttle to businesses on 128?

**Response:**

*We believe NND will appeal to professionals working along Route 128 as well as in Newton, Boston, Cambridge, LMA and Brookline.*

*Based on the available data sets (including traffic data, mode usage data, public transportation ridership, older commuter surveys, and 128 Business Council's more recent in-house origin/destination surveying), possible northbound destinations along Route 128 lack the origin/destination clustering needed to build a route. What this means is that, while there may be a lot of commuters currently traveling between Newton and destinations along Route 128, not enough of them are starting and stopping in adjoining locations.*

*However, as the NND Shuttle System manifests, it's likely that there will be opportunities to integrate our service into a broader network that would serve Route 128 office parks. The specific stops for future expansions can be informed both by (a) the surveying of shuttle riders and local non-riders in order to determine demand, and (b) the development of other new shuttle routes that might be connected to ours, which is in keeping with 128BC's historical operating model.*

7. I have docketed an item to understand the add a lane impact on the City of Newton. It appears that traffic has increased in some areas and may be flat in others. In theory, what mitigation can actually be done post final work that makes a difference in traffic? Will we have the same issues with Northland - that once it is built, mitigation measures can only do so much?

**Response:**

*Northland's commitment to a performance goal for limiting trip generation is unique and forward-looking. We will be able to monitor the success of our shuttle and then make modifications if results are not satisfactory. We will employ a variety of tools to help insure success. But the tool that would probably be most supportive of NND and most effective in animating the shuttles, would be a dedicated bus/shuttle lane.*

**Councilor Chris Markiewicz Questions:**

Note: I understand that not all of these questions affect the granting of a permit, but they may be relevant to conditions included in the Council order or provide context to understand the requirements that the petitioner must address in order to sustain a viable project/investment

**Housing:**

1. We recently heard testimony (from a demographic expert consultant hired by our schools) that mixed age residential complexes are not for the most part attractive to the over-55 population. Do you have data that supports the opposite conclusion? Is it locally based?

**Response:**

**The information from the demographer regarding mixed age residential was anecdotal, personal, non-New England, and not fact based. I would defer to the experts at the Council of Aging that have the complete opposite view.**

**Timeline:**

2. I understand the timeframe from start to a full build out will be 5 years or more. Is this correct?

**Response:**

***Please see attached Exhibit H for 5 Year Development Schedule***

3. Given the timeframe, and understanding that plans can change for several reasons, including economic conditions, can specify which buildings/facilities will be delivered in specific years or at least group them into tranches with target dates? Noting any significant dependencies that could affect this would be appreciated

**Response:**

***Northland is not phasing the project. Northland is investing only internal equity, which it has in hand. Given our long-term view, we have no intention of changing plans in light of near-term market changes or dislocation.***

***Our only condition precedent to breaking ground is closing a construction loan. Given our national reputation, the fact that we have borrower channel status with FNMA and a Freddie Mac Select Sponsor and have kept our lenders apprised of our progress, we expect to close the construction financing this year (assuming we get the permits in a timely fashion).***

***Please see attached Exhibit H for 5 Year Development Schedule***

**Transportation/Traffic**

4. You have an objective of getting 40% of residents to use one of the 4 shuttles (daily?) to commute. Does this imply that there would be a pro-rata decrease in the number of cars parked onsite considering each unit's planned/traditional estimate of parking need?

**Response:**

*We expect 40% to use alternative transportation, including the shuttle, the T (free annual T passes), the commuter rail (shuttle access), walking, and biking (and soon presumably scootering). Those numbers are factored into our parking count.*

*Just an additional clarification: There are three planned routes (the Newton Local serving Newton Highlands and Newtonville, the Boston Express, and the Cambridge Express), but there will be 8 dedicated shuttles needed to achieve the planned frequencies for these routes. See the slides from Monica G. Tibbits-Nutt's statement before the LUC on 4/9/19 (attached Exhibit G), esp. p. 8.*

5. How will you remediate the situation if this 40% objective is not reached? My understanding of these types of arrangements is that the likelihood of success is often evident early on in the implementation. What kind of timeline(s) do you have to measure whether the objective is being achieved? How will you measure and report?

*Response:*

*As outlined in the April 5<sup>th</sup> planning department memo, we have agreed to commit to a metric of performance regardless of method or resource used to achieve that goal using a basket of TDM measures, outlined in the TDM Workplan Exhibit H.*

6. The price of one or more of the shuttles was shown at \$7 per ride. Are there plans for subsidies, volume or other discounts? For some shuttles, \$14 round trip plus additional costs for the next leg of transportation could be more than many can bear, even those who can pay 3k a month for rent. For others, the net difference in cost for driving may not be enough to motivate them to abandon the convenience (for the most part) of using a car.

*Response:*

*See p. 9 of the slides from Monica G. Tibbits-Nutt's statement before the LUC on 4/9/19 (attached Exhibit G) for the proposed fare structure. The Newton Local is set at \$2.50, while the Boston Express and Cambridge Express are set at \$7.00. These rates are set to be competitive with the MBTA, with the latter comparable to the cost of the Commuter Rail, although the two express routes may prove more 'express' than either the Commuter Rail or the Green Line.*

*Yes, there are plans for multi-ride passes that will reduce the per-ride cost, as well as other forms of potential subsidies.*

*We anticipate there being two distinct audiences for the Boston and Cambridge Express routes:*

*(1) Riders who are living a car-free or shared-car lifestyle, for whom the shuttles are an opportunity to avoid using TNCs (like Uber and Lyft) and who will appreciate the more dependable and more direct service as compared to other public transportation options.*

*(2) Riders who do own a car but are making the choice to take the shuttle for the sake of comfort and reduced hassle. 128 Business Council has found through both anecdotal and survey research that many drivers do not actually view driving their single-occupancy vehicles*

*as convenient. In fact, they have an established ridership on their preexisting routes of commuters who own vehicles but self-report that they prefer taking a shuttle, because it allows them to reclaim the time they would have spent driving (since they can work or engage in entertainment on the shuttle), reduce stress, and avoid the hassle of parking. These potential benefits will be a major part of the shuttle system's marketing.*

7. Can you make all shuttles electric and require any ride share that is allowed on the property to be electric?

*Response:*

*Unfortunately, electric buses are not viable for most shuttle systems at this time. 32-passenger buses such as the ones we will employ must be charged at more frequent intervals than must an electric car and would require charging at irregular intervals when sitting in dense traffic. The Commonwealth currently lacks the electric charging infrastructure to use electric vehicles on longer trips (such as the Boston and Cambridge Express routes), and frequent charging would also reduce service frequency and prevent schedule reliability on the shorter Newton Local route. It is our hope that alternate fuel vehicles will become more viable in time. 128 Business Council is well-apprised of state and national standards and projections in this regard and will make fleet upgrade recommendations as they become feasible.*

**Finances:**

8. Can you provide an estimate of what the rental rates will be for both market and affordable rate units?

*Response:*

*We do not yet know the market rate pricing and we are 5 years out. Attached (Exhibit J) is a schedule of typical affordable rents, income levels, and a comparison of salaries for teachers, police, and fire professionals in newton.*

9. Can you provide an estimate/range for the rental of office space?

*Response:*

*The office space will be best in class. Our consultant is currently contemplating mid 40s per square foot. We believe it will be substantially higher. Northland will take approximately 25% of the mill space for our headquarters.*

10. Is there a minimum amount of residential units and total square footage below which the project is financially unattractive to investors and financiers of the project? I do understand that this may not be something you wish to disclose in any detail, and I appreciate the reasons for that, but my intention is to balance the scale of this which concerns many due to the unknowns regarding impacts on traffic and other factors, it would be helpful to have some sense here.

*Response:*

*Northland does not take investors in our development projects. The funds are internal. As noted above, Northland made a massive concession early in the process to place 1,054 parking spaces underground. That was the recommendation of the peer reviewer and planning and we agree. It will set up NND as a national model of permeability and connectivity and open space. That change along with the open space, the seven fully programmed parks, the community building, the community playground, the mobility hub, the shuttle, the all age friendly building, the I and I contribution, the traffic contribution and the school contribution leaves us at the threshold of financial viability.*

11. Do you have plans to securitize this property ( e.g. a REIT ) ?

*Response:*

*No. Northland has never sold a development and we are certainly not going to sell or securitize this crown jewel in our home town.*

12. While I hear from many sources that we need housing and more of it everywhere, I also have been hearing from some local landlords of smaller (multifamily) properties that they can't rent their units. Are you aware of this and although anecdotal, does this reflect a move towards the type of complex you are planning to create or is the rental market in Newton showing signs of softening?

*Response:*

*Northland owns and operates more than 25,000 units throughout the country. The market is Stable and firm, at 95% occupancy. That anecdotal information does not match our experience.*

**Other:**

1. Will you commit to meet on a regular basis (your representative, not a resident designee) with the neighborhood association(s) to review status of implementation of the various programs that will benefit or issues that are negatively impacting the local neighborhood and seen as being caused by Northland either during construction or after completion? Can you explain how you would have to be accountable to address true adverse conditions cited by the association rather than just acknowledging them without being able to address them in a satisfactory manner. (not trying to be flip, just want to see how this is considered and understanding that our inspections dept. has some authority here as well)

*Response:*

*Yes. We have attended hundreds of meetings and met thousands of residents. I believe that all would agree (residents such as Jack Neville specifically) that even when we disagree, we are respectful, honest and direct. We want to be a great neighbor. We believe NND will knit Upper Falls, Newton Highlands, and Oak Hill back together in the most amazing and beautiful way. We know change is hard. But we believe when residents see the fruits of our labors, they will enjoy them immensely.*

*We anticipate owing NND for ever (whatever that actually means) and will meet our neighbors, listen to them and respond in a constructive way, if at all possible.*

**Chief Planner Jen Caira Questions:**

**Documents to be provided:**

1. Information on new shuttle route and numbers of total seats during peak hours
2. Revised shared parking plan
3. Additional peak parking demand information for December
4. Updated traffic generation numbers
5. Historic Shuttle data from other 128 Business Council services or routes— ideally case study of an existing development that is being served by their shuttles; ridership trends on services provided over the last three years; provide examples of how they have adjusted services in response to demand at the companies they serve.
6. Annual (or phased?) TDM work plans from first occupancy through full occupancy. This should be as detailed an outline as possible at this point.

Updated 4.19.2019 From J Caira: (Redundancies omitted)

7. Provide mode share and internal capture trip generation adjustment calculations; this should be as detailed as possible and should serve as an example of how changes in mode share will be reported to the Planning staff.
8. Approach, as detailed as possible, on managing TNC operations (see attached link on how Uber plans to enter the shuttle bus market.) <https://www.geekwire.com/2019/uber-sees-rapid-adoption-new-bus-service-recruits-high-capacity-vehicles-team-seattle/>
9. Approach to conducting the annual transportation surveys: methodology; sample size; how will they ensure a representative sample; what kind of tabulations will they run; how will it be administered; sample questionnaire.

**Responses to Councilor questions, including:**

10. Will there be age restrictions on the shuttles?
11. Where will the shuttles stop? Will they (should they) stop at places like the library, YMCA, Boys and Girls Club, Senior Center, etc.?
12. How are the shuttles counted in the trip generation?
13. What will the pricing be for the shuttles and what control will there be over time?
14. How will the shuttle system be phased?
15. What will the travel time be for shuttles during rush hour?
16. Can electric shuttles be utilized?
17. How will the parking garages be designed and operated to improve efficiency (red and green lights over available spaces, etc.)?
18. What will be the impact of Waze on the neighborhoods?
19. How did they come up with ridership numbers? What examples show the riders will come?
20. What percentage of people are expected to live and work on site?
21. How will the surveys be administered and what sort of data is expected?

**VHB's Responses to the comments received on April 3, 2019, from BETA Group:**

**Trip Generation Comment**

1. In Table 2 – Project Trip Generation – ITE Unadjusted Vehicle Trips, the weekday morning peak hour unadjusted vehicle trips is shown as 668 trips. BETA has calculated the number of unadjusted vehicle trips in the weekday morning peak hour to be 592 trips. Please confirm and recalculate Build Condition vehicle trips.

**Response:**

*VHB rechecked the calculations for the Build Conditions unadjusted weekday morning vehicle trips and has confirmed that number to be 668 vehicle trips. The unadjusted vehicle trips are based on the ITE land use code regression equations for each proposed land use. The ITE trip generation worksheets for each land use are included in the Attachments to this memorandum.*

2. Please provide the mode share and internal capture trip generation adjustment calculations.

**Response:**

*The mode share and internal capture trip generation adjustment calculations are included in the Attachments to this memorandum.*

3. In Table 8 – Project-Generated Peak-Hour Vehicle Trips by Use – Build Condition with Robust Shuttle Service, the vehicle trip numbers under the residential, office, retail, and pass-by columns are not correct. They are the same numbers shown in Table 6 – Project-Generated Peak-Hour Vehicle Trips by Use – Build Conditions with Existing Mode Share. The numbers in this table should be updated.

**Response:**

*Table 8 has been updated with the correct numbers for residential, office, retail, and pass-by vehicle trips based on the Robust Shuttle service scenario and is provided below:*

**Parking**

1. Please provide the shared-parking calculations by hour for both weekday and weekend.

**Response:**

*The shared-parking calculations for both weekday and weekend for the month of December are included in the Attachments to this memorandum.*

*The following is a summary comparing the proposed project parking spaces by use with the MBTA/MassDOT Transit-Oriented Development Policies and Guidelines.*

- The 800 residential spaces (1 space/unit) meet the MBTA/MassDOT TOD guideline of 0.75-1.5 spaces/unit.
- The 149 retail spaces (3 spaces/KSF) meets the guideline of 1.5-3.0/KSF.
- The 245 restaurant spaces (6.1 spaces/KSF) exceed the retail guideline of 1.5-3.0/KSF. However, the guidelines do not break out restaurants.

- The 51 medical office spaces (3.4 spaces/KSF) exceed the office guideline of between 1.0 and 2.5 spaces/KSF. However, medical office parking demand is typically higher than general office use.
- The 38 health club spaces (3.8 spaces/KSF) exceed the retail guideline of 1.5-3.0/KSF, but not significantly so and they are relatively few spaces.
- The office use has 298 spaces with a rate of 1.7 spaces/KSF, which meet the guidelines between 1.0 and 2.5 spaces/KSF.
- The proposed 1,550 parking spaces will meet demand, except for the peak December shopping season (1,596 vehicles). The option to use a portion of the residential spaces for shared-parking, if needed, appears reasonable.
- Overall, the proposed 1,550 parking spaces appear adequate to accommodate parking demand for the mix of land uses in a shared-parking operation.

## Exhibits

- Exhibit A – Shuttle Detail
- Exhibit B – Shared Parking Management Plan
- Exhibit C – Hourly Parking Detail
- Exhibit D – Updated Traffic Generation Response from VHB
- Exhibit E – Updated Shadow Studies April 2019
- Exhibit F – Newton Multifamily Development Density
- Exhibit G – Monica Tibbets Nutt LUC Presentation
- Exhibit H – Development Five Year Timeline
- Exhibit I – TDM Work Plan
- Exhibit J – Newton Salaries & HUD Affordable Rents 80% AMI
- Exhibit K – NND Open Space Comparison

## **Exhibit A**

**Option 4.4 - Reduced Schedule Recommendation 2**

60-minute frequencies **weekdays** from 6:45am-11:00am and 3:45pm-9:00pm

60-minute frequencies **weekend** from 7:30am-10:30pm

**Monday-Friday**

	B1	B2	B1	B2	B1	B1	B2	B1	B2	B1	B2	B1	B2
<i>depart Transit Hub</i>		7:00		8:00	9:00	10:00		4:00	5:00	6:00	7:00	8:00	
Central Square	6:45	7:45	8:45	9:45	10:45		3:45	4:45	5:45	6:45	7:45	8:45	
Kendall Square	6:55	7:55	8:55	9:55	10:55		3:55	4:55	5:55	6:55	7:55	8:55	
<i>arrive Transit Hub</i>	7:40	8:40	9:40	10:40			4:40	5:40	6:40	7:40	8:40		

**Saturday-Sunday**

	B1	B2	B1	B2	B1	B2	B1	B2	B1	B2	B1	B2	B1
<i>depart Transit Hub</i>	7:30	8:30	9:30	10:30	11:30	12:30	1:30	2:30	3:30	4:30	5:30	6:30	7:30
Central Square	8:15	9:15	10:15	11:15	12:15	13:15	2:15	3:15	4:15	5:15	6:15	7:15	8:15
Kendall Square	8:25	9:25	10:25	11:25	12:25	13:25	2:25	3:25	4:25	5:25	6:25	7:25	8:25
<i>arrive Transit Hub</i>	9:10	10:10	11:10	12:10	13:10	14:10	3:10	4:10	5:10	6:10	7:10	8:10	9:10

**Option 1NH.4 - Newton Highlands Express with Alternating Extension to Newtonville Commuter Rail**

Service 6:00am - 10:30pm weekdays and 7:30am - 10:30pm weekends.

20-minute frequencies weekdays from 6:00am-10:00am and 4:00pm-8:00pm.

20-minute frequencies weekdays from  
30-minute frequencies all other times.

**Monday-Friday**

## Saturday-Sunday

**Shuttle Capacity Numbers, i.e. "available seats on the bus"**

	average potential rides per hour across entire workday period	potential rides per hour during peak workday hours (a.m. & p.m.)	average potential rides per hour across entire weekend period	potential rides per hour during peak weekend hour (midday)
Option 1.1 - Newton Circulator Original Schedule (pp. 3-4)	137.8 87.49*	(170.67)	128 85.33*	128 85.33*
Option 1.2 - Newton Circulator 30-minute frequencies (pp. 5-6)	197.67 126.38*	212 128*	189.44 126.29*	192 128*
Option 1.3 - Newton Circulator Reduced Schedule Recommendation (pp. 7-8)	196.40 121.60*	212 128*	128 85.33*	128 85.33*
Option 1NH.1 - Newton Highlands Express on 20/30-min frequencies (pp. 17-18)	159.03	192	128	128
Option 1NH.2 - NH Express Alternating Extension to Newtonville (pp. 19-20)	141.58 128*	(152) 128*	128	128
Option 1NH.3 - Newton Highlands and Newton Centre on 30-min frequencies (pp. 21-22)	189.13 126.09*	192 128*	188.85 125.90*	192 128*
Option 1NH.4 - NH Express Alternating Ext to Newtonville on 20/30-min freq (pp. 23-24)	178.42 159.03*	(232) 192*	128	128
Option 4.1 - Boston/Cambridge Express Original Schedule (pp. 9-10)	62.32	64	62.32	64
Option 4.2 - Boston/Cambridge Express 30-minute frequencies (pp. 11-12)	119.58	128	119.58	128
Option 4.3 - Boston/Cambridge Express Reduced Schedule Rec 1 (pp. 13-14)	108.80	128	61.87	64
Option 4.4 - Boston/Cambridge Express Reduced Schedule Rec 2 (pp. 15-16)	60.63	64	61.87	64

\*Adjusted downward to only consider the seats immediately available upon leaving or entering the development, rather than seats that may become available when riders alight and board away from the Development.

## **Exhibit B**

**NORTHLAND NEWTON DEVELOPMENT  
UPDATED PARKING MANAGEMENT PLAN  
APRIL 23, 2019**

The parking supply at the Northland Newton Development (“NND”) will be reduced to 1,450 striped parking spaces in four underground garages and NND streets (see Table 1). Additional valet pods aggregating 200 spaces will be created in the two largest garages to accommodate peak daily and seasonal parking demand. The monthly peak parking demand for NND is estimated to range from 1,507 to 1,596 spaces on the busiest weekdays and 1,331 to 1,447 spaces on the busiest weekend days (see Table 2).

**Table 1 – Proposed Parking Supply**

<b>Location</b>	<b>No. of Marked Spaces</b>
Building 3	103
Building 4	294
Building 5/6	840
Building 8	107
Building 14	6
NND On-street	100
	<b>1,450</b>

**Table 2 – Peak Parking Demand – Shared Parking, by Month**

	Jan	Feb	Mar	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec
<b>Weekdays</b>												
Residential	800	800	800	800	800	800	800	800	800	800	800	800
Commercial	707	708	733	719	729	728	715	725	723	738	742	796
Total	1,507	1,508	1,533	1,519	1,529	1,528	1,515	1,525	1,523	1,538	1,542	1,596
<b>Weekends</b>												
Residential	800	800	800	800	800	800	800	800	800	800	800	800
Commercial	531	534	569	554	568	567	567	568	575	554	576	647
Total	1,331	1,334	1,369	1,354	1,368	1,367	1,367	1,378	1,355	1,374	1,376	1,447

A parking management plan is necessary to accommodate the day-to-day parking needs of the mix of users. The key elements of the parking management plan of the Northland Newton Development include:

- A state-of-the-art monitoring system to track parking space availability and occupancy patterns,
- Short-term parking in the most convenient locations,
- Resident-only parking in smaller parking garages,
- Visitor and customer parking in the central garage only, and
- Use of valet and/or assisted parking to provide extra parking capacity when needed.

### **Monitoring of Parking Occupancy**

The parking occupancy patterns in the garages will be monitored using the latest available and highest quality technology. For a resident-only parking garage this may be in the form of automated overnight counts of unused parking spaces. For the Building 5/6 Garage, where most commercial parking will be, the monitoring will be an automated count system continually tracking occupancy.

The monitoring of the parking utilization in the garages will provide data on parking occupancy trends so that proactive transportation and parking management strategies can be implemented. For example, as the project is being leased the parking counts can be used to estimate the point during the lease-up that certain parking management strategies will first be needed. When the project is fully occupied, the parking counts can be used to determine the appropriate level of parking attendant and valet staffing for each day of the week and times during each day.

### **On Street Parking Within NND:**

After allocation of parking spaces for loading zones, valet parking stations, and TNC pickup, there will be approximately 100 on-street parking spaces available within the development. The objective for managing on-street parking is to accommodate most of the site's short-term parkers. The on-street parking time limit will be predominately one hour. Some of the most convenient spaces, including those near entrances to residential buildings, will be "quick stop" parking spaces with time limits of 20 minutes or less.

### **Underground Garage Parking**

The garage parking will be shared by residents and commercial users, including office employees, restaurants, retailers and customers. Residents will have unassigned parking among designated areas for residential use.

Permits will be issued for each garage except for the designated retail and visitor parking areas of the central garage of the 5/6 Block, and only those with the specific permit will be allowed to park in those garages. The assignment of the parking will be as follows:

#### **Building 3 Garage**

The parking for this 103-space garage will be used by residents of Building 3 (94 units). The remaining parking will be available for Building 7 residents.

#### **Building 4 Garage**

This garage comprises 294 spaces on two levels. The lower level will be the designated parking location for residents of Buildings 4, 9, 10, and 11 (142 units). The remaining parking located on Level One will be available to office tenants (152 spaces). Level One will also be utilized for valet parking by restaurants in the evenings and weekends.

#### **Building 8 Garage**

The parking for this 107-space garage will be used by residents of Building 8 (80 units), with remaining spaces available to Building 7 residents.

#### Building 14 Garages

The parking for these six townhouse units will be in individual garages connected to the units and reserved for the unit occupants.

#### Block 5/6 Garage

The Block 5/6 Garage has 840 spaces on two levels and represents more than half of the total parking supply. The garage will be the location for all customer/visitor parking, most of the commercial (office and retail) parking, and parking for residents of Block 5, Block 6, Building 12 and the balance of parking for Building 7.

Parking for residents will generally be on Level Two of the garage (430 spaces). Level One (410 spaces) will be used for office, retail, visitor parking and valet service. Some of the parking spaces in the commercial area may be designated for short-term parking, but most will be available to all commercial parkers.

#### **Valet-Assist Parking**

A portion of the office and restaurant parking will be managed using valet or assisted parking once the entirety of the anticipated commercial (office and retail) parking demand is reached. Per Table 2, the monthly peak parking demand for the commercial space is estimated to range from 707 to 796 spaces on the busiest weekdays and 531 to 647 spaces on the busiest weekend days. There will be enough self-parking available for commercial users on weekends other than in December. Additional parking capacity may be needed, at full occupancy, during the daytime on weekdays.

This additional capacity will be available through valet and attendant-assist parking in the Block 5/6 Garage and in the commercial portion of the Building 4 Garage. In the Block 5/6 Garage, parking attendants will stack cars in the 25-foot wide drive aisles and will be available to move and retrieve cars. Additional valet capacity will be made available on Level Two of the Block 5/6 Garage as needed. The commercial parking area in Building 4 will be used for valet services operated by restaurants. The additional capacity made available by valet parking will be approximately 200 vehicles, or up to 30% of the striped capacity of the parking areas. See Table 3 below.

**Table 3 – Parking Supply with Additional Valet Capacity**

Location	Total Available Parking	Residential Spaces	Commercial Spaces	Additional Capacity with Valet Parking
Building 3	103	103	0	0
Building 4	339	142	152	45
Building 5/6	995	430	410	155
Building 8	107	107	0	0
Building 14	6	6	0	0
On-street	100	12	88	0
	<b>1,650</b>	800	650	200

## **Exhibit C**

**Northland Newton Development - Right-Sized Parking**  
**Weekday - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

January

Land Use	User	Annual																								
		Peak Demand	Seasonal Factor	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid				
Shopping Center - Typical	Customer Employee	121 28	56% 80%	68 22	1 2	3 3	10 9	24 17	44 19	58 21	64 22	68 22	64 22	61 21	64 21	64 21	54 21	34 20	20 17	7 9	3 3					
Fine/Casual Dining	Customer Employee	134 30	85% 95%	114 29	- 6	- 14	- 21	17 26	46 26	85 26	85 26	74 26	46 21	57 29	85 29	108 29	114 29	114 29	108 29	85 24	28 10					
Family Restaurant	Customer Employee	106 22	85% 95%	90 21	23 10	45 16	54 19	68 19	77 21	81 21	90 21	81 21	45 10	41 10	68 20	72 20	72 20	72 20	54 17	50 14	45 14	23 7				
Health Club	Customer Employee	53 4	100% 100%	53 4	37 3	21 3	21 3	37 3	37 3	42 3	32 3	37 3	37 3	42 3	48 4	53 4	48 4	42 3	37 2	19 1	5 1	- -				
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800		
Office Office	Visitor Employee	41 311	100% 100%	41 311	- 8	- 93	8 233	25 295	41 311	18 280	6 280	18 311	41 280	18 311	6 280	4 156	2 78	2 31	1 22	- 9	- 3	- -	- -	- -	- -	
Medical/Dental Office	Visitor Employee	40 15	100% 100%	40 15	- -	- 9	36 15	36 15	40 15	40 15	12 15	36 15	40 15	40 15	36 15	32 15	27 10	12 5	6 2	- -	- -	- -	- -	- -		
		1705		1608	885	990	1,216	1,360	1,451	1,482	1,456	1,492	1,488	1,425	1,394	1,346	1,288	1,220	1,183	1,112	1,053	984	868			

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
 Weekday - Seasonally Adjusted Parking Demand by Time of Day

March 2019

February																		Annual									
Land Use	User	Annual Peak Demand	Seasonal Factor	Seasonal Demand	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12MId				
					6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12MId				
Shopping Center - Typical	Customer Employee	121 28	57% 80%	69 22	1 2	3 3	10 9	24 17	45 19	59 21	66 22	69 22	66 22	62 22	62 22	66 21	66 21	55 21	34 20	21 17	7 9	3 3	-				
Fine/Casual Dining	Customer Employee	134 30	86% 95%	115 29	- -	- 6	- 14	- 21	17 26	46 26	86 26	86 26	75 26	46 21	58 21	86 29	109 29	115 29	115 29	115 29	109 29	86 24	29 10				
Family Restaurant	Customer Employee	106 22	86% 95%	81 21	23 10	46 16	55 19	68 19	77 21	82 21	91 21	82 21	46 10	41 10	41 10	68 20	73 20	73 20	55 20	50 17	46 14	23 14	7 1				
Health Club	Customer Employee	53 4	95% 100%	50 4	35 3	20 3	20 3	35 3	35 3	40 3	30 3	35 3	35 3	40 3	45 4	50 4	45 3	40 2	35 1	18 1	5 1	- -	-				
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800				
Office Office	Visitor Employee	41 311	100% 100%	41 311	- 9	- 93	8 233	25 295	41 311	18 280	6 280	18 311	41 311	18 280	6 156	4 78	2 31	1 22	- 9	- 3	- -	- -	- -				
Medical/Dental Office	Visitor Employee	40 15	100% 100%	40 15	- -	- 9	36 15	36 15	40 15	40 15	12 15	36 15	40 15	40 15	36 15	32 15	27 10	12 5	6 2	- -	- -	- -	- -				
		1705		1809	883	990	1,216	1,358	1,450	1,482	1,458	1,493	1,490	1,424	1,394	1,346	1,289	1,221	1,184	1,112	1,054	986	869				

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
 Weekday - Seasonally Adjusted Parking Demand by Time of Day

March 2019

March

Land Use	User	Annual																					
		Peak Demand	Seasonal Factor	Seasonal Demand	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid
Shopping Center - Typical	Customer Employee	121 28	64% 80%	77 22	1 2	4 3	12 9	27 17	50 19	66 21	74 22	77 22	74 22	70 22	70 22	74 21	74 21	62 21	39 20	23 17	8 9	- 3	- -
Fine/Casual Dining	Customer Employee	134 30	95% 100%	127 30	- +	- 6	- 15	- 23	19 27	51 27	95 27	95 27	83 23	51 23	64 30	95 30	121 30	127 30	127 30	121 30	95 26	32 11	
Family Restaurant	Customer Employee	106 22	95% 100%	101 22	25 11	50 17	60 20	76 20	86 22	91 22	101 22	91 22	50 11	45 11	45 21	76 21	81 21	81 21	60 18	55 14	50 14	25 8	
Health Club	Customer Employee	53 4	85% 95%	45 4	32 3	18 3	18 3	32 3	32 3	36 3	27 3	32 3	32 3	36 3	41 4	45 4	41 4	36 3	32 2	16 1	5 1	- -	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office Office	Visitor Employee	41 311	100% 100%	41 311	- 9	- 93	8 233	25 295	41 311	18 311	6 280	18 280	41 311	18 280	6 156	4 78	2 31	1 22	- 9	- 3	- -	- -	
Medical/Dental Office	Visitor Employee	40 15	100% 100%	40 15	- -	- -	36 9	36 15	40 15	40 15	12 15	36 15	40 15	40 15	36 15	32 10	27 5	12 2	6 -	- -	- -	- -	
		1705		1636	883	994	1,223	1,369	1,465	1,501	1,484	1,518	1,509	1,441	1,411	1,389	1,314	1,247	1,209	1,133	1,072	1,002	876

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
 Weekday - Seasonally Adjusted Parking Demand by Time of Day

March 2019

April

Land Use	User	Annual Peak Demand		Seasonal Factor	Seasonal Demand		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid
		Customer	Employee		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid		
Shopping Center - Typical	Customer	121	83%	76	1	4	11	27	50	65	72	76	72	69	69	72	72	72	61	38	23	8	-		
	Employee	28	80%	22	2	3	9	17	19	21	22	22	22	22	21	21	21	21	20	17	9	3	-		
Fine/Casual Dining	Customer	134	92%	123	-	-	-	18	49	92	92	80	49	62	92	117	123	123	123	117	92	31			
	Employee	30	100%	30	-	-	6	15	23	27	27	27	27	23	30	30	30	30	30	30	30	26	11		
Family Restaurant	Customer	106	92%	98	24	49	59	73	83	88	98	88	49	44	44	73	78	78	78	59	54	48	24		
	Employee	22	100%	22	11	17	20	20	22	22	22	22	11	11	21	21	21	21	18	14	14	8			
Health Club	Customer	53	70%	37	26	15	15	26	26	30	22	26	26	26	30	33	37	33	30	26	13	4	-		
	Employee	4	80%	3	2	2	2	2	2	2	2	2	2	2	3	3	3	2	1	1	1	-			
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800			
Office	Visitor	41	100%	41	-	-	8	25	41	18	6	18	41	18	6	4	2	1	-	-	-	-			
Office	Employee	311	100%	311	9	93	233	295	311	311	280	280	311	311	280	156	78	31	22	9	3	-			
Medical/Dental Office	Visitor	40	100%	40	-	-	36	36	40	40	12	36	40	40	36	32	27	12	6	-	-	-			
	Employee	15	100%	15	-	-	9	15	15	15	15	15	15	15	10	5	2	-	-	-	-	-			
		1705		1619	875	989	1,217	1,359	1,454	1,488	1,470	1,504	1,496	1,430	1,400	1,352	1,296	1,229	1,195	1,121	1,064	997	874		

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
 Weekday - Seasonally Adjusted Parking Demand by Time of Day

March 2019

May

Land Use	User	Annual																					
		Peak Demand	Seasonal Factor	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid	
Shopping Center - Typical	Customer Employee	121 28	66% 80%	80 22	1 2	4 3	12 9	28 17	52 19	68 21	76 22	80 22	76 22	72 22	76 21	76 21	76 21	64 20	40 17	24 9	8 3	-	
Fine/Casual Dining	Customer Employee	134 30	96% 100%	129 30	- -	- 6	- 15	- 23	19 27	51 27	96 27	96 27	84 27	51 23	64 23	96 30	122 30	129 30	129 30	122 30	96 26	32 11	
Family Restaurant	Customer Employee	106 22	96% 100%	102 22	25 11	51 17	61 20	76 20	86 22	92 22	102 22	92 11	51 11	46 11	46 21	76 21	81 21	81 21	61 18	56 14	51 14	25 8	
Health Club	Customer Employee	53 4	65% 75%	34 3	24 2	14 2	14 2	24 2	24 2	28 2	21 2	24 2	24 2	28 2	31 3	34 3	31 2	28 2	24 1	12 1	3 1	-	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office Office	Visitor Employee	41 311	100% 100%	41 311	- 9	- 93	8 233	25 295	41 311	18 311	6 280	18 311	41 280	18 311	6 280	4 156	2 78	1 31	- 22	- 9	- 3	- 3	-
Medical/Dental Office	Visitor Employee	40 15	100% 100%	40 15	- -	- 9	36 15	36 15	40 15	40 15	12 15	36 15	40 15	36 15	32 15	27 10	12 5	6 2	- -	- -	- -	-	
		1705		1629	874	990	1,219	1,361	1,458	1,495	1,481	1,514	1,504	1,435	1,405	1,361	1,305	1,240	1,205	1,129	1,071	1,002	876

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
 Weekday - Seasonally Adjusted Parking Demand by Time of Day

March 2019

June

Land Use	User	Annual		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid	
		Peak Demand	Seasonal Factor																				
Shopping Center - Typical	Customer Employee	121 28	67% 80%	81 22	1 2	4 3	12 9	28 17	53 19	69 21	77 22	81 22	77 22	73 22	73 22	77 21	77 21	65 21	41 20	24 17	8 9	- 3	
Fine/Casual Dining	Customer Employee	134 30	95% 100%	127 30	- -	- 6	- 15	- 23	19 27	51 27	95 27	95 27	83 27	51 23	64 30	95 30	121 30	127 30	127 30	121 30	95 26	32 11	
Family Restaurant	Customer Employee	106 22	95% 100%	101 22	25 11	50 17	60 20	76 22	86 22	91 22	101 22	91 22	50 11	45 11	45 21	76 21	81 21	81 21	60 18	55 14	50 14	25 8	
Health Club	Customer Employee	53 4	65% 75%	34 3	24 2	14 2	14 2	24 2	24 2	28 2	21 2	24 2	24 2	24 2	28 3	31 3	34 3	31 2	28 2	24 1	12 1	3 1	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office Office	Visitor Employee	41 311	100% 100%	41 311	- 9	- 93	8 233	25 295	41 311	18 280	6 311	18 280	41 311	18 280	6 156	4 78	2 31	1 22	- 9	- 3	- -	- -	
Medical/Dental Office	Visitor Employee	40 15	100% 100%	40 15	- -	- 9	36 15	36 15	40 15	40 15	12 15	36 15	40 15	36 15	32 15	27 10	12 5	6 2	- -	- -	- -	- -	
		1705		1628	874	989	1,218	1,361	1,459	1,495	1,480	1,513	1,503	1,435	1,405	1,361	1,305	1,239	1,204	1,127	1,069	1,000	876

*Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.*

**Northland Newton Development - Right-Sized Parking**  
**Weekday - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

July

Land Use	User	Annual		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid	
		Peak Demand	Seasonal Factor																				
Shopping Center - Typical	Customer Employee	121 28	64% 80%	77 22	1 2	4 3	12 9	27 17	50 19	66 21	74 22	77 22	74 22	70 22	70 22	74 21	74 21	74 21	62 20	39 17	23 9	8 3	-
Fine/Casual Dining	Customer Employee	134 30	98% 100%	131 30	- -	- 6	- 15	- 23	20 27	53 27	98 27	98 27	85 27	53 23	66 30	98 30	125 30	131 30	131 30	131 30	125 30	98 26	33 11
Family Restaurant	Customer Employee	106 22	98% 100%	104 22	26 11	52 17	62 20	78 22	88 22	93 22	104 22	93 22	52 11	47 11	47 11	78 21	83 21	83 21	83 21	62 18	57 14	52 14	26 8
Health Club	Customer Employee	53 4	65% 75%	34 3	24 2	14 2	14 2	24 2	24 2	28 2	21 2	24 2	24 2	28 2	31 3	34 3	31 2	28 2	24 1	12 1	3 1	-	-
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800
Office Office	Visitor Employee	41 311	95% 95%	39 295	- 9	- 89	8 222	23 281	39 295	18 266	6 266	18 295	39 295	18 266	6 148	4 74	2 74	1 30	- 21	- 9	- 3	- -	- -
Medical/Dental Office	Visitor Employee	40 15	100% 100%	40 15	- -	- 9	36 15	36 15	40 15	40 15	12 15	36 15	40 15	40 15	36 15	32 10	27 5	12 2	6 2	- -	- -	- -	- -
		1705		1614	875	987	1,209	1,346	1,441	1,480	1,469	1,500	1,486	1,420	1,392	1,355	1,304	1,241	1,206	1,131	1,074	1,005	878

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekday - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

August

Land Use	User	Annual		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid	
		Peak Demand	Seasonal Factor																				
Shopping Center - Typical	Customer Employee	121 28	69% 80%	83 22	1 2	4 3	13 9	29 17	54 19	71 21	79 22	83 22	79 22	75 22	75 22	79 21	79 21	67 21	42 20	25 17	8 9	- 3	
Fine/Casual Dining	Customer Employee	134 30	99% 100%	133 30	- -	- 6	- 15	- 23	20 27	53 27	99 27	99 27	86 23	53 23	66 30	99 30	126 30	133 30	133 30	126 30	99 26	33 11	
Family Restaurant	Customer Employee	106 22	99% 100%	105 22	26 11	52 17	63 20	79 20	89 22	94 22	105 22	94 11	52 11	47 11	47 21	79 21	84 21	84 21	63 18	58 14	52 14	26 8	
Health Club	Customer Employee	53 4	70% 80%	37 3	26 2	15 2	15 2	28 2	26 2	30 2	22 2	26 2	26 2	30 2	33 3	37 3	33 2	30 2	26 1	13 1	4 1	- -	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office Office	Visitor Employee	41 311	95% 95%	39 295	- 9	- 89	8 222	23 281	39 295	18 266	6 266	18 295	39 295	18 266	6 148	4 74	2 74	1 30	- 21	- 9	- 3	- -	
Medical/Dental Office	Visitor Employee	40 15	100% 100%	40 15	- -	- 9	36 15	36 15	40 15	40 15	12 15	36 15	40 15	40 15	36 15	32 15	27 10	12 5	6 2	- -	- -	- -	
		1705		1625	877	988	1,212	1,351	1,448	1,488	1,477	1,510	1,494	1,427	1,399	1,364	1,314	1,251	1,216	1,139	1,079	1,007	878

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekday - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

September				Annual																			
Land Use	User	Demand	Peak Factor	Seasonal Demand	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid
Shopping Center - Typical	Customer Employee	121 28	64% 80%	77 22	1 2	4 3	12 9	27 17	50 19	66 21	74 22	77 22	74 22	70 22	70 22	74 21	74 21	74 21	62 20	39 17	23 9	8 3	- -
Fine/Casual Dining	Customer Employee	134 30	91% 100%	122 30	- -	- 6	- 15	- 23	18 27	49 27	91 27	91 27	79 27	49 23	61 30	81 30	116 30	122 30	122 30	116 30	91 26	30 11	
Family Restaurant	Customer Employee	106 22	91% 100%	96 22	24 11	48 17	58 20	72 20	82 22	87 22	96 22	87 22	48 11	43 11	43 11	72 21	77 21	77 21	58 18	53 14	48 14	24 8	
Health Club	Customer Employee	53 4	80% 90%	42 4	30 3	17 3	17 3	30 3	34 3	25 3	30 3	30 3	34 3	38 4	42 4	38 3	34 2	30 1	15 1	4 1	- -	- -	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office Office	Visitor Employee	41 311	100% 100%	41 311	- 9	- 93	8 233	25 295	41 311	18 280	6 280	18 311	41 280	18 311	6 280	4 156	2 78	1 31	- 22	- 9	- 3	- -	- -
Medical/Dental Office	Visitor Employee	40 15	100% 100%	40 15	- -	- -	36 9	36 15	40 15	40 15	12 15	36 15	40 15	40 15	36 15	32 15	27 10	12 5	6 2	- -	- -	- -	
		1705		1623	880	991	1,220	1,363	1,458	1,493	1,473	1,508	1,501	1,435	1,404	1,358	1,302	1,235	1,198	1,124	1,084	995	873

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekday - Seasonally Adjusted Parking Demand by Time of Day**  
**October**

March 2019

Land Use	User	Annual Peak Demand		Seasonal Factor	Seasonal Demand	Time of Day																						
		6:00	7:00			8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12:Mid						
Shopping Center - Typical	Customer Employee	121 28	68% 80%	80 22	1 2	4 3	12 9	28 17	52 19	68 21	76 22	80 22	76 22	72 22	72 22	76 21	76 21	76 21	64 20	40 17	24 9	8 3	-	-	-	-	-	
Fine/Casual Dining	Customer Employee	134 30	96% 100%	129 30	- -	- 6	- 15	- 23	19 27	51 27	96 27	96 27	84 27	51 23	64 30	96 30	122 30	129 30	129 30	122 30	96 26	32 11	-	-	-	-	-	
Family Restaurant	Customer Employee	106 22	96% 100%	102 22	25 11	51 17	61 20	76 20	86 22	92 22	102 22	92 22	51 11	46 11	46 11	76 21	81 21	81 21	81 21	61 18	56 14	51 14	25 8	-	-	-	-	-
Health Club	Customer Employee	53 4	85% 95%	45 4	32 3	18 3	18 3	32 3	32 3	36 3	27 3	32 3	32 3	32 3	36 3	41 4	45 4	41 3	36 2	32 1	16 1	5 1	-	-	-	-	-	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office Office	Visitor Employee	41 311	100% 100%	41 311	- 9	- 93	8 233	25 295	41 311	18 311	6 280	18 311	41 280	18 311	6 280	4 156	2 78	1 31	- 22	- 9	- 3	-	-	-	-	-	-	-
Medical/Dental Office	Visitor Employee	40 15	100% 100%	40 15	- -	- 9	36 15	36 15	40 15	40 15	12 15	36 15	40 15	40 15	36 15	32 15	27 10	12 5	6 2	- -	- -	-	-	-	-	-	-	
		1705		1641	883	995	1,224	1,370	1,467	1,504	1,488	1,523	1,513	1,444	1,414	1,372	1,317	1,251	1,213	1,137	1,075	1,004	876					

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekday - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

November																			Annual					
Land Use	User	Demand	Peak Factor	Seasonal		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid
				Demand	Factor	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid
Shopping Center - Typical	Customer Employee	121 28	72% 90%	87 25		1 3	4 4	13 10	30 19	57 21	74 24	83 25	87 25	83 25	78 25	78 25	83 24	83 24	83 24	70 23	44 19	26 10	9 4	-
Fine/Casual Dining	Customer Employee	134 30	93% 100%	125 30	-	-	-	-	19 6	50 15	93 23	93 27	81 27	50 27	62 23	93 30	118 30	125 30	125 30	125 30	118 30	93 26	31 11	
Family Restaurant	Customer Employee	106 22	93% 100%	99 22	25	49	59	74	84 20	89 22	99 22	89 22	49 11	44 11	44 11	74 21	79 21	79 21	79 21	59 18	54 14	49 14	25 8	
Health Club	Customer Employee	53 4	85% 95%	45 4	32	18	18	32	32 3	36 3	27 3	32 3	32 3	32 3	36 3	41 4	45 4	41 4	36 3	32 2	16 1	5 1	-	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office Office	Visitor Employee	41 311	100% 100%	41 311	-	-	8 9	25 93	41 233	18 295	6 311	18 280	41 311	18 280	6 156	4 78	2 31	1 22	- 9	- 3	- -	- -	- -	
Medical/Dental Office	Visitor Employee	40 15	100% 100%	40 15	-	-	36 9	36 15	40 15	40 15	12 15	36 15	40 15	36 15	32 15	27 10	12 5	6 2	- -	- -	- -	- -		
		1705		1643	884	994	1,224	1,372	1,472	1,509	1,492	1,527	1,518	1,450	1,419	1,377	1,321	1,255	1,216	1,137	1,072	1,001	875	

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekday - Seasonally Adjusted Parking Demand by Time of Day**  
**December**

March 2019

Land Use	User	Annual																						
		Peak Demand	Seasonal Factor	Seasonal Demand	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid	
Shopping Center - Typical	Customer Employee	121 28	100% 100%	121 28	1 3	6 4	18 11	36 21	67 24	91 27	109 28	121 28	121 28	115 28	103 27	97 27	91 27	79 25	61 21	36 11	12 4	- -		
Fine/Casual Dining	Customer Employee	134 30	100% 100%	134 30	- -	- 6	- 15	- 23	20 27	54 27	101 27	101 27	87 27	54 23	67 30	101 30	127 30	134 30	134 30	127 30	101 26	34 11		
Family Restaurant	Customer Employee	106 22	100% 100%	106 22	27 11	53 17	64 20	80 20	90 22	95 22	106 22	95 11	53 11	48 11	48 21	80 21	85 21	85 21	85 18	64 14	58 14	53 8		
Health Club	Customer Employee	53 4	95% 100%	50 4	35 3	20 3	20 3	35 3	35 3	40 3	30 3	35 3	35 3	35 3	40 3	45 4	50 4	45 3	40 2	35 1	18 1	5 1		
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800		
Office Office	Visitor Employee	41 311	100% 100%	41 311	- 9	- 93	8 233	25 295	41 311	18 311	6 280	18 280	41 311	18 280	6 156	4 78	2 31	1 22	- 9	- 3	- -	- -		
Medical/Dental Office	Visitor Employee	40 15	100% 100%	40 15	- -	- 9	36 15	36 15	40 15	40 15	12 15	36 15	40 15	36 15	32 15	27 10	12 5	6 2	- -	- -	- -	- -		
		1705		1702	889	1,002	1,237	1,389	1,495	1,543	1,539	1,581	1,572	1,507	1,472	1,418	1,358	1,285	1,246	1,173	1,098	1,016	880	

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

**January**

Land Use	User	Annual																					
		Peak Demand	Seasonal Factor	Seasonal Demand	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid
Shopping Center - Typical	Customer Employee	167 32	56% 80%	94 26	1 3	5 4	9 10	28 19	47 22	61 24	75 26	84 26	94 26	89 26	84 24	75 22	70 20	61 19	47 17	33 12	14 4	-	
Fine/Casual Dining	Customer Employee	187 33	85% 95%	159 31	- 6	- 9	- 19	- 24	- 24	24 24	79 24	87 24	72 24	72 24	95 31	143 31	151 31	159 31	143 31	143 31	143 27	79 16	
Family Restaurant	Customer Employee	187 33	85% 95%	159 31	16 16	40 24	72 28	111 31	143 31	143 31	159 31	135 31	103 20	64 20	72 20	95 30	111 30	111 30	103 25	48 20	40 20	24 11	
Health Club	Customer Employee	56 3	100% 100%	56 3	45 2	25 2	20 2	28 2	20 2	28 2	28 2	17 2	14 2	17 2	31 2	56 3	53 3	34 2	17 2	6 1	1 1	-	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office Office	Visitor Employee	5 52	100% 100%	5 52	- 10	1 31	3 42	4 47	5 52	5 47	4 42	3 31	2 21	1 10	1 5	1 3	- -	- -	- -	- -	- -	- -	
Medical/Dental Office	Visitor Employee	50 25	100% 100%	50 25	- - - 15	45 25	45 25	50 25	50 25	15 25	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -		
		1630		1491	883	917	1,044	1,151	1,216	1,269	1,316	1,252	1,189	1,142	1,147	1,224	1,271	1,249	1,222	1,118	1,081	1,034	922

*Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.*

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

Land Use	User	Annual Peak Demand		Seasonal Factor	Seasonal Demand		6:00		7:00		8:00		9:00		10:00		11:00		Noon	1:00		2:00		3:00		4:00		5:00		6:00		7:00		8:00		9:00		10:00		11:00		12Mid	
		Customer	Employee		Customer	Employee	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid																		
Shopping Center - Typical	Customer Employee	167 32	57% 80%	95 26	1 3	5 4	10 10	29 19	48 22	62 24	76 26	86 26	95 26	95 26	90 26	86 24	76 22	71 20	62 19	48 17	33 12	14 4	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -										
Fine/Casual Dining	Customer Employee	187 33	86% 95%	161 31	- -	- 6	- 9	- 19	- 24	- 24	24 24	80 24	88 24	72 24	72 24	96 31	145 31	153 31	161 31	145 31	145 31	145 31	80 27	- 16	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -									
Family Restaurant	Customer Employee	187 33	86% 95%	161 31	16 16	40 24	72 28	113 28	145 31	145 31	161 31	137 31	105 20	64 20	72 20	96 30	113 30	113 30	105 30	48 30	40 30	24 25	16 20	- 20	11 11	- -																	
Health Club	Customer Employee	56 3	95% 100%	53 3	43 2	24 2	19 2	27 2	19 2	27 2	27 2	16 2	13 2	16 2	29 2	53 3	51 3	32 2	16 2	5 1	1 1	1 1	1 1	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -									
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800							
Office Office	Visitor Employee	5 52	100% 100%	5 52	- -	1 10	3 31	4 42	5 47	5 52	5 47	4 42	3 31	2 21	1 10	1 5	1 3	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -									
Medical/Dental Office	Visitor Employee	50 25	100% 100%	50 25	- -	- 15	45 25	45 25	50 25	50 25	15 25	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -									
		1630		1493	881	916	1,044	1,153	1,218	1,271	1,319	1,256	1,191	1,142	1,146	1,225	1,274	1,252	1,226	1,120	1,083	1,036	923																				

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

March

Land Use	User	Annual		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid	
		Peak Demand	Seasonal Factor																				
Shopping Center - Typical	Customer Employee	167 32	64% 80%	107 26	1 3	5 4	11 10	32 19	53 22	69 24	86 26	96 26	107 26	102 26	96 24	86 22	80 20	59 19	53 17	37 12	16 4	-	
Fine/Casual Dining	Customer Employee	187 33	95% 100%	178 33	- -	- 7	- 10	- 20	- 25	27 25	89 25	98 25	80 25	80 25	107 33	160 33	169 33	178 33	160 33	160 33	160 28	89 17	
Family Restaurant	Customer Employee	187 33	95% 100%	178 33	18 17	44 25	80 30	124 30	160 33	160 33	178 33	151 33	115 21	71 21	80 21	107 31	124 31	124 31	115 26	53 21	44 21	27 21	18 12
Health Club	Customer Employee	56 3	85% 95%	48 3	38 1	21 1	17 1	24 1	17 1	24 1	14 1	12 1	14 1	12 2	14 3	26 3	48 3	45 3	29 2	14 1	5 1	- 1	- 1
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office Office	Visitor Employee	5 52	100% 100%	5 52	- 10	1 31	3 42	4 47	5 52	5 47	4 42	3 31	2 21	1 10	1 5	1 3	- -	- -	- -	- -	- -	- -	
Medical/Dental Office	Visitor Employee	50 25	100% 100%	50 25	- -	- 15	45 25	45 25	50 25	50 25	15 25	- -											
		1630		1536	878	918	1,053	1,168	1,238	1,295	1,354	1,290	1,221	1,168	1,173	1,255	1,307	1,288	1,260	1,148	1,108	1,057	936

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

April

Land Use	User	Annual		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid	
		Peak Demand	Seasonal Factor																				
Shopping Center - Typical	Customer Employee	167 32	63% 80%	105 26	1 3	5 4	11 10	32 19	53 22	68 24	84 26	95 26	105 26	100 26	95 24	84 22	79 20	68 19	53 17	37 12	16 4	-	
Fine/Casual Dining	Customer Employee	187 33	92% 100%	172 33	- -	- 7	- 10	- 20	- 25	26 25	86 25	95 25	77 25	77 25	103 33	155 33	163 33	172 33	155 33	155 33	155 33	86 17	
Family Restaurant	Customer Employee	187 33	92% 100%	172 33	17 17	43 25	77 30	120 30	155 33	155 33	172 33	146 33	112 21	69 21	77 21	103 31	120 31	120 31	112 31	52 26	43 21	26 21	17 12
Health Club	Customer Employee	56 3	70% 80%	39 2	31 1	18 1	14 1	20 1	14 1	20 1	12 1	10 1	12 1	22 2	39 2	37 2	24 2	12 1	4 -	- -	- -	- -	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office Office	Visitor Employee	5 52	100% 100%	5 52	- -	1 10	3 31	4 42	5 47	5 52	4 47	4 42	3 31	2 21	1 10	1 5	1 3	- -	- -	- -	- -	- -	
Medical/Dental Office	Visitor Employee	50 25	100% 100%	50 25	- -	- 15	45 25	45 25	50 25	50 25	15 25	- -	- -										
		1630		1514	870	914	1,047	1,158	1,230	1,284	1,339	1,279	1,211	1,159	1,161	1,236	1,287	1,272	1,248	1,140	1,101	1,050	932

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

## **Northland Newton Development - Right-Sized Parking Weekend - Seasonally Adjusted Parking Demand by Time of Day**

March 2010

May		Annual Peak Demand		Seasonal Factor	Seasonal Demand	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12:Mid
Land Use	User	Customer	Employee																					
Shopping Center - Typical	Customer	167	66%	110	1	6	11	33	55	72	88	99	110	110	105	99	88	83	72	55	39	17	-	
	Employee	32	80%	26	3	4	10	19	22	24	26	26	26	26	24	22	20	19	17	12	4	-		
Fine/Casual Dining	Customer	187	96%	180	-	-	-	-	-	27	90	99	81	81	81	108	162	171	180	162	162	90		
	Employee	33	100%	33	-	7	10	20	25	25	25	25	25	25	25	33	33	33	33	33	33	28		
Family Restaurant	Customer	187	96%	180	18	45	81	126	162	162	180	153	117	72	81	108	126	126	117	54	45	27	18	
	Employee	33	100%	33	17	25	30	30	33	33	33	33	21	21	21	31	31	31	31	26	21	21	12	
Health Club	Customer	56	65%	36	29	16	13	18	13	18	18	11	9	11	20	36	35	22	11	4	-	-	-	
	Employee	3	75%	2	1	1	1	1	1	1	1	1	1	1	2	2	2	2	1	-	-	-	-	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office	Visitor	5	100%	5	-	1	3	4	5	5	5	4	3	2	1	1	-	-	-	-	-	-	-	
Office	Employee	52	100%	52	-	10	31	42	47	52	47	42	31	21	10	5	3	-	-	-	-	-	-	
Medical/Dental Office	Visitor	50	100%	50	-	-	45	45	50	50	15	-	-	-	-	-	-	-	-	-	-	-	-	
	Employee	25	100%	25	-	-	15	25	25	25	25	-	-	-	-	-	-	-	-	-	-	-	-	
		1630		1532	869	915	1,050	1,163	1,238	1,294	1,353	1,293	1,224	1,170	1,172	1,247	1,302	1,288	1,264	1,151	1,112	1,059	937	

*Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.*

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

June

Land Use	User	Annual Peak Demand		Seasonal Factor	Seasonal Demand		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid
		Customer	Employee		67%	112	1	6	11	34	56	73	90	101	112	112	106	101	90	84	73	56	39	17	4
Shopping Center - Typical	Customer Employee	167	80%	67%	112	1	6	11	34	56	73	90	101	112	112	106	101	90	84	73	56	39	17	4	
Fine/Casual Dining	Customer Employee	187	100%	95%	178	-	-	-	-	-	27	89	98	80	80	80	80	107	160	169	178	160	160	160	89
Family Restaurant	Customer Employee	187	100%	95%	178	18	44	80	124	160	160	178	151	115	71	80	107	124	124	115	53	44	27	18	12
Health Club	Customer Employee	56	75%	65%	36	29	16	13	18	13	18	18	11	9	11	20	36	35	22	11	4	-	-	-	-
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800
Office Office	Visitor Employee	5	100%	5	-	1	3	4	5	5	5	4	3	2	1	1	-	-	-	-	-	-	-	-	-
Medical/Dental Office	Visitor Employee	50	100%	50	-	-	45	45	50	50	15	-	-	-	-	-	-	-	-	-	-	-	-	-	-
		1630		1529	869	914	1,049	1,162	1,237	1,293	1,352	1,292	1,223	1,170	1,171	1,247	1,300	1,285	1,261	1,149	1,109	1,057	936		

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

July

Land Use	User	Annual		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid	
		Peak Demand	Seasonal Factor																				
Shopping Center - Typical	Customer Employee	167 32	64% 80%	107 26	1 3	5 4	11 10	32 19	53 22	69 24	86 26	96 26	107 26	102 26	96 24	86 22	80 20	69 19	53 17	37 12	16 4	-	
Fine/Casual Dining	Customer Employee	187 33	98% 100%	183 33	- -	- 7	- 10	- 20	- 25	27 25	92 25	101 25	82 25	82 25	82 25	110 33	165 33	174 33	183 33	165 33	165 33	92 17	
Family Restaurant	Customer Employee	187 33	98% 100%	183 33	18 17	46 25	82 30	128 30	165 33	165 33	183 33	156 33	119 21	73 21	82 21	110 31	128 31	128 31	119 31	55 28	46 21	27 21	18 12
Health Club	Customer Employee	56 3	65% 75%	36 2	29 1	16 1	13 1	18 1	13 1	18 1	18 1	11 1	9 1	11 1	20 2	36 2	35 2	22 2	11 1	4 -	-	-	-
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800
Office	Visitor	5	95%	5	-	1	3	4	4	5	4	4	3	2	1	-	-	-	-	-	-	-	-
Office	Employee	52	95%	49	-	10	30	40	44	49	44	40	30	20	10	5	2	-	-	-	-	-	-
Medical/Dental Office	Visitor	50	100%	50	-	-	45	45	50	50	15	-	-	-	-	-	-	-	-	-	-	-	-
	Employee	25	100%	25	-	-	15	25	25	25	-	-	-	-	-	-	-	-	-	-	-	-	-
		1630		1533	869	915	1,050	1,162	1,235	1,291	1,352	1,293	1,223	1,168	1,171	1,247	1,304	1,290	1,266	1,153	1,114	1,061	939

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

August

Land Use	User	Annual		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid	
		Peak Demand	Seasonal Factor																				
Shopping Center - Typical	Customer Employee	167	69%	115	1	5	12	35	58	75	92	104	115	109	104	92	86	75	58	40	17	-	
		32	80%	26	3	4	10	19	22	24	26	26	26	26	24	22	20	19	17	12	4	-	
Fine/Casual Dining	Customer Employee	187	99%	185	-	-	-	-	-	28	93	102	83	83	83	111	167	176	185	167	167	93	
		33	100%	33	-	7	10	20	25	25	25	25	25	25	25	33	33	33	33	33	33	17	
Family Restaurant	Customer Employee	187	99%	185	19	46	83	130	167	167	185	157	120	74	83	111	130	130	120	56	46	28	19
		33	100%	33	17	25	30	30	33	33	33	33	21	21	31	31	31	31	26	21	21	12	
Health Club	Customer Employee	56	70%	39	31	18	14	20	14	20	20	12	10	12	22	39	37	24	12	4	-	-	
		3	80%	2	1	1	1	1	1	1	1	1	1	1	2	2	2	1	-	-	-	-	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office Office	Visitor Employee	5	95%	5	-	1	3	4	4	5	4	4	3	2	1	-	-	-	-	-	-	-	
		52	95%	49	-	10	30	40	44	49	44	40	30	20	10	5	2	-	-	-	-	-	
Medical/Dental Office	Visitor Employee	50	100%	50	-	-	45	45	50	50	15	-	-	-	-	-	-	-	-	-	-	-	
		25	100%	25	-	-	15	25	25	25	-	-	-	-	-	-	-	-	-	-	-	-	
		1630		1548	872	918	1,053	1,169	1,243	1,302	1,363	1,304	1,234	1,179	1,182	1,260	1,316	1,302	1,276	1,161	1,119	1,065	941

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**  
**September**

March 2019

Land Use	User	Annual Peak Seasonal Demand			6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid
		Demand	Factor	Seasonal Demand	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid
Shopping Center - Typical	Customer Employee	167 32	64% 80%	107 26	1	5	11	32	53	69	86	96	107	107	102	96	86	80	69	53	37	16	
Fine/Casual Dining	Customer Employee	187 33	91% 100%	170 33	-	-	-	-	-	26	85	94	77	77	77	102	153	162	170	153	153	85	
Family Restaurant	Customer Employee	187 33	91% 100%	170 33	17	43	77	119	153	153	170	145	111	68	77	102	119	119	111	51	43	26	
Health Club	Customer Employee	56 3	80% 90%	45 3	36	20	16	22	16	22	22	13	11	13	25	45	43	27	13	4	-	-	
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office	Visitor Employee	5 52	100% 100%	5 62	-	1	3	4	5	5	5	4	3	2	1	1	-	-	-	-	-	-	
Medical/Dental Office	Visitor Employee	50 25	100% 100%	50 25	-	-	45	45	50	50	15	-	-	-	-	-	-	-	-	-	-	-	
		1630		1518	875	916	1,049	1,159	1,230	1,285	1,340	1,279	1,213	1,161	1,166	1,242	1,293	1,274	1,247	1,138	1,100	1,049	931

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**  
**October**

March 2019

Land Use	User	Annual																					
		Peak Demand	Seasonal Factor	Seasonal Demand	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid
Shopping Center - Typical	Customer Employee	167 32	66% 80%	110 26	1 3	6 4	11 10	33 19	55 22	72 24	88 26	88 26	110 26	105 26	99 24	88 22	83 20	72 19	55 17	39 12	17 4	-	
Fine/Casual Dining	Customer Employee	187 33	96% 100%	180 33	- -	- 7	- 10	- 20	- 25	27 25	90 25	99 25	81 25	81 25	108 33	162 33	171 33	180 33	162 33	162 33	162 33	90 17	
Family Restaurant	Customer Employee	187 33	96% 100%	180 33	18 17	45 25	81 30	126 30	162 33	162 33	180 33	153 33	117 21	72 21	81 31	108 31	126 31	126 31	117 31	54 26	45 21	27 21	18 12
Health Club	Customer Employee	56 3	85% 95%	48 3	38 1	21 1	17 1	24 1	17 1	24 1	24 1	14 1	12 1	14 1	14 2	28 3	48 3	45 2	29 1	14 1	5 1	- 1	- 1
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	
Office	Visitor Employee	5 52	100% 100%	5 52	- -	1 10	3 31	4 42	5 47	5 52	5 47	4 42	3 31	2 21	1 10	1 5	1 3	- -	- -	- -	- -	- -	-
Medical/Dental Office	Visitor Employee	50 25	100% 100%	50 25	- -	- 15	45 25	45 25	50 25	50 25	15 25	- -	- -										
		1630		1543	878	920	1,054	1,169	1,242	1,300	1,359	1,296	1,227	1,173	1,178	1,260	1,313	1,295	1,267	1,153	1,113	1,060	937

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**

March 2019

November				Annual		Peak		Seasonal Factor		Seasonal Demand		6:00		7:00		8:00		9:00		10:00		11:00		Noon		1:00		2:00		3:00		4:00		5:00		6:00		7:00		8:00		9:00		10:00		11:00		12Mid	
Shopping Center - Typical	Customer Employee	167 32	72% 90%	120 29	1 3	6 4	12 12	36 22	60 24	78 27	96 29	108 29	120 29	114 29	108 27	86 24	90 23	78 22	60 19	42 13	18 4	- -	- -																										
Fine/Casual Dining	Customer Employee	187 33	93% 100%	174 33	- -	- 7	- 10	- 20	- 25	26 25	87 25	96 25	78 25	78 25	78 25	104 33	157 33	165 33	174 33	157 33																													
Family Restaurant	Customer Employee	187 33	93% 100%	174 33	17 17	43 25	78 30	122 30	157 33	157 33	174 33	148 33	113 21	70 21	78 21	104 31	122 31	122 31	113 31	52 26	43 26	26 21	17 21	17 21																									
Health Club	Customer Employee	56 3	85% 95%	48 3	38 1	21 1	17 1	24 1	17 1	24 1	24 1	14 1	12 1	14 1	26 2	48 3	45 3	29 2	14 1	5 1	- 1																												
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800											
Office	Visitor Employee	5 52	100% 100%	5 52	- -	1 10	3 31	4 42	5 47	5 52	5 47	4 42	3 31	2 21	1 10	1 5	1 3	- -																															
Medical/Dental Office	Visitor Employee	50 25	100% 100%	50 25	- -	- 15	45 25	45 25	50 25	50 25	15 25	- -																																					
		1630		1545	877	918	1,054	1,171	1,244	1,303	1,361	1,300	1,233	1,181	1,184	1,264	1,314	1,295	1,266	1,153	1,110	1,055	933																										

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**  
**December**

March 2019

Land Use	User	Annual																						
		Peak Demand	Seasonal Factor	Seasonal Demand	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mid	
Shopping Center - Typical	Customer Employee	167 32	100% 100%	187 32	2 3	8 5	17 13	58 24	100 27	117 30	142 32	159 32	167 32	159 32	150 30	134 27	125 26	109 24	84 21	58 14	25 5	- -		
Fine/Casual Dining	Customer Employee	187 33	100% 100%	187 33	- 7	- 10	- 20	- 25	- 25	28 25	94 25	103 25	84 25	84 25	112 33	168 33	178 33	187 33	168 33	168 33	168 33	94 28		
Family Restaurant	Customer Employee	187 33	100% 100%	187 33	19 17	47 25	84 30	131 30	168 33	187 33	159 33	122 21	75 21	84 21	112 31	131 31	131 31	122 26	56 21	47 21	28 21	19 12		
Health Club	Customer Employee	56 3	90% 100%	50 3	40 2	23 2	18 2	25 2	18 2	25 2	25 2	15 2	13 2	15 2	28 3	50 3	48 3	30 2	15 2	5 1	1 1	- -		
Residential		800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800		
Office	Visitor Employee	5 52	100% 100%	5 52	- -	1 10	3 31	4 42	5 47	5 52	4 47	3 42	2 31	1 21	1 10	1 5	1 3	- -	- -	- -	- -	- -		
Medical/Dental Office	Visitor Employee	50 25	100% 100%	50 25	- -	- 15	45 25	45 25	50 25	50 25	15 25	- -												
		1630		1624	883	928	1,068	1,206	1,300	1,360	1,432	1,374	1,300	1,244	1,246	1,327	1,378	1,356	1,323	1,194	1,143	1,077	942	

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

## **Exhibit D**



To: Kent Gonzales  
Northland Development

Date: April 16, 2019

## Memorandum

Project #: 12239.00

From: Randall C. Hart, Principal  
Matthew Duranleau, EIT

Re: Response to Transportation Peer Review  
Memo Dated April 3, 2019  
The Northland Newton Development  
Newton, Massachusetts

---

VHB has prepared the following response to comments received on April 3, 2019, from BETA Group. The comments received from BETA Group were in response to the *Expanded Revised Building Program Traffic Generation Memo* by VHB dated March 28, 2019, and the *Right-Sized Parking Memo* by VHB dated March 27, 2019. For ease of review the comments that were received are outlined below along with the responses.

### Trip Generation

*Comment 1: In Table 2 – Project Trip Generation – ITE Unadjusted Vehicle Trips, the weekday morning peak hour unadjusted vehicle trips is shown as 668 trips. BETA has calculated the number of unadjusted vehicle trips in the weekday morning peak hour to be 592 trips. Please confirm and recalculate Build Condition vehicle trips.*

**Response:** VHB rechecked the calculations for the Build Conditions unadjusted weekday morning vehicle trips and has confirmed that number to be 668 vehicle trips. The unadjusted vehicle trips are based on the ITE land use code regression equations for each proposed land use. The ITE trip generation worksheets for each land use are included in the Attachments to this memorandum.

*Comment 2: Please provide the mode share and internal capture trip generation adjustment calculations.*

**Response:** The mode share and internal capture trip generation adjustment calculations are included in the Attachments to this memorandum.

*Comment 3: In Table 8 – Project-Generated Peak-Hour Vehicle Trips by Use – Build Condition with Robust Shuttle Service, the vehicle trip numbers under the residential, office, retail, and pass-by columns are not correct. They are the same numbers shown in Table 6 – Project-Generated Peak-Hour Vehicle Trips by Use – Build Conditions with Existing Mode Share. The numbers in this table should be updated.*

**Response:** Table 8 has been updated with the correct numbers for residential, office, retail, and pass-by vehicle trips based on the Robust Shuttle service scenario and is provided below:

101 Walnut Street  
PO Box 9151  
Watertown, MA 02472-4026  
P 617.924.1770

**Table 8 Project-Generated Peak-Hour Vehicle Trips by Use – Build Condition with Robust Shuttle Service**

	Residential <sup>a</sup>	Office <sup>b</sup>	Retail <sup>c</sup>	Pass-By <sup>d</sup>	Total Net Vehicle Trips <sup>e</sup>	Existing Vehicle Trips <sup>f</sup>	Total Net New Vehicle Trips
<b>Weekday Morning</b>							
Enter	40	95	89	22	224	221	3
<u>Exit</u>	<u>115</u>	<u>12</u>	<u>45</u>	<u>22</u>	<u>172</u>	<u>56</u>	<u>116</u>
Total	155	107	134	44	396	277	119
<b>Weekday Evening</b>							
Enter	63	10	140	75	213	120	93
<u>Exit</u>	<u>46</u>	<u>79</u>	<u>149</u>	<u>75</u>	<u>274</u>	<u>248</u>	<u>26</u>
Total	109	89	289	150	487	368	119
<b>Saturday Midday</b>							
Enter	55	20	216	70	291	186	105
<u>Exit</u>	<u>67</u>	<u>21</u>	<u>179</u>	<u>70</u>	<u>267</u>	<u>163</u>	<u>104</u>
Total	122	41	395	140	558	349	209

Note: Table 8 only presents the Project-generated vehicle trips. The Project-generated transit trips and walk/bike trips are presented in Table 7.

a New vehicle trips with internal capture and mode share credits applied.

b New vehicle trips with internal capture and mode share credits applied.

c New vehicle trips with internal capture, mode share, and pass-by credits applied.

d Pass-by Credits of 25%, 34%, and 26% applied to weekday morning, weekday evening, and Saturday midday peak hour retail trip generation, respectively.

e Sum of columns a through c.

f Net vehicle trips that can be generated by the Site under existing conditions (from Table 3).

## Parking

*Comment 4: Please provide the shared-parking calculations by hour for both weekday and weekend.*

Response: The shared-parking calculations for both weekday and weekend for the month of December are included in the Attachments to this memorandum.

*Comment 5: The following is a summary comparing the proposed project parking spaces by use with the MBTA/MassDOT Transit-Oriented Development Policies and Guidelines.*

- The 800 residential spaces (1 space/unit) meet the MBTA/MassDOT TOD guideline of 0.75-1.5 spaces/unit.
- The 149 retail spaces (3 spaces/KSF) meets the guideline of 1.5-3.0/KSF.
- The 245 restaurant spaces (6.1 spaces/KSF) exceed the retail guideline of 1.5-3.0/KSF. However, the guidelines do not break out restaurants.
- The 51 medical office spaces (3.4 spaces/KSF) exceed the office guideline of between 1.0 and 2.5 spaces/KSF. However, medical office parking demand is typically higher than general office use.

- *The 38 health club spaces (3.8 spaces/KSF) exceed the retail guideline of 1.5-3.0/KSF, but not significantly so and they are relatively few spaces.*
- *The office use has 298 spaces with a rate of 1.7 spaces/KSF, which meet the guidelines between 1.0 and 2.5 spaces/KSF.*
- *The proposed 1,550 parking spaces will meet demand, except for the peak December shopping season (1,596 vehicles). The option to use a portion of the residential spaces for shared-parking, if needed, appears reasonable.*
- *Overall, the proposed 1,550 parking spaces appear adequate to accommodate parking demand for the mix of land uses in a shared-parking operation.*

**Response:** No response needed.

## Attachments

- Trip Generation Calculations
- Shared Parking Calculations

---

**Trip Generation Calculations**

**ITE TRIP GENERATION WORKSHEET**  
**(10th Edition, Updated 2017)**

**PROPOSED**

LANDUSE: Mid-Rise Residential  
 LANDUSE CODE: 221  
 SETTING/LOCATION: General Urban/Suburban  
 JOB NAME:  
 JOB NUMBER:

Independent Variable --- Number of Units

800 units

**WEEKDAY**

RATES:			Total Trip Ends			Independent Variable Range			Directional Distribution	
	# Studies	R^2	Average	Low	High	Average	Low	High	Enter	Exit
DAILY	27	0.77	5.44	1.27	12.50	205	21	494	50%	50%
AM PEAK OF GENERATOR	48	0.69	0.32	0.06	0.77	225	21	1,168	27%	73%
PM PEAK OF GENERATOR	47	0.66	0.41	0.09	1.26	211	21	1,168	60%	40%
AM PEAK (ADJACENT ST)	53	0.67	0.36	0.06	1.61	207	26	703	26%	74%
PM PEAK (ADJACENT ST)	60	0.72	0.44	0.15	1.11	208	26	703	61%	39%

TRIPS:

BY AVERAGE			BY REGRESSION		
Total	Enter	Exit	Total	Enter	Exit
4,352	2,176	2,176	4,358	2,179	2,179
288	75	213	263	68	194
352	215	137	326	199	127

**SATURDAY**

RATES:			Total Trip Ends			Independent Variable Range			Directional Distribution	
	# Studies	R^2	Average	Low	High	Average	Low	High	Enter	Exit
DAILY	6	0.73	4.91	4.03	8.51	224	111	336	50%	50%
PEAK OF GENERATOR	8	0.89	0.44	0.34	0.73	264	111	462	49%	51%

TRIPS:

BY AVERAGE			BY REGRESSION		
Total	Enter	Exit	Total	Enter	Exit
3,928	1,964	1,964	2,849	1,425	1,425
352	172	180	343	168	175

**SUNDAY**

RATES:			Total Trip Ends			Independent Variable Range			Directional Distribution	
	# Studies	R^2	Average	Low	High	Average	Low	High	Enter	Exit
DAILY	6	--	4.09	3.06	8.41	224	111	336	50%	50%
PEAK OF GENERATOR	6	--	0.39	0.26	1.07	224	111	336	62%	38%

TRIPS:

BY AVERAGE			BY REGRESSION		
Total	Enter	Exit	Total	Enter	Exit
3,272	1,636	1,636	N/A	N/A	N/A
312	193	119	NA	NA	NA

**ITE TRIP GENERATION WORKSHEET**  
*(10th Edition, Updated 2017)*

**PROPOSED**

LANDUSE: Shopping Center  
 LANDUSE CODE: 820  
 SETTING/LOCATION: General Urban/Suburban  
 JOB NAME:  
 JOB NUMBER:

Independent Variable --

FLOOR AREA (KSF): 115.0

**WEEKDAY**

RATES:			Total Trip Ends						Independent Variable Range			Directional Distribution	
	# Studies	R^2	Average	Low	High	Average	Low	High	Enter	Exit			
DAILY	147	0.76	37.75	7.42	207.98	453	9	1,510	50%	50%			
AM PEAK OF GENERATOR	47	0.71	3.00	0.70	23.74	323	8	1,320	54%	46%			
PM PEAK OF GENERATOR	53	0.76	4.21	0.78	27.27	298	7	1,320	50%	50%			
AM PEAK (ADJACENT ST)	84	0.90	0.94	0.18	23.74	351	9	1,510	62%	38%			
PM PEAK (ADJACENT ST)	261	0.82	3.81	0.74	18.69	327	2	2,200	48%	52%			

**TRIPS:**

	DAILY	BY AVERAGE			BY REGRESSION		
		Total	Enter	Exit	Total	Enter	Exit
AM PEAK (ADJACENT ST)		4,341	2,171	2,171	6,611	3,306	3,306
PM PEAK (ADJACENT ST)		108	67	41	209	130	80
		438	210	228	603	289	313

**SATURDAY**

RATES:			Total Trip Ends						Independent Variable Range			Directional Distribution	
	# Studies	R^2	Average	Low	High	Average	Low	High	Enter	Exit			
DAILY	58	0.71	46.12	13.07	167.89	602	56	1,510	50%	50%			
PEAK OF GENERATOR	119	0.87	4.50	1.42	15.10	416	4	1,510	52%	48%			

**TRIPS:**

	DAILY	BY AVERAGE			BY REGRESSION		
		Total	Enter	Exit	Total	Enter	Exit
PEAK OF GENERATOR		5,304	2,652	2,652	9,719	4,860	4,860
		518	269	248	691	359	332

**SUNDAY**

RATES:			Total Trip Ends						Independent Variable Range			Directional Distribution	
	# Studies	R^2	Average	Low	High	Average	Low	High	Enter	Exit			
DAILY	30	-	21.10	4.15	148.15	509	47	1,510	50%	50%			
PEAK OF GENERATOR	24	-	2.79	0.39	12.40	382	47	1,268	49%	51%			

**TRIPS:**

	DAILY	BY AVERAGE			BY REGRESSION		
		Total	Enter	Exit	Total	Enter	Exit
PEAK OF GENERATOR		2,427	1,213	1,213	N/A	N/A	N/A
		321	157	164	N/A	N/A	N/A

**ITE TRIP GENERATION WORKSHEET**  
*(10th Edition, Updated 2017)*

**PROPOSED**

**LANDUSE:** General Office Building  
**LANDUSE CODE:** 710  
**SETTING/LOCATION:** General Urban/Suburban  
**JOB NAME:**  
**JOB NUMBER:**

Independent Variable ---

**FLOOR AREA (KSF):** 180

**WEEKDAY**

RATES:			Total Trip Ends						Independent Variable Range			Directional Distribution	
	# Studies	R^2	Average	Low	High	Average	Low	High	Enter	Exit			
DAILY	66	0.83	9.74	2.71	27.56	171	6	1,300	50%	50%			
AM PEAK OF GENERATOR	228	0.84	1.47	0.57	4.93	209	6	2,408	88%	12%			
PM PEAK OF GENERATOR	243	0.82	1.42	0.49	6.20	205	6	2,408	18%	82%			
AM PEAK (ADJACENT ST)	35	0.85	1.16	0.37	4.23	117	5	511	86%	14%			
PM PEAK (ADJACENT ST)	32	0.88	1.15	0.47	3.23	114	6	511	16%	84%			

TRIPS:

BY AVERAGE			BY REGRESSION			
Total	Enter	Exit	Total	Enter	Exit	
<b>DAILY</b>	<b>1,753</b>	<b>877</b>	<b>877</b>	<b>1,877</b>	<b>938</b>	<b>938</b>
AM PEAK (ADJACENT ST)	209	180	29	196	168	27
PM PEAK (ADJACENT ST)	207	33	174	199	32	167

**SATURDAY**

RATES:			Total Trip Ends						Independent Variable Range			Directional Distribution	
	# Studies	R^2	Average	Low	High	Average	Low	High	Enter	Exit			
DAILY	5	--	2.21	1.24	7.46	94	28	183	50%	50%			
PEAK OF GENERATOR	3	--	0.53	0.30	1.57	82	28	183	54%	46%			

TRIPS:

BY AVERAGE			BY REGRESSION			
Total	Enter	Exit	Total	Enter	Exit	
<b>DAILY</b>	<b>398</b>	<b>199</b>	<b>199</b>	<b>N/A</b>	<b>N/A</b>	<b>N/A</b>
PEAK OF GENERATOR	95	52	44	N/A	N/A	N/A

**SUNDAY**

RATES:			Total Trip Ends						Independent Variable Range			Directional Distribution	
	# Studies	R^2	Average	Low	High	Average	Low	High	Enter	Exit			
DAILY	5	--	0.70	0.19	3.05	94	28	183	50%	50%			
PEAK OF GENERATOR	3	--	0.21	0.11	0.68	82	28	183	58%	42%			

TRIPS:

BY AVERAGE			BY REGRESSION			
Total	Enter	Exit	Total	Enter	Exit	
<b>DAILY</b>	<b>126</b>	<b>63</b>	<b>63</b>	<b>N/A</b>	<b>N/A</b>	<b>N/A</b>
PEAK OF GENERATOR	38	22	16	N/A	N/A	N/A

The Northland Newton Development  
12239.00

## **PROPOSED SHARED PERSON TRIPS - WEEKDAY**

WEEKDAY DAILY					WEEKDAY MORNING					WEEKDAY EVENING				
RETAIL		%	#	BALANCED	%	#	BALANCED	%	#	BALANCED	%	#	BALANCED	%
EXIT ->	ENTER -<	2%	5,884	159	1,060	15%	11	33	190	4%	558	11	36	21%
		4%	5,884	233	1,060	22%	231	9	31	28%	515	38	189	20%
OFFICE		> ENTER			> ENTER			> ENTER			> ENTER			OFFICE
RESIDENTIAL		<- EXIT			<- EXIT			<- EXIT			<- EXIT			RESIDENTIAL
WEEKDAY DAILY					WEEKDAY MORNING					WEEKDAY EVENING				
RETAIL		%	#	BALANCED	%	#	BALANCED	%	#	BALANCED	%	#	BALANCED	%
EXIT ->	ENTER -<	2%	5,884	1,133	2,462	49%	2	77	77	26%	558	104	225	26%
		10%	5,884	588	2,462	42%	231	2	220	1%	515	52	144	4%
RESIDENTIAL		> ENTER			> ENTER			> ENTER			> ENTER			RESIDENTIAL
OFFICE		<- EXIT			<- EXIT			<- EXIT			<- EXIT			OFFICE
WEEKDAY DAILY					WEEKDAY MORNING					WEEKDAY EVENING				
OFFICE		%	#	BALANCED	%	#	BALANCED	%	#	BALANCED	%	#	BALANCED	%
EXIT ->	ENTER -<	2%	1,060	21	2,462	3%	0	77	77	0%	189	4	225	2%
		10%	1,060	0	2,462	0%	190	4	220	7%	36	6	144	4%
RESIDENTIAL		> ENTER			> ENTER			> ENTER			> ENTER			RESIDENTIAL
OFFICE		<- EXIT			<- EXIT			<- EXIT			<- EXIT			OFFICE
WEEKDAY DAILY					WEEKDAY MORNING					WEEKDAY EVENING				
OFFICE		%	#	BALANCED	%	#	BALANCED	%	#	BALANCED	%	#	BALANCED	%
EXIT ->	ENTER -<	2%	1,060	21	2,462	3%	0	77	77	0%	189	4	225	2%
		10%	1,060	0	2,462	0%	190	4	220	7%	36	6	144	4%
RESIDENTIAL		> ENTER			> ENTER			> ENTER			> ENTER			RESIDENTIAL
OFFICE		<- EXIT			<- EXIT			<- EXIT			<- EXIT			OFFICE
WEEKDAY DAILY					WEEKDAY MORNING					WEEKDAY EVENING				
OFFICE		%	#	BALANCED	%	#	BALANCED	%	#	BALANCED	%	#	BALANCED	%
EXIT ->	ENTER -<	2%	1,292	2113			RETAIL	11	10	21	RETAIL	90	115	20%
		10%	1,292	2113			OFFICE	12	9	21	OFFICE	17	42	59
RESIDENTIAL		> ENTER			> ENTER			> ENTER			> ENTER			RESIDENTIAL
RESIDENTIAL		<- EXIT			<- EXIT			<- EXIT			<- EXIT			RESIDENTIAL

1 Weekday AM and PM Internal capture rates based on NCHRP Report 684, Saturday midday rates assumed to be the same was weekday evening rate.

**2 Daily Internal capture rates based on Trip Generation Handbook, 1st Edition, 2001**

The Northland Newton Development  
12239.00

### PROPOSED SHARED PERSON TRIPS - SATURDAY

RETAIL - OFFICE									
SATURDAY DAILY					SATURDAY MIDDAY				
RETAIL	%	#	BALANCED	#	%	#	BALANCED	#	OFFICE
EXIT ->	3%	8,650	34	225	15%	12	58	2%	-> ENTER
ENTER <-	4%	8,650	50	225	27%	10	50	3%	<- EXIT

RETAIL - RESIDENTIAL									
SATURDAY DAILY					SATURDAY MIDDAY				
RETAIL	%	#	BALANCED	#	%	#	BALANCED	#	RESIDENTIAL
EXIT ->	26%	8,650	741	1,610	46%	87	190	45%	-> ENTER
ENTER <-	18%	8,650	676	1,610	42%	64	198	42%	<- EXIT

OFFICE - RESIDENTIAL									
SATURDAY DAILY					SATURDAY MIDDAY				
OFFICE	%	#	BALANCED	#	%	#	BALANCED	#	RESIDENTIAL
EXIT ->	2%	225	5	1,610	1%	1	190	1%	-> ENTER
ENTER <-	0%	225	0	1,610	0%	8	198	1%	<- EXIT

TOTAL SHARED TRIPS - SATURDAY DAILY		
ENTER	EXIT	TOTAL
RETAIL	726	775
OFFICE	34	55
RES	746	676
	1501	1422

TOTAL SHARED TRIPS - SATURDAY MIDDAY		
ENTER	EXIT	TOTAL
RETAIL	74	99
OFFICE	20	11
RES	88	72
	173	160

1 Weekday AM and PM Internal capture rates based on NCHRP Report 684. Saturday midday rates assumed to be the same was weekday evening rate

2 Daily Internal capture rates based on Trip Generation Handbook, 1st Edition, 2001

TRIP GENERATION - WITH ROBUST SHUTTLE SERVICE																		
	FUTURE DEVELOPMENT - RETAIL						FUTURE DEVELOPMENT - RESIDENTIAL				FUTURE DEVELOPMENT - OFFICE			TOTAL NON-VEHICLE		TOTAL VEHICLE TRIPS		
	Proposed Retail Net Person Trips *	Proposed Retail Walk/Bike Trips	Proposed Retail Transit Trips	Proposed Retail Vehicle Trips	Proposed Retail Pass-By	Proposed Retail Net 237 KSF	Proposed Residential Net Person Trips *	Proposed Residential Walk/Bike Trips	Proposed Residential Transit Trips	Proposed Residential Net 824 UNITS	Proposed Office Net Person Trips *	Proposed Office Walk/Bike Trips	Proposed Office Transit Trips	Proposed Office Net 180 KSF	Proposed Walk/Bike Trips Net	Proposed Transit Trips Net	Proposed Development Net	Existing Net Trips
<b>Weekday AM Peak Hour</b>																		
Enter	220	11	11	111	22	89	75	8	23	42	178	18	53	37	87	224	222	3
Exit	132	7	7	67	22	44	214	21	64	138	22	2	7	30	78	172	56	136
Total	352	18	18	178	44	134	289	29	87	155	200	20	50	67	165	396	277	129
<b>Weekday Evening Peak Hour</b>																		
Enter	425	21	21	215	75	340	117	12	35	117	19	2	6	35	62	213	120	99
Exit	443	22	22	224	75	340	203	21	61	104	147	15	44	46	92	274	248	76
Total	868	43	43	439	150	289	203	21	61	104	166	17	50	89	154	487	368	119
<b>Saturday Midday Peak Hour</b>																		
Enter	566	28	28	286	70	318	102	10	31	103	38	4	11	42	70	291	186	105
Exit	492	25	25	249	70	318	128	13	38	103	39	4	12	42	75	267	163	104
Total	1,058	53	53	535	140	305	228	23	69	103	77	8	23	84	145	558	349	209

a - Net Person trips includes credit for internal capture

TRIP GENERATION - WITH EXISTING MODE SHARES																			
	FUTURE DEVELOPMENT - RETAIL						FUTURE DEVELOPMENT - RESIDENTIAL				FUTURE DEVELOPMENT - OFFICE			TOTAL NON-VEHICLE		TOTAL VEHICLE TRIPS			
	Proposed Retail Net Person Trips *	Proposed Retail Walk/Bike Trips	Proposed Retail Transit Trips	Proposed Retail Vehicle Trips	Proposed Retail Pass-By	Proposed Retail Net 237 KSF	Proposed Residential Net Person Trips *	Proposed Residential Walk/Bike Trips	Proposed Residential Transit Trips	Proposed Residential Net 824 UNITS	Proposed Office Net Person Trips *	Proposed Office Walk/Bike Trips	Proposed Office Transit Trips	Proposed Office Net 180 KSF	Proposed Walk/Bike Trips Net	Proposed Transit Trips Net	Proposed Development Net Vehicle Trips	Existing Net Trips	Proposed Development Net New Vehicle Trips
<b>Weekday AM Peak Hour</b>																			
Enter	220	11	11	111	22	89	75	6	10	42	178	5	12	36	33	282	221	41	
Exit	132	7	7	67	22	44	214	17	28	138	22	1	2	23	32	213	56	152	
Total	352	18	18	178	44	134	289	23	38	104	200	10	14	157	11	70	495	277	213
<b>Weekday Evening Peak Hour</b>																			
Enter	425	21	21	215	75	340	117	9	15	117	19	1	1	31	37	238	120	138	
Exit	443	22	22	224	75	340	203	7	11	131	147	7	10	36	43	326	248	78	
Total	868	43	43	439	150	289	203	16	26	144	166	8	11	121	87	80	564	368	194
<b>Saturday Midday Peak Hour</b>																			
Enter	566	28	28	286	70	318	102	8	13	103	38	2	3	36	44	318	186	132	
Exit	492	25	25	249	70	318	128	10	16	103	39	2	3	37	44	293	183	138	
Total	1,058	53	53	535	140	305	228	18	29	161	77	4	6	61	75	88	617	349	208

a - Net Person trips includes credit for internal capture

Mode Splits - Existing Mode Shares

Future Mode Splits Based on 2012 Census Data

Mode Share	Workers	Existing Residents	Retail *
Drive	88%	79%	90%
Transit	7%	13%	5%
Walk/Bike	8%	3%	5%
Total	100%	100%	100%

\* Based on US Census Bureau Journey to Work Data, City of Newton, 2010 for workers, US Census American Community Survey 2015 for residents of Newton

\*\* Based on assumed transit rates

\*\*\* Based on prediction of retail mode split

Mode Splits - Robust Shuttle Service

Future Mode Splits Based on Aggressive TDM and Shuttle Usage

Mode Share	Workers	Residents	Retail *
Drive	68%	79%	90%
Transit	7%	13%	5%
Walk/Bike	8%	8%	5%
Total	100%	100%	100%

\* Based on US Census Bureau Journey to Work Data, City of Newton, 2010 for workers, US Census American Community Survey 2015 for residents of Newton

\*\* Based on assumed transit rates

\*\*\* Based on prediction of retail mode split

---

**Shared Parking Calculations**

**Northland Newton Development - Right-Sized Parking**  
 Weekday - Seasonally Adjusted Parking Demand by Time of Day  
**December**

March 2019

Land Use	User	Annual Peak Demand		Seasonal Factor	Seasonal Demand		6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mld
		Customer	Employee		Customer	Employee	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mld
Shopping Center - Typical	Customer	121	100%	121	1	6	18	36	67	91	109	121	121	121	115	103	97	91	79	61	36	12	-		
	Employee	28	100%	28	3	4	11	21	24	27	28	28	28	28	28	27	27	27	27	25	21	11	4	-	
Fine/Casual Dining	Customer	134	100%	134	-	-	-	-	20	54	101	101	87	54	67	101	127	134	134	134	127	101	34		
	Employee	30	100%	30	-	6	15	23	27	27	27	27	27	23	23	30	30	30	30	30	30	30	26	11	
Family Restaurant	Customer	106	100%	106	27	53	64	80	90	95	106	95	53	48	48	80	85	85	85	64	58	53	27		
	Employee	22	100%	22	11	17	20	20	22	22	22	22	11	11	11	21	21	21	21	18	14	14	8		
Health Club	Customer	53	95%	50	35	20	20	35	35	40	30	35	35	35	40	45	50	45	40	35	18	5	-		
	Employee	4	100%	4	3	3	3	3	3	3	3	3	3	3	3	4	4	4	3	2	1	1	-		
Residential	Reserved	800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800		
Office	Visitor	41	100%	41	-	-	8	25	41	18	6	18	41	18	6	4	2	1	-	-	-	-	-		
Office	Employee	311	100%	311	9	93	233	295	311	311	280	280	311	311	280	156	78	31	22	9	3	-	-		
Medical/Dental Office	Visitor	40	100%	40	-	-	36	36	40	40	12	36	40	40	36	32	27	12	6	-	-	-	-		
	Employee	15	100%	15	-	-	9	15	15	15	15	15	15	15	15	10	5	2	-	-	-	-	-		
		1705		1702	889	1,002	1,237	1,389	1,495	1,543	1,539	1,581	1,572	1,507	1,472	1,418	1,358	1,285	1,246	1,173	1,098	1,016	880		

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

**Northland Newton Development - Right-Sized Parking**  
**Weekend - Seasonally Adjusted Parking Demand by Time of Day**


March 2019


December				Annual																			
Land Use	User	Peak Demand	Seasonal Factor	Seasonal Demand	6:00	7:00	8:00	9:00	10:00	11:00	Noon	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00	9:00	10:00	11:00	12Mld
Shopping Center - Typical	Employee	167	100%	167	2	8	17	58	100	117	142	159	167	167	159	150	134	125	109	84	58	25	-
		32	100%	32	3	5	13	24	27	30	32	32	32	32	30	27	26	24	21	14	5	-	-
Fine/Casual Dining	Customer	187	100%	187	-	-	-	-	-	28	94	103	84	84	84	112	168	178	187	168	168	168	94
	Employee	33	100%	33	-	7	10	20	25	25	25	25	25	25	33	33	33	33	33	33	33	28	17
Family Restaurant	Customer	187	100%	187	19	47	84	131	168	168	187	159	122	75	84	112	131	131	122	56	47	28	19
	Employee	33	100%	33	17	25	30	30	33	33	33	21	21	21	31	31	31	31	26	21	21	21	12
Health Club	Customer	56	90%	50	40	23	18	25	18	25	25	15	13	15	28	50	48	30	15	5	1	1	-
	Employee	3	100%	3	2	2	2	2	2	2	2	2	2	2	3	3	2	1	1	1	1	1	-
Residential	Reserved	800	100%	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800	800
Office	Visitor	5	100%	5	-	1	3	4	5	5	5	4	3	2	1	1	-	-	-	-	-	-	-
Office	Employee	52	100%	52	-	10	31	42	47	52	47	42	31	21	10	5	3	-	-	-	-	-	-
Medical/Dental Office	Visitor	50	100%	50	-	-	45	45	50	50	15	-	-	-	-	-	-	-	-	-	-	-	-
	Employee	25	100%	25	-	-	15	25	25	25	25	-	-	-	-	-	-	-	-	-	-	-	-
		1630		1624	883	928	1,068	1,206	1,300	1,360	1,432	1,374	1,300	1,244	1,246	1,327	1,378	1,356	1,323	1,194	1,143	1,077	942

Note: Does not include parking demand associated with community space. Assumed to be 15 spaces during peak times.

## **Exhibit E**







## **Exhibit F**

**Exhibit F**

**Density of Multi Family Developments**

Newton, MA

Property	Owner	Address	Units	Site Acreage	Units Per Acre
Avalon @UpperFalls	Avalon	99 Needham Street	294	7.80	37.7
Avalon @ChestnutHill	Avalon	160 Boylston Street	204	4.66	43.7
Washington Place	Mark Development	855 Washington Street	140	3.39	41.3
Austin Street	Dinosaur Capital	28 Austin Street	68	1.71	39.8
Woodland Station Apartments	National Development	1946 Washington Street	180	3.86	46.6
Village Falls Condos	Condominium	183 Oak Street	123	3.40	36.2
The Towers Chesnut Hill	Condominium	250 Hammond Pond Parkway	423	4.46	94.9
Northland Newton Development	NIC	156 Oak / 55 Tower / 241 Needham	800	22.65	35.3

## **Exhibit G**

# newton local

from the statement of Monica G. Tibbits-Nutt, LUC 4/9/19 1 of 9

**Monday-Friday**

## Saturday-Sunday

**newton local peak hour “available seats on the bus”: 192\***

from the statement of Monica G. Tibbits-Nutt, LUC 4/9/19 2 of 9

# boston express

from the statement of Monica G. Tibbits-Nutt, LUC 4/9/19 3 of 9

**Monday-Friday**

	B1	B2	B1	B2	B1	B1	B2	B1	B2	B1	B2	B1	B2
<i>depart</i> Transit Hub		7:00		8:00	9:00	10:00		4:00		5:00	6:00	7:00	8:00
Seaport/WTC	6:45	7:45	8:45	9:45	10:45		3:45	4:45	5:45	6:45	7:45	8:45	
South Station	6:58	7:58	8:58	9:58	10:58		3:58	4:58	5:58	6:58	7:58	8:58	
<i>arrive</i> Transit Hub	7:43	8:43	9:43	10:43			4:43	5:43	6:43	7:43	8:43		

**Saturday-Sunday**

	B1	B2	B1	B2	B1	B2	B1	B2	B1	B2	B1	B2	B1
<i>depart</i> Transit Hub	7:30	8:30	9:30	10:30	11:30	12:30	1:30	2:30	3:30	4:30	5:30	6:30	7:30
Seaport/WTC	8:15	9:15	10:15	11:15	12:15	1:15	2:15	3:15	4:15	5:15	6:15	7:15	8:15
South Station	8:28	9:28	10:28	11:28	12:28	1:28	2:28	3:28	4:28	5:28	6:28	7:28	8:28
<i>arrive</i> Transit Hub	9:13	10:13	11:13	12:13	1:13	2:13	3:13	4:13	5:13	6:13	7:13	8:13	9:13

**boston express peak hour “available seats on the bus”: 64**

from the statement of Monica G. Tibbits-Nutt, LUC 4/9/19 4 of 9

# cambridge express

from the statement of Monica G. Tibbits-Nutt, LUC 4/9/19 5 of 9

**Monday-Friday**

	B1	B2	B1	B2	B1		B1	B2	B1	B2	B1	B2	B1	B2
<i>depart</i> Transit Hub		7:00		8:00		9:00	10:00			4:00	5:00	6:00	7:00	8:00
Central Square	6:45		7:45		8:45		9:45	10:45		3:45	4:45	5:45	6:45	7:45
Kendall Square	6:55		7:55		8:55		9:55	10:55		3:55	4:55	5:55	6:55	7:55
<i>arrive</i> Transit Hub		7:40		8:40		9:40	10:40			4:40	5:40	6:40	7:40	8:40

**Saturday-Sunday**

	B1	B2	B1	B2	B1	B2	B1	B2	B1	B2	B1	B2	B1	B2
<i>depart</i> Transit Hub	7:30	8:30	9:30	10:30	11:30	12:30	1:30	2:30	3:30	4:30	5:30	6:30	7:30	8:30
Central Square	8:15	9:15	10:15	11:15	12:15	1:15	2:15	3:15	4:15	5:15	6:15	7:15	8:15	9:15
Kendall Square	8:25	9:25	10:25	11:25	12:25	1:25	2:25	3:25	4:25	5:25	6:25	7:25	8:25	9:25
<i>arrive</i> Transit Hub	9:10	10:10	11:10	12:10	1:10	2:10	3:10	4:10	5:10	6:10	7:10	8:10	9:10	10:10

**cambridge express peak hour “available seats on the bus”:** 64

from the statement of Monica G. Tibbits-Nutt, LUC 4/9/19 6 of 9



## **the northland shuttle system**

**day 1**

from the statement of Monica G. Tibbits-Nutt, LUC 4/9/19, 7 of 9

## system-wide stats

	devoted shuttles	runs per day (Mon-Fri)	runs per day (Sat-Sun)	Peak hour available seats on the bus
<b>newton local</b>	3	41	30	192
to newton highlands only		(31)		
to newton highlands + newtonville		(10)		
<b>boston express</b>	2	11	15	64
<b>cambridge express</b>	2	11	15	64
back-up vehicle	1			

8

63

60

320

from the statement of Monica G. Tibbits-Nutt, LUC 4/9/19 8 of 9


## **fare structure recommendations**

one seat on the <b>newton local</b>	\$2.50
one seat on the <b>boston or cambridge express</b>	\$7.00

from the statement of Monica G. Tibbits-Nutt, LUC 4/9/19 9 of 9

## **Exhibit H**

## Five Year Timeline



## **Exhibit I**

## **Northland Newton Development**

### **TDM Work Plan Outline**

This Work Plan Outline summarizes the key stages in the implementation of the TDM Plan. Please refer to the TDM Plan for background. There will be three basic stages to the implementation of the TDM Plan; **Pre-Shuttle**, **Shuttle** and **Ongoing**.

#### **Pre-Shuttle Stage:**

This is the stage prior to the receipt of Certificates of Occupancy (CO) for the first 400 units. This stage will begin during construction, approximately 6 months prior to the anticipated receipt of the first CO's.

During this stage, extensive marketing to potential residents and commercial tenants will highlight and promote the opportunities for non-SOV modes of transit that the Northland Newton Development (NND) will offer. Due to the nature of building sizes and anticipated sequence of construction, the first of the 400 CO's are anticipated to be issued within two years of the commencement of construction.

1. The **TDM Coordinator** position will be filled and begin outreach and coordination with the 128 Business Council (128BC) on early stage options for non-SOV transit. The TDM Coordinator will also establish plans for education, communication and marketing of the then current, and planned non-SOV transit options. The TDM Coordinator will also work and coordinate with City of Newton officials to minimize SOV use and to monitor SOV trips generated by NND.
2. Opening of the **Mobility Hub (MH)**. The TDM coordinator will be located in the MH. The TDM Coordinator will expand communication and outreach to residents and commercial tenants/employees to ensure that they are fully aware of all the non-SOV transit modes available to them, especially the shuttle. The TDM Coordinator will conduct informational sessions in the MH as well as in the Saco Pettee Mill for office employees and in the apartment buildings for residents. The TDM Coordinator will also make sure all residents and tenants/employees are aware of transit incentives such as T-passes, reduced shuttle fees, etc. All marketing materials will highlight and include details about the shuttle and other transit options available at NND.
  - a. Two on-street parking spaces will be designated for TNC pick-up/drop-off in front of the MH closest to Main Street.
3. **Residents and commercial tenants/employees** will be provided car sharing, bicycle routes, and MBTA and car/van-pooling information. Residents will be provided T-passes. Employers will be encouraged to provide T-passes to their employees and will be motivated by the lack of typical market-provided parking.

Designated ZipCar (or similar) spaces will be established in the central parking garage as will car/van pool spaces.

4. Residential **bicycle parking** will be provided as the apartment buildings are completed. Retail (in the central parking garage and on-street through-out the project) and office (at the Saco Pettee Mill) bicycle parking will also be provided as the buildings and parks/open spaces are completed.
5. As part of the NND **project website**, there will be a section dedicated to non-SOV transit options for employees, residents and visitors.
6. One on-street parking space will be designated for **TNC pick-up/drop-off** at the following locations:
  - a. Building 3, near the residential lobby entrance on Main Street.
  - b. Building 6, near the residential lobby entrance on Main Street and near the residential lobby on Charlemont St.
  - c. Building 5, near the residential lobby entrance on Main Street and near the leasing office entry on Pettee Lane.

#### **Shuttle Stage:**

This stage continues to build on the work started in the Pre-Shuttle Stage and begins upon receipt of the 400<sup>th</sup> CO. This stage initiates the full TDM Plan including the following:

1. It will be at this stage that the full **Shuttle System** commences it's full service and schedule. All routes will begin operation from the MH. This will include the "guaranteed ride-home" program. The TDM Coordinator will work with the 128BC/Shuttle Operator to monitor operations.
2. The transit options section on the NND **project website** will be enhanced to include information on the shuttles including schedules. Additionally, transit information will be available in the MH, in the residential lobbies and throughout the site on digital information monitors. Marketing efforts for the Shuttle System will be increased leading up to the opening of the shuttle and will be maintained on an ongoing basis.
3. Active management of the **Shared Parking Program** will commence.

#### **Ongoing:**

As the remaining 400 residential units and office/retail space become available, the TDM strategy will continue to be enhanced. Some of the elements will have started during the

Pre-Shuttle Stage (e.g., marketing, SOV tracking, etc.) and some will start during the Shuttle Stage (e.g., the shuttle system and shuttle tracking, Active Shared Parking, etc.).

1. As Building 4 comes online, a **TNC pick-up/drop-off** space will be designated near the lobby entrance on Main Street.
2. **TNC activity** will be monitored to ensure that project SOV trip generation limits are not exceeded. The TDM Coordinator will work with the City and the TNC's to manage their utilization. It is important to note that TNC's are an important option for residents without cars. Due to their high cost relative to the shuttles (\$14 shuttle round trip to Boston/Cambridge, vs \$40-50 for TNC's) it is expected that the TNC option will be used as a limited alternative.
3. **Marketing and outreach** will continue and be adjusted to ensure success as NND progresses.
4. **New transit trends/options** (i.e. Uber shuttles, Shared Autonomous Vehicles, expanded "regional" shuttle system, etc.) will continually be monitored for useful and impactful application to NND.
5. The TDM Coordinator will **maintain communication** with project residents, retail/office employees, the City, area business, the Chamber and others to ensure that the non-SOV transit options available at NND are responsive, effective and successful.
6. The TDM Coordinator will begin the process of **Data Gathering** to for annual review with the City.
7. As part of this Work Plan Outline, there are at least 3 three key points for **review with the City** to make adjustments to the TDM Plan:
  - a. Prior to commencement of the initial sequence of construction (**Pre-Shuttle Stage**).
  - b. Prior to the commencement of the final sequence of construction (**Shuttle Stage**).
  - c. Upon review of metrics provided for understanding SOV generation, shuttle program utilization, TNC utilization, and overall TDM effectiveness. The timing of this review will be at least annually but may be adjusted depending on program operations (**Ongoing Stage**).

## **Exhibit J**

**Exhibit F**

<b>80% of AMI</b>	<b>HUD Income Limit:</b>	<b>\$81,100</b>	<b>Max Gross Monthly Rent</b>	<b>Utility Allowance</b>	<b>Max Net Monthly Rent</b>
<b>Unit Size</b>	<b>HH Size</b>	<b>HH Income</b>			
Studio	1.00	\$56,800	\$1,420	(\$90)	\$1,330
1 BD	2.00	\$64,900	\$1,623	(\$119)	\$1,504
2 BD	3.00	\$73,000	\$1,825	(\$151)	\$1,674
3 BD	4.00	\$81,100	\$2,028	(\$182)	\$1,846
4 BD	5.00	\$87,600	\$2,190	(\$217)	\$1,973

**Newton Salary Ranges**

	<b>25th Percentile</b>	<b>Average</b>	<b>75th Percentile</b>
Newton FD	\$39,493	\$52,656	\$65,821
Newton PD	\$58,400	\$62,500	\$68,100
Public School Teachers	\$56,357	\$64,557	\$74,524

## **Exhibit K**

## Needham Street | Newton, MA

### OPEN SPACE CHARACTER



Site: 22.6 acres  
Open Space: 10.4 acres / 46%

### 4 Types of Open Space

- 1 – Civic Space  
Village Green at Main Street
- 2 – Community Space & Natural Green  
Oak Street Park  
Community Park  
Greenway  
South Meadow Brook Park
- 3 – Mobility Plaza
- 4 – Flexible / Semi-public  
Mill Park  
Courtyard

## BLUE BACK SQUARE | West Hartford, CT



24.5 acres

Open Space: ~ 19%



## BLUE BACK SQUARE | West Hartford, CT



## PIKE & ROSE | North Bethesda, MD



Site: 24 acres

Open Space: ~10%



## PARK DISTRICT | North Hills, Raleigh, NC



Site: 22 acres

Open space: ~12%



**PARK DISTRICT** | North Hills, Raleigh, NC



**PIKE & ROSE** | North Bethesda, MD





## ASSEMBLY ROW | Sommerville, MA



Site: 27.7 acres phase 1 by 2017


Open Space: ~10%



## ASSEMBLY ROW | Sommerville, MA



## ADISON CIRCLE Dallas, TX



Site: 21.7 acres

Open Space: ~10%



## STATION LANDING | Medford, MA




Site: 17 acres

Open Space: ~8%



## STATION LANDING | Medford, MA



## Nadia Khan

---

**From:** DCrossley <djcrossley26@verizon.net>  
**Sent:** Sunday, April 14, 2019 3:16 PM  
**To:** Nadia Khan  
**Cc:** Deborah J. Crossley; Jennifer Caira; Gregory R. Schwartz  
**Subject:** Re: Northland Newton Development re Transit.

Nadia, please circulate these questions regarding the Northland project

Here were my questions posed in conversation after the meeting, some of which were answered in a recent letter from Peter Standish:

1 - I understand that, if we permit this project, it will be a year or more before the working drawings would be completed for building permits -  
and then maybe about five years or so to build it.  
Although we were told at the April meeting that 'phasing' is the wrong term, because the project must be financed as a whole,  
I'd like to understand in more detail how construction will be sequenced.  
**Which buildings, uses and public outdoor spaces would come on line first, second, etcetera - ?**

2 - I also heard the commitment to achieving 40% shared ridership for the project, and read that the shuttle would be operational once the first 400 units come on line,  
but **will the shuttle be a fully operational system at that point?**

3 - Although I understood that the significant proposed reduction of retail uses clearly reduces the number of trips to and from the project,  
I found some of the presentation of traffic counts and assumptions somewhat confusing, and left not clear about what the discrepancies are between the petitioner and peer reviewer.  
The discrepancies were not large - but it was difficult for me to follow when both parties were working off the same assumptions and/or whether the peer reviewer was current on the reduced scope.

I appreciate the quick response from Mr. Standish related to these questions, and **look forward to the summary of traffic numbers.**

4 - I see that some opinions we are seeing in letters from the public, try to relate the intensity of use proposed for this site to others they can see - particularly Avalon at Newton Highlands and Chestnut Hill. I believe both of those projects have more square foot of building relative to site area, and far less usable open space relative to the amount of building on each sites, although Avalon at Newton Highlands may be more comparable to Northland.  
I believe that both Austin Street and Washington Place were permitted with a higher proportion of building area to open space a well.  
**It would be helpful if the Planning Department could verify the numbers.**

5 - I also heard at the meeting that the intersection of the Avalon Bay drive and Needham Street works at a level of service **LoS A**.  
There are 294 units there on less than eight acres, and now the Nexus lot is connected directly to Avalon, providing another egress from their site.

**It would be helpful if the Planning Department would confirm this data.**

6 - I understand that given the investments made so far - two layers of underground parking, more open space, a subsidized shuttle serve, and more we'll hear about with stormwater management, affordability and building design... that there is proposed a cap on other mitigation spending of five million. This is related to the list of investments we'd like to make in alternative transit options including a 275K comprehensive feasibility study including a look at a Greenline extension, accessible access to the Elliot and Highlands T stops, extending the bikeway to Needham over the Christina bridge, etcetera. Some of these ideas have been kicking around for a few years.  
**Can the Planning Department help us understand what each of these projects would entail , where they stand - and identify the challenges to achieving each one/.**

Finally, the public comment went so late that the committee did not have a chance to hold a constructive conversation the same night.

Although we are invited to put forward our questions in this forum, it would be more helpful - given how managed transit is critical to the success of the project - if we could have a conversation in committee to make sure we all understand the intricacies of this very new approach to transit.

It would be my **preference to hold such a meeting completely separately** from the final design, stormwater and sustainability meeting coming up in May.

Thank you,  
Deb

Deborah J. Crossley  
COUNCILOR  
Public Facilities Chair  
[dcrossley@newtonma.gov](mailto:dcrossley@newtonma.gov)  
617/ 775-1294 cell phone

When responding, please be advised that the Secretary of the Commonwealth has determined that email may be considered a public record.

On Apr 12, 2019, at 4:08 PM, Alan J. Schlesinger <[aschlesinger@sab-law.com](mailto:aschlesinger@sab-law.com)> wrote:

Deb – Peter Standish has put together some responses to your questions of yesterday. Attached.

I hope to talk to you next week.



**Confidentiality Note**

This e-mail contains information intended only for the use of the addressee named above. If you are not the intended recipient of this e-mail, or the agent or employee responsible for delivering it to the

April 12, 2019

Deborah J. Crossley  
City Councilor  
City of Newton  
1000 Commonwealth Avenue  
Newton, MA 02459

RE: April 9, 2019 Land Use Committee Hearing

Dear Councilor Crossley,

Alan Schlesinger told me of your conversation following Tuesday's hearing and the questions you had about the information we presented. I wanted to make sure to provide you with a timely response to address your questions.

With regard to phasing, NND will be financed and built as one project. The actual development of the buildings will be sequenced to efficiently manage construction and allow for orderly lease-up of the apartments. Based on our current planning, the first sequence of construction will include blocks 5 and 6 as well as Buildings 2, 3, 7, and the community building. Also included with the first sequence will be the renovation of 156 Oak Street and the construction of the Village Green, the Community Park & Playground, the Mill Park, the Mobility Park, and the restoration of South Meadow Brook. The second sequence will include Buildings 4, 8, the townhouses and the Oak Street Park. The first sequence will comprise 498 units and the second sequence will include 302 units. I have attached a 5-year timeline showing this sequencing.

With regard to the commencement of the shuttle program, we have made the commitment to start the full program once we have received a certificate of occupancy for 400 units. We will hit this point in the first sequence of construction. The shuttle program will be an integral part of our marketing program, so it is essential to be operational in this first sequence.

We are preparing a chart clearly summarizing and reconciling the traffic numbers presented by both Beta and VHB. We will have this for you in the next few days and would welcome the opportunity to meet with you and review everything. We will make any person on our team available to meet with you to discuss these or any other issues. Please let us know a time and we can schedule a meeting.

Please do not hesitate to contact me with any other questions you may have.


Sincerely,



Peter M. Standish  
Senior Vice President

# Northland Newton Development

## Five Year Timeline



April 12, 2019

Alison M. Leary  
City Council  
City of Newton  
1000 Commonwealth Avenue  
Newton, MA 02459

RE: April 9, 2019 Land Use Committee Hearing

Dear Councilor Leary,

I want to thank you for the insightful comments you made to Monica Tibbits-Nutt following her presentation of the proposed NND shuttle program. As you heard Tuesday, Northland is committed to a radically aggressive program to reduce traffic generation associated with the development. We are aligned with the City in setting out, and achieving, a performance goal of a 40% reduction in vehicle trip generation, and we have proposed a broad spectrum of TDM measures to accomplish our goal.

Our shuttle program will provide both door-to-workplace and 20-minute frequency last mile service to residents and workers, and offer a superior rider experience with comfortable seats, wifi, real-time schedule and tracking, and in-app pay options. The shuttle is intended to complement MBTA service rather than compete with it. The shuttle schedule is coordinated with both T and commuter rail service, and our mobility hub is intended to service T bus customers, particularly those traveling west to the Needham Height commuter rail stop. We have also committed to installing a shelter at the bus stop on the east side of Needham street.

We are proposing a shuttle fare structure that is competitive with MBTA fares, yet provides far greater service and value. We will provide financial incentives that will further reduce transit costs for riders, including shuttle and T discounts. Residents that commit to living car-free at NND will be offered a free annual T pass. If these incentives are unsuccessful in building ridership, we will re-evaluate our fare structure and routes.

We've worked very diligently to reduce the number of parking spaces at NND down to 1550, a level that maximizes shared parking opportunity yet provides a base number satisfactory to finance and lease the project. That said, we've continued to investigate viable strategies that can lower parking even further. We are preparing a revision that will solve any lingering issues and address both sides of the debate (reduction and addition of spaces). We are going to reduce striped spaces from 1550 to 1450 AND allow for extra capacity by creating a 200-car valet pad (a total of 1650) that will accommodate overflow in the peak holiday season. This plan is responsive to the marketplace (peak demand) and our commitment to reducing single occupancy vehicles (lowered number of parking spaces). We agree that any further reduction of parking should be done in concert with parking restrictions or resident parking policy on neighborhood streets. We can include a lease provision to restrict parking on neighborhood streets and void incentives for violators. However, it will be difficult to enforce without a neighborhood parking restriction.

Our commitment to providing mobility options goes well beyond our shuttle and reduced parking. NND will offer car and bike-sharing options on site, bike path connections and parking for 1100 bicycles, end-to-end pedestrian connections in all directions with inviting, activated streets, and our mobility hub providing a comfortable transit lounge providing real-time transit information. Electric charging stations also will be conveniently located throughout the development to promote electric vehicle usage. NND will be a model for leadership in promoting alternate transit opportunities in Newton.

If you have any further questions on these points or any other aspect of NND, please do not hesitate to contact me. Any member of our team is happy to meet with you in person to discuss any issues in greater detail. Please let us know a time and we will schedule a meeting.

Sincerely,

A handwritten signature in blue ink that reads "Peter M. Standish".

Peter M. Standish  
Senior Vice President

April 12, 2019

Andreae Downs  
City Councilor  
City of Newton  
1000 Commonwealth Avenue  
Newton, MA 02459

RE: April 9, 2019 Land Use Committee Hearing

Dear Councilor Downs,

Alan Schlesinger told me of your conversation following Tuesday's hearing and the questions you had about the information we presented. I wanted to make sure to provide you with a timely response to address your questions.

You asked if there may be an opportunity to bank parking spaces as suggested in the State's 2017 ENF response on the project. We've worked very diligently to reduce the number of parking spaces at NND down to 1550, a level that maximizes shared parking opportunity yet provides a base number satisfactory to finance and lease the project. That said, we are preparing a revision that will solve any lingering issues and address both sides of the debate (reduction and addition of spaces). We are going to reduce striped spaces from 1550 to 1450 AND allow for extra capacity by creating a 200-car valet pad (a total of 1650) that will accommodate overflow in the peak holiday season. This plan is responsive to the marketplace (peak demand) and our commitment to reducing single occupancy vehicles (lowered number of parking spaces).

You requested from Alan a shadow study. Attached for your review is an updated shadow study for NND based on the revised laneway plan we presented in March. We will be presenting this study in an easy-to-read video graphic at our next meeting. I would be happy to send you the video model by next Friday.

On the merits of density, we firmly believe density is critical to enlivening NND's streets and open spaces to create a sense of place. NND will be the heart of activity along the corridor and the N-Squared District, and will achieve the over-arching goals of the Needham Street Vision Plan, most importantly the vision for land use. We cannot achieve this with lower density. We have put our parking underground to create a more desirable pedestrian environment. We have dedicated 43% of development to open space, and are providing a dedicated community building, a playground and several large green spaces for public benefit. Density is the financial engine necessary to provide these critical place-making ingredients. Finally, it enables us to add critically needed housing inventory to the City, including 123 affordable housing units and a dedicated building designed to allow seniors to age in-place.

If you have any further questions on these points or any other aspect of NND, please do not hesitate to contact me. Any member of our team is happy to meet with you in person to discuss any issues in greater detail. Please let us know a time and we will schedule a meeting.

Sincerely,



Peter M. Standish  
Senior Vice President

NORTHLAND  
NEWTON  
DEVELOPMENT  
NEEDHAM STREET /  
OAK STREETNORTHLAND  
INVESTMENT  
CORPORATION  
2150 WASHINGTON  
ST NEWTON MA  
02462ZONE CHANGE &  
MASTER PLAN

drawing by: [ ]  
 drawing checked by: [ ]  
 drawing date: 6 AUGUST 2010  
 drawing scale: 1200' = 1'

Shadow  
Studies**A-15.01**

3

Summer Solstice 3:00 p.m.  
N/S

2

Summer Solstice 12:00 p.m.  
N/S


1

Summer Solstice 9:00 a.m.  
N/S


6

Equinox 3:00 p.m.  
N/S


5

Equinox 12:00 p.m.  
N/S


4

Equinox 9:00 a.m.  
N/S

9

Winter Solstice 3:00 p.m.  
N/S

8

Winter Solstice 12:00 p.m.  
N/S

7

Winter Solstice 9:00 a.m.  
N/S