

CITY OF NEWTON
Department of Public Works
ENGINEERING DIVISION

MEMORANDUM

To: Council Mark Laredo, Land Use Committee Chairman

From: John Daghljan, Associate City Engineer

Re: Special Permit – 235 Woodcliff Road

Date: October 19, 2016

CC: Lou Taverna, PE City Engineer
Nadia Khan, Committee Clerk
Alexandria Ananth, Chief Planner
Michael Gleba, Sr. Planner

In reference to the above site, I have the following comments for a plan entitled:

*Renovations & Improvements to the Robins Residence
235 Woodcliff Road
Newton, MA
Prepared by: SLR Architecture
Dated: 9-1-'16*

Executive Summary:

This application entails an addition of a two stall garage and family room above onto an existing single family dwelling. A new expanded driveway is proposed along with drainage improvements, however the plans are not at full scale and no drainage study was provided for review at this of this memo.

A full scale plan set and drainage report is needed for proposer evaluation. The engineer of record shows some sort of stormwater collection and infiltration system however no calculations were provided.

Drainage:

1. A drainage analysis needs to be performed based on the City of Newton's 100-year storm event of 6-inches over a 24-hour period. All runoff from impervious areas need to be infiltrated on site, for the project. The design of the proposed on site drainage system needs to comply with the MassDEP Stormwater Regulations and City Ordinances.
2. An on-site soil evaluation needs to be performed to obtain the seasonal high groundwater elevation, percolation rate in accordance to Title V. This information must be submitted with the drainage study. The locations of these tests need to be shown on the site plan and must be performed within 25-feet of a proposed system.
3. An Operations and Maintenance (O&M) plan for Stormwater Management Facilities needs to drafted and submitted for review. Once approved the O&M must be adopted by applicant, incorporated into the deeds; and recorded at the Middlesex Registry of Deeds. A copy of the recording instrument shall be submitted to the Engineering Division.
4. It is imperative to note that the ownership, operation, and maintenance of the proposed drainage system and all appurtenances including but not limited to the drywells, catch basins, and pipes are the sole responsibility of the property owner(s).

General:

1. All trench excavation contractors shall comply with Massachusetts General Laws Chapter 82A, Trench Excavation Safety Requirements, to protect the general public from unauthorized access to unattended trenches. Trench Excavation Permit required. This applies to all trenches on public and private property. *This note shall be incorporated onto the plans*
2. All tree removal shall comply with the City's Tree Ordinance.
3. The contractor is responsible for contacting the Engineering Division and scheduling an appointment 48 hours prior to the date when the utilities will be made available for an inspection of water services, sewer service, and drainage system installation. The utility is question shall be fully exposed for the inspector to view; backfilling shall only take place when the City's Inspector has given their approval. *This note should be incorporated onto the plans*

4. The applicant will have to apply for Street Opening, Sidewalk Crossing, and Utilities Connecting permits with the Department of Public Works prior to any construction. *This note must be incorporated onto the site plan.*
5. The applicant will have to apply for a Building Permits with the Department of Inspectional Service prior to any construction.
6. Prior to Occupancy Permit being issued, an As-Built Plan shall be submitted to the Engineering Division in both digital format and in hard copy. The plan should show all utilities and final grades, any easements and final grading, improvements and limits of restoration work. The plan shall also include profiles of the various new utilities, indicating rim & invert elevations, slopes of pipes, pipe material, and swing ties from permanent building corners. ***This note must be incorporated onto the final contract plans.***
7. All site work including trench restoration must be completed before a Certificate of Occupancy is issued. *This note must be incorporated onto the site plan.*

Note: If the plans are updated it is the responsibility of the Applicant to provide all City Departments [Conservation Commission, ISD, and Engineering] involved in the permitting and approval process with complete and consistent plans.

If you have any questions or concerns please feel free to contact me @ 617-796-1023.