SITE PLAN

OR

499 WINCHESTER STREET NEWTON, MASSACHUSETTS

FEBRUARY 25, 2019

PLAN INDEX

SHEET 1 COVER SHEET

SHEET 2 EXISTING CONDITIONS PLAN


SHEET 3 GRADING AND DRAINAGE PLAN

SHEET 4 LAYOUT AND UTILITIES PLAN


SHEET 5 CONSTRUCTION DETAILS

SHEET 6 EROSION & SEDIMENT

CONTROL PLAN



LOCUS PLAN
SCALE: 1"=100'



LOCUS MAP
SCALE: 1"=1,200'



ENGINEER/SURVEYOR

STAMSKI AND MCNARY, INC. 1000 MAIN STREET ACTON, MASSACHUSETTS 01720 (978) 263-8585



RECORD OWNER


DUANE F. HILLIS
MARY E. HILLIS
499 WINCHESTER STREET
NEWTON, MA


ZONING DISTRICT SINGLE RESIDENCE 3 - SR3

DATUM
CITY OF NEWTON.

REFERENCE

MIDDLESEX REGISTRY OF DEEDS SOUTH DISTRICT DEED BOOK 58824 PAGE 181





PROPOSED ROOF DRYWELL 1 N/F CITY OF NEWTON PROPOSED - ACCESSIBLE ENTRANCE 26.2'± 7 26.3'± CB-2 PROPOSED UNITS 3 & 4 F.F.=158.9± - PROPOSED MILK HOUSE T.C.=157.70 B.F.=147.7± PROPOSED INFILTRATION BED 43,567 S.F.±. 1.0002 AC.± 33.6'±\(\)(10'MIN) PROPOSED -GRASSPAVE PROPOSED ROOF DRYWELL 2 PROPOSED SLOPED GRANITE N/F CHARLES RIVER COUNTRY CLUB, INC. PROPOSED CB-1 -UNITS 1 & 2 F.F.=162.90 T.C.=161.70 N/F CITY OF NEWTON B.F.=151.7± (50RC) PROPOSED SEWER SERVICE PROPOSED -WATER SERVICE PROPOSED ELECTRIC SERVICE PROPOSED GAS SERVICE PROPOSED TRANSFORMER S00°53'04"E WINCHESTER STREET (1963 CITY LAYOUT - 50' WIDE) TBM TOP HYDRANT ELEV.=160.72

LAND USE DATA ZONING REQUIREMENTS ZONING DISTRICT: SINGLE RESIDENCE 3 (SR3) REQUIRED: PROVIDED: MIN LOT AREA: 1 ACRE 1.0002 ACRE MIN LOT FRONTAGE: 80 FT 206.70 FT MIN FRONT YARD: 30 FT 31.2 FT 25 FT 26.3 FT MIN SIDE & REAR YARD: 30% (13,067 SF) 18.3% (7,958 SF) MAX LOT COVERAGE: 50% (21,778 SF) 66.7% (29,075 SF) MIN OPEN SPACE: FLOOR AREA REQUIREMENTS 43,567 SF LOT AREA = MAX NET FLOOR AREA ALLOWED 0.38 PROPOSED GROSS FLOOR AREA = 16,544 SF

4 UNITS x 2

0.3797

8 STALLS

16 STALLS

LEGEND:

PROPOSED GROSS FLOOR AREA RATIO =

NUMBER OF STALLS PROVIDED: 4 UNITS x 4

PARKING REQUIREMENTS
(FROM SECTION 5.1.4)
2 STALLS / DWELLING UNIT

NUMBER OF STALLS REQ'D:

N/F NOW OR FORMERLY — UCW UNDERGROUND WIRES TREE LINE UTILITY POLE GAS GATE — G— GAS SERVICE (BURIED) WATER GATE O DMH DRAIN MANHOLE - D - SUB-SURFACE DRAIN LINE OOOOO STONE WALL TOP OF CONCRETE T.C. F.F. FIRST FLOOR BASEMENT FLOOR GARAGE FLOOR

SITE PLAN
499 WINCHESTER STREET
NEWTON, MASSACHUSETTS
(MIDDLESEX COUNTY)


LAYOUT AND UTILITIES PLAN

FOR: CAROLINA PROPERTIES, LLC SCALE: 1"=20' FEBRUARY 25, 2019


STAMSKI AND MCNARY, INC.
1000 MAIN STREET ACTON, MASSACHUSETTS
ENGINEERING - PLANNING - SURVEYING

0 10 20 40 60 80 FT

(6139.SITE.F.dwg) SM-6139 SHEET 4 OF 6





GEORGE DIMAKARAKOS CIVIL No. 4/281





PLAN VIEW:


SINGLE RESIDENCE 3 (SR3) SCALE: 1"=20'















18" MEDIUM-COARSE WELL DRAINED SOIL



TYPICAL GRASSPAVE2 DETAIL

CHOOSE THIS PRODUCT FOR REINFORCING GRASS WEARING SURFACES

50 CM (19.7")

16.7 CM (6.6") 25 CM (9.8")

SPECIFICATIONS

UNIT SIZE - 50 CM X 50 CM X 2.5 CM

AVAILABLE IN 9 STANDARD ROLL SIZES

UNIT WEIGHT - 510 GRAMS (18 OZ.) OR 2.0 KG (4.5 POUNDS)

COLOR - BLACK (STANDARD)


GRASSPAVE2 SQUARES


STRENGTH - 402 KG/CM (5720 PSI)


RESIN - HDPE (WITH SOME POST-CONSUMER RECYCLED CONTENT)


1600 Jackson St., Ste. 310 GOLDEN, COLORADO 80401 800-233-1510 OR 303-233-8383 FAX: 800-233-1522 OR 303-233-8282 www.invisiblestructures.com rev. 10/05


(20" X 20" X 1")


















Structures, Inc.















SU-30 TURNING ANALYSIS


72/24/WWW





- 2. ALL WATER LINE VALVES, ETC. SHALL MEET ALL SPECIFICATIONS OF THE CITY OF HAVERHILL WATER DEPARTMENT.
- ALL STUMPS AND OTHER CONSTRUCTION DEBRIS SHALL BE PROPERLY REMOVED FROM THE
- ANY FILL MATERIAL USED SHALL BE FREE OF HAZARDOUS MATERIALS, WASTE, AND CONSTRUCTION DEBRIS.
- RIP RAP SHALL CONSIST OF HARD DURABLE STONE, ANGULAR IN SHAPE, THAT IS WELL GRADED WITHIN THE 25# TO 125# RANGE. THE RIP RAP SHALL BE PLACED OVER A 12" BASE OF COARSE BANK RUN GRÄVEL. RIP RAP SHOWN SCHEMATICALLY AT DRAINAGE OUTFALLS SHALL BE PLACED FOR A 3' WIDTH AND 6' LENGTH UNLESS OTHERWISE SPEC'D.
- THE LIMITS OF WORK SHALL BE CLEARLY MARKED IN THE FIELD PRIOR TO THE START OF CONSTRUCTION OR SITE CLEARING PER THE STORMWATER POLLUTION PREVENTION PLAN.


BOULDERS, BRUSH, TREES, STUMPS, UNSUITABLE MATERIALS AND LIKE MATERIAL.


- EXISTING TOPSOIL SHALL BE STRIPPED, STOCKPILED, SCREENED AND SPREAD TO REQUIRED DEPTHS SHOWN ON THE PLAN.
- CATCH BASIN SUMPS AND STORM WATER BASINS SHALL BE CLEANED FOLLOWING COMPLETION OF CONSTRUCTION AND ANNUALLY THEREAFTER PER O & M PLAN.
- THE ENTIRE WORK AREA SHALL BE CLEARED OF BUILDINGS TO BE RAZED, PAVEMENT, DEBRIS,
- 10. ALL TOP AND SUBSOIL WITHIN WORK AREA SHALL BE REMOVED AND STOCKPILED ON SITE AS DIRECTED BY THE OWNER. LOAM SHALL BE SCREENED AND STOCKPILED ON-SITE FOR RE-USE
- IN AREAS OF GENERAL LOAM AND SEED. 11. THE CONTRACTOR SHALL MAINTAIN THE SITE IN A SAFE CONDITION THROUGHOUT THE CONTRACT PERIOD. THE CONTRACTOR SHALL FULLY COMPLY WITH ALL STATE, FEDERAL,
- AND LOCAL REGULATIONS PERTAINING TO SAFETY.
- 12. ALL DISTURBED EARTHEN SURFACES SHALL BE PROVIDED WITH 6" OF LOAM AND SEED UNDERLAIN BY 18" OF MEDIUM-COARSE WELL DRAINED SOIL. SEE GENERAL LOAM AND SEED
























GEORGE DIMAKARAKOS/


ຸ CIV∕IL


No. 41281




8. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.









INLET PROTECTION DETAIL NOT TO SCALE

INSPECT REGULARLY AND REPLACE AS NEEDED AND AS DIRECTED BY APPROVING AUTHORITY

WOOD STAKES Ø 8' MAX. SPACING ——

UNDISTURBED

SUBGRADE

SEDIMENT CONTROL FABRIC ATTACHED TO POSTS W/

EROSION AND SEDIMENTATION CONTROL NOTES

CONSTRUCTION ON THE SITE.

- 1. THE LIMITS OF WORK SHALL BE MARKED IN THE FIELD PRIOR TO THE START OF CONSTRUCTION OR SITE CLEARING.
- SEDIMENT AND EROSION CONTROL MEASURES SHALL BE IMPLEMENTED PRIOR TO ANY
- CONTRACTOR SHALL INSPECT AND REPAIR ALL EROSION CONTROL DEVISES IF INTENSE RAINFALL IS PREDICTED. THE CONTRACTOR'S REPRESENTATIVE SHALL INSPECT THE CONSTRUCTION SITE AS NEEDED AND WITHIN 24 HOURS OR A RAINFALL OF 0.5 INCHES OR MORE.
- 4. ALL SOIL STOCKPILES SHALL HAVE EROSION CONTROL MEASURES AROUND THEIR EDGES AT ALL TIMES, SOIL STOCKPILES SHALL BE COVERED WITH TEMPORARY VEGETATION OR FASTENED TARPAULIN SHEETS.
- DURING DRIVEWAY CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN A ONE FOOT HIGH BY TWO FOOT WIDE EARTHEN BERM ALONG THE EDGES OF THE DRIVEWAY TO DIVERT RUNOFF TO A TEMPORARY SEDIMENT BASIN. STRAWBALES MAY BE UTILIZED TO DIVERT RUNOFF FROM THE DRIVEWAY LOW POINTS TO A TEMPORARY SEDIMENT BASIN DURING CONSTRUCTION UNTIL THE DRAINAGE SYSTEM IS INSTALLED.
- 6. THE DRAINAGE SYSTEM SHALL BE CONSTRUCTED DURING THE EARLIEST STAGES OF THE PROJECT IN ORDER TO COLLECT RUNOFF AND SEDIMENT.
- . ALL CATCH BASINS SHALL BE PROTECTED WITH SILT SACKS DURING CONSTRUCTION. CATCH BASIN GRATES ARE TO BE SET AT BINDER GRADE AND INSTALL SILT SACK UNTIL IT IS TIME TO APPLY THE PAVEMENT WEARING COURSE.
- 8. ALL CATCH BASIN SUMPS SHALL BE CLEANED DURING AND FOLLOWING CONSTRUCTION. THEREAFTER REFER TO OPERATION AND MAINTENANCE PLAN.
- 9. ALL CUT AND FILL SLOPES SHALL BE IMMEDIATELY COVERED WITH 6" OF LOAM AND SEEDED DURING THE GROWING SEASON (APRIL 1 TO NOVEMBER 1) OR COVERED WITH HAYMULCH DURING THE NON-GROWING SEASON (NOVEMBER 1 TO APRIL 1). IN AREAS SUBJECT TO THE WETLANDS PROTECTION ACT, THE HAYMULCH AND/OR REQUIRED MEASURES SHALL REMAIN IN PLACE UNTIL PERMANENT VEGETATION IS ESTABLISHÉD. UNLESS OTHERWISE INDICATED, ALL DISTURBED AREAS SHALL RECEIVE 6" OF LOAM AND BE SEEDED TO PREVENT EROSION.
- 10. THE SILTATION BARRIER SHALL BE MAINTAINED UNTIL VEGETATIVE COVER HAS BEEN SUITABLY ESTABLISHED AND GRADED SLOPES ARE STABLE.
- 11. DISTRUBED AREAS WHERE CONSTRUCTION HAS PERMANENTLY OR TEMPORARILY CEASED MUST BE STABILIZED WITHIN 14 DAYS OF THE LAST DISTURBANCE. AREAS WHICH WILL BE REDISTURBED WITHIN 21 DAYS DO NOT HAVE TO BE STABILIZED.
- 12. ADDITIONAL EROSION CONTROL MEASURES SHALL BE STOCK-PILED ON-SITE, INCLUDING BUT NOT LIMITED TO CRUSHED STONE, STRAW BALES, SILT FENCE AND EROSION CONTROL MATS.
- 13. SEDIMENT SHALL BE REMOVED BEHIND ALL STRAW BALES AND SILT FENCES IF DEPTH EXCEEDS 6".
- 14. THE EROSION CONTROL DEVICES SHALL BE MAINTAINED UNTIL TRIBUTARY SURFACES ARE
- 15. DURING CONSTRUCTION, THE CONTRACTOR SHALL SPRAY DOWN THE SITE WITH A WATER TRUCK AS NEEDED FOR DUST CONTROL IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REGULATIONS. TEMPORARY VEGETATION AND/OR USE OF TARPAULIN MAY BE NECESSARY.
- 16. THE DEVELOPER IS REQUIRED TO CLEAN UP ANY SAND, DIRT, OR DEBRIS WHICH ERODES FROM THE SITE ONTO ANY PUBLIC STREET OR PRIVATE PROPERTY, AND TO REMOVE SILT OR DEBRIS THAT ENTERS ANY EXISTING DRAINAGE SYSTEM INCLUDING CATCH BASIN SUMPS, PIPE LINE, MANHOLES AND DITCHES.

LONG TERM POLLUTION PREVENTION AND

DRAINAGE SYSTEM OPERATION AND MAINTENANCE PLAN

THERE SHALL BE NO ILLICIT DISCHARGES TO ANY PART OF THE STORM DRAIN SYSTEM.

THE IMPLEMENTATION, INSPECTION, AND REPAIR OF THE EROSION CONTROLS IS THE RESPONSIBILITY OF THE SITE CONTRACTOR DURING CONSTRUCTION.

THE INSPECTION AND OPERATION OF THE STORM WATER MANAGEMENT SYSTEM UPON COMPLETION OF CONSTRUCTION IS THE RESPONSIBILITY OF:

PARTIES RESPONSIBLE FOR LONG TERM OPERATION/MAINTENANCE: HOMEOWNERS ASSOCIATION

SCHEDULE FOR INSPECTION AND MAINTENANCE:

STREET SWEEPING:

IT IS RECOMMENDED THAT THE PAVEMENT SHALL BE PROPERLY SWEPT FOUR TIMES A YEAR, WITH CONCENTRATIONS IN THE SPRING AND THE FALL.

SUBSURFACE CHAMBERS:

INSPECT THE DRYWELL/INFILTRATION BED AFTER EVERY MAJOR STORM FOR THE FIRST FEW MONTHS TO ENSURE PROPER STABILIZATION AND FUNCTION. THEREAFTER, INSPECT AND CLEAN IT AT LEAST ONCE PER YEAR. WATER LEVELS SHOULD BE RECORDED OVER SEVERAL DAYS TO CHECK THE DRYWELL DRAINAGE.

DEEP SUMP AND HOODED CATCH BASINS

DURING CONSTRUCTION, CATCH BASIN GRATES SHALL BE PROVIDED WITH SILT SACKS. CATCH BASINS SHALL BE CLEANED UPON THE COMPLETION OF CONSTRUCTION. AFTER CONSTRUCTION, THE DEEP SUMPS FOR ALL CATCH BASINS AND DRAIN MANHOLES SHALL BE INSPECTED FOUR TIMES A YEAR AND CLEANED FOUR TIMES A YEAR. SEDIMENT REMOVED SHALL BE DISPOSED OF IN ACCORDANCE WITH APPLICABLE LOCAL, STATE, AND FEDERAL GUIDELINES AND REGULATIONS.

THE DEPTH OF THE DESIMENT IN A BASIN SHALL NOT EXCEED A DEPTH OF 18 INCHES AS DETERMINED BY PROBING WITH A STICK. IF THE STICK HITS THE BOTTOM WITHIN 30 INCHES OF THE WATER LEVEL, MORE THAN 18 INCHES OF SEDIMENT HAS ACCUMULATED AND MUST BE REMOVED. LICENSED PERSONS SHOULD REMOVE AND DISPOSE OF THE CONTENTS OF THE SUMP IN ACCORDANCE WITH APPLICABLE REGULATIONS.

EMERGENCY CONTACTS: IN THE EVENT OF A HAZARDOUS MATERIALS SPILL ON THE SITE THE FOLLOWING PARTIES SHALL BE CONTACTED: FIRE DEPARTMENT: PH: (617) 796-2210

RECORDS:

THE DEVELOPER SHALL MAINTAIN AN INSPECTION LOG OF ALL ELEMENTS OF THE STORMWATER MANAGEMENT PLAN DURING CONSTRUCTION. A COPY OF THE EROSION CONTROL AND STORM WATER MAINTENANCE PLAN AND INSPECTION LOGS SHALL BE KEPT ONSITE AT ALL TIMES UNTIL ACCEPTANCE OF THE ROAD. EACH INDIVIDUAL LOT OWNER SHALL ALSO MAINTAIN RECORDS FOR PRIVATE STRUCTURES ON THEIR LOT.

SITE PLAN 499 WINCHESTER STREET


NEWTON, MASSACHUSETTS (MIDDLESEX COUNTY)

EROSION & SEDIMENT CONTROL PLAN

CAROLINA PROPERTIES, LLC SCALE: 1"=20' FEBRUARY 25, 2019

STAMSKI AND MCNARY, INC. 1000 MAIN STREET ACTON, MASSACHUSETTS

ENGINEERING - PLANNING - SURVEYING SHEET 6 OF (6139.SITE.F.dwa) SM - 6139



MARCH

\$638#

GEORGE

