

CITY OF NEWTON
Department of Public Works
ENGINEERING DIVISION

MEMORANDUM

To: Alderman Mark Laredo, Land Use Committee Chairman

From: John Daghlian, Associate City Engineer

Re: Special Permit – 2 Wells Avenue

Date: May 27, 2015

CC: Lou Taverna, PE City Engineer
Linda Finucane, Associate City Clerk
Alexandria Ananth, Chief Planner
Dan Sexton, Sr. Planner

In reference to the above site, I have the following comments for a plan entitled:

*2 Wells Avenue Expansion
Newton, MA
Prepared by: Nitsch Engineering
Dated: 5-8-'15
&
Stormwater Report Dated: May 8, 2015*

Executive Summary:

This projects involves the partial demolition of a one story building and addition of a 3 story office building; expansion of a parking lot and updating of municipal utilities. The project involves on-site collection and infiltration of storm-water runoff from the parking facilities and impervious surfaces of the building. The enhancements will improve water quality being discharged from the site compared to the existing conditions.

As a public benefit the DPW is requesting that the existing asphalt sidewalks along the frontage of the property be upgraded to current ADA Standards and City of Newton Standards.

Construction Management:

1. A construction management plan is needed for this project. At a minimum, it must address the following: staging site for construction equipment, construction materials, parking of construction worker's vehicles, phasing of the project with anticipated completion dates and milestones, safety precautions, emergency contact personnel of contractor. It shall also address any anticipated dewatering during construction, site safety & stability, and impact to abutting properties.

Drainage:

1. The storm water report and drainage analysis is acceptable for the City of Newton's 100-year storm event of 6-inches over a 24-hour period. The design of the proposed on site drainage system complies with the MassDEP Stormwater Regulations and City Ordinances and DPW policies.
2. When a connection to the City's drainage system is proposed, prior to approval of the Building Permit a Closed Circuit Television (CCTV) inspection shall be performed and witnessed by the Engineering Division, the applicant shall retain a contractor that specializes in CCTV inspection. The applicant shall contact the Engineering Division 48 hours in advance to schedule an appointment. At the end of the inspection the video or CD shall be given to the inspector. Furthermore, upon completion of the connection to the drainage system a Post – Construction video inspection shall also take place and witnessed as described above. This is required regardless of the connection point, the intent is to ensure that there are no downstream blockages or damaged pipe so that the contractor of record is not held accountable for preexisting conditions.
3. The proposed Operations and Maintenance (O&M) plan for Stormwater Management Facilities is acceptable; if the permit is approved the document shall be incorporated into the deeds; and recorded at the Middlesex Registry of Deeds. A copy of the recording instrument shall be submitted to the Engineering Division.
4. It is imperative to note that the ownership, operation, and maintenance of the proposed drainage system and all appurtenances including but not limited to the drywells, catch basins, and pipes are the sole responsibility of the property owner(s).

Environmental:

1. Has a 21E investigation & report been performed on the site, if so copies of the report should be submitted the Newton Board of Health and the Engineering Division.
2. Are there any existing underground oil or fuel tanks, are they to be removed, if they have been evidence should be submitted to the Newton Fire Department, and Newton Board of Health.
3. As the total site disturbance is over an acre, a Phase II General Construction (NPDES) Permit will need to be filed with DEP & EPA. A Stormwater Pollution Prevention Plan (SWPPP) will need to be developed.

Sewer:

1. The project lies within Area A of the City's sewer basin; this basin has Infiltration & Inflow (I &I) issues that affect the carrying capacity of the sewer system. Since the project is an office building it does not trigger an assessment for I & I; however, if in the future the use of the building is converted to residential use, then an assessment will be implemented.
2. The existing water & sewer services to the building shall be cut and capped at the main and be completely removed from the main and the site then properly back filled. The Engineering Division must inspect this work; failure to having this work inspected may result in the delay of issuance of the Utility Connection Permit.
3. Use City of Newton Details in lieu of the details submitted they are in PDF format on the City's website.
4. With the exception of natural gas service(s), all utility trenches with the right of way shall be backfilled with Control Density Fill (CDF) Excavatable Type I-E, detail is available in the city of Newton Construction Standards Detail Book.
5. All new sewer service and/or structures shall be pressure tested or videotaped after final installation is complete. Method of final inspection shall be determined solely by the construction inspector from the City Engineering Division. All sewer manholes shall be vacuum tested in accordance to the City's Construction Standards & Specifications. The sewer service will NOT be accepted until one of the two methods stated above is completed. All testing MUST be witnessed by a

representative of the Engineering Division. A Certificate of Occupancy will not be recommended until this test is completed and a written report is received by the City Engineer. ***This note must be added to the final approved plans.***

6. All sewer manholes shall be vacuum tested in accordance to the City's Construction Standards & Specifications. The sewer service will NOT be accepted until one of the two methods stated above is completed. All testing MUST be witnessed by a representative of the Engineering Division. A Certificate of Occupancy will not be recommended until this test is completed and a written report is received by the City Engineer.

Water:

1. Fire flow testing is required for the proposed fire suppression system. The applicant must coordinate this test with both the Newton Fire Department and the Utilities Division; representatives of each department shall witness the testing, test results shall be submitted in a write report. Hydraulic calculation shall be submitted to the Newton Fire Department for approval.
2. For water quality issues a fire hydrant will be required at the end of the proposed water main. This hydrant will be utilized for flushing out the main as required.
3. All water connections shall be chlorinated & pressure tested in accordance to AWWA and the City of Newton Construction Standards and Specifications prior to opening the connection to existing pipes.
4. Approval of the final configuration of the water service(s) shall be determined by the Utilities Division, the engineer of record should submit a plan to the Director of Utilities for approval

General:

1. Finalized utility connection plan reflecting the above changes that meets the minimal design standards of the City of Newton must be submitted for approval by the contractor of record with appropriate Bonds & Insurance. The Engineering Division makes no representations and assumes no responsibility for the design(s) in terms of suitability for the particular site conditions or of the functionality or performance of any items constructed in accordance with the design(s). The City of Newton assumes no liabilities for design assumption, error or omissions by the Engineer of Record.

2. All trench excavation contractors shall comply with Massachusetts General Laws Chapter 82A, Trench Excavation Safety Requirements, to protect the general public from unauthorized access to unattended trenches. Trench Excavation Permit required. This applies to all trenches on public and private property. *This note shall be incorporated onto the plans*
3. All tree removal shall comply with the City's Tree Ordinance.
4. Due to the total square footage of the building, a scale massing model will be needed.
5. The contractor is responsible for contacting the Engineering Division and scheduling an appointment 48 hours prior to the date when the utilities will be made available for an inspection of water services, sewer service, and drainage system installation. The utility is question shall be fully exposed for the inspector to view; backfilling shall only take place when the City's Inspector has given their approval. *This note should be incorporated onto the plans*
6. The applicant will have to apply for Street Opening, Sidewalk Crossing, and Utilities Connecting permits with the Department of Public Works prior to any construction. *This note must be incorporated onto the site plan.*
7. The applicant will have to apply for a Building Permits with the Department of Inspectional Service prior to any construction.
8. Prior to Occupancy Permit being issued, an As-Built Plan shall be submitted to the Engineering Division in both digital format and in hard copy. The plan should show all utilities and final grades, any easements and final grading. *This note must be incorporated onto the site plan.*
9. All site work must be completed before a Certificate of Occupancy is requested. *This note must be incorporated onto the site plan.*

Note: If the plans are updated it is the responsibility of the Applicant to provide all City Departments [Conservation Commission, ISD, and Engineering] involved in the permitting and approval process with complete and consistent plans.

If you have any questions or concerns please feel free to contact me @ 617-796-1023.