CITY OF NEWTON Department of Public Works ENGINEERING DIVISION

MEMORANDUM

To: Alderman Mark Laredo, Land Use Committee Chairman

From: John Daghlian, Associate City Engineer

Re: Special Permit – 15 South Gate Park

Date: July 9, 2015

CC: Lou Taverna, PE City Engineer

Linda Finucane, Associate City Clerk Alexandria Ananth, Chief Planner Stephen Pantalone, Sr. Planner

In reference to the above site, I have the following comments for a plan entitled:

Proposed Conditions Site Plan 15 South Gate Park Newton, MA Prepared by: Verne T. Porter, Jr., PLS Dated: June 8, 2015

Executive Summary:

The proposed project is a 5 unit attached dwelling with underground and surface parking located on a 14,120 square foot lot currently occupied by the Knights of Columbus Hall. The site is essentially all impervious except for a grassy area on the north side of the lot. No drainage study was submitted for review. The plan indicates a ramp sloped at 10% gradient down to the underground parking facility, given the sighting of the proposed building it appears that vehicle maneuvering into and out of the garage will be impractical. The driveway scales approximately 10' wide, which is not wide enough for two way traffic; so some sort of traffic signals will be needed to enter and exit the underground garage. The proposed retaining wall that is parallel to the ramp needs

15 South Gate Park Page 1 of 6

grades and elevations as well as material specification. It is also unclear as to the clearance under the wood bridge crossing the ramp to the garage, sections and profiles and vehicle turning template plans are needed to demonstrate that this design actually works. More than likely the Fire Department will require a fire suppression system for the development, yet only a generic note for a single copper water service is labeled.

All drainage within the interior of the garage must be connected to the sanitary sewer yet there is nothing shown to reference this. Three curb cuts seems a bit excessive for one lot, the engineer of record should reconsider and consolidate the total number of curb cuts. Snow storage needs to be identified, how will trash & recycling be addressed?

In concert with the proposed cement concrete sidewalks and curbing pedestrian curb cuts (a.k.a. HP ramps) are needed at Adena Road and South Gate Park.





Construction Management:

1. A construction management plan is needed for this project. At a minimum, it must address the following: staging site for construction equipment, construction materials, parking of construction worker's vehicles, phasing of the project with anticipated completion dates and milestones, safety precautions, emergency

15 South Gate Park Page 2 of 6

contact personnel of contractor. It shall also address any anticipated dewatering during construction, site safety & stability, and impact to abutting properties.

2. Stabilized driveway entrances are needed during construction which will provide a tire wash and mud removal to ensure City streets are kept clean.

Drainage:

- 1. A drainage analysis needs to be performed based on the City of Newton's 100-year storm event of 6-inches over a 24-hour period. All runoff from impervious areas need to be infiltrated on site, for the project. The design of the proposed on site drainage system needs to comply with the MassDEP Stormwater Regulations and City Ordinances.
- 2. An on-site soil evaluation needs to be performed to obtain the seasonal high groundwater elevation, percolation rate in accordance to Title V. This information must be submitted with the drainage study. The locations of these tests need to be shown on the site plan and must be performed within 25-feet of a proposed system.
- 3. An Operations and Maintenance (O&M) plan for Stormwater Management Facilities needs to drafted and submitted for review. Once approved the O&M must be adopted by applicant, incorporated into the deeds; and recorded at the Middlesex Registry of Deeds. A copy of the recording instrument shall be submitted to the Engineering Division.
- 4. It is imperative to note that the ownership, operation, and maintenance of the proposed drainage system and all appurtenances including but not limited to the drywells, catch basins, and pipes are the sole responsibility of the property owner(s).

Environmental:

- 1. Has a 21E investigation & report been performed on the site, if so copies of the report should be submitted the Newton Board of Health and the Engineering Division.
- **2.** Are there any existing underground oil or fuel tanks, are they to be removed, if they have been evidence should be submitted to the Newton Fire Department, and Newton Board of Health.

15 South Gate Park Page 3 of 6

Sewer:

- 1. A detailed profile is needed which shows the existing water main, proposed water service(s), sewer main and proposed sewer service(s) with the slopes and inverts labeled to ensure that there are no conflicts between the sewer services and the water service. The minimum slope for a service is 2.0%, with a maximum of 10%. Pipe material shall be 6" diameter SDR 35 PVC pipe within 10' of the dwelling then 4" pipe per Massachusetts State Plumbing Code. In order to verify the slopes and inverts of the proposed service connection, two manholes of the existing sanitary sewer system need to be identified on the plan with rim & invert elevations. The crown of the service connection & the sewer man need to match.
- 2. The existing water & sewer services to the building shall be cut and capped at the main and be completely removed from the main and the site then properly back filled. The Engineering Division must inspect this work; failure to having this work inspected may result in the delay of issuance of the Utility Connection Permit.
- **3.** Use City of Newton Details in lieu of the details submitted they are in PDF format on the City's website.
- **4.** With the exception of natural gas service(s), all utility trenches with the right of way shall be backfilled with Control Density Fill (CDF) Excavatable Type I-E, detail is available in the city of Newton Construction Standards Detail Book.
- 5. All new sewer service and/or structures shall be pressure tested or videotaped after final installation is complete. Method of final inspection shall be determined solely by the construction inspector from the City Engineering Division. All sewer manholes shall be vacuum tested in accordance to the City's Construction Standards & Specifications. The sewer service will NOT be accepted until one of the two methods stated above is completed. All testing MUST be witnessed by a representative of the Engineering Division. A Certificate of Occupancy will not be recommended until this test is completed and a written report is received by the City Engineer. This note must be added to the final approved plans.
- 6. All sewer manholes shall be vacuum tested in accordance to the City's Construction Standards & Specifications. The sewer service will NOT be accepted until one of the two methods stated above is completed. All testing MUST be witnessed by a representative of the Engineering Division. A Certificate of Occupancy will not be recommended until this test is completed and a written report is received by the City Engineer.

15 South Gate Park Page 4 of 6

Water:

- 1. Fire flow testing is required for the proposed fire suppression system. The applicant must coordinate this test with both the Newton Fire Department and the Utilities Division; representatives of each department shall witness the testing, test results shall be submitted in a write report. Hydraulic calculation shall be submitted to the Newton Fire Department for approval.
- 2. All water connections shall be chlorinated & pressure tested in accordance to AWWA and the City of Newton Construction Standards and Specifications prior to opening the connection to existing pipes.
- 3. Approval of the final configuration of the water service(s) shall be determined by the Utilities Division, the engineer of record should submit a plan to the Director of Utilities for approval

General:

- 1. Finalized utility connection plan reflecting the above changes that meets the minimal design standards of the City of Newton must be submitted for approval by the contractor of record with appropriate Bonds & Insurance. The Engineering Division makes no representations and assumes no responsibility for the design(s) in terms of suitability for the particular site conditions or of the functionability or performance of any items constructed in accordance with the design(s). The City of Newton assumes no liabilities for design assumption, error or omissions by the Engineer of Record.
- 2. All trench excavation contractors shall comply with Massachusetts General Laws Chapter 82A, Trench Excavation Safety Requirements, to protect the general public from unauthorized access to unattended trenches. Trench Excavation Permit required. This applies to all trenches on public and private property. *This note shall be incorporated onto the plans*
- 3. All tree removal shall comply with the City's Tree Ordinance.
- 4. The contractor is responsible for contacting the Engineering Division and scheduling an appointment 48 hours prior to the date when the utilities will be made available for an inspection of water services, sewer service, and drainage system installation. The utility is question shall be fully exposed for the inspector to view; backfilling shall only take place when the City's Inspector has given their approval. This note should be incorporated onto the plans

15 South Gate Park Page 5 of 6

- 5. The applicant will have to apply for Street Opening, Sidewalk Crossing, and Utilities Connecting permits with the Department of Public Works prior to any construction. *This note must be incorporated onto the site plan*.
- 6. The applicant will have to apply for a Building Permits with the Department of Inspectional Service prior to any construction.
- 7. Prior to Occupancy Permit being issued, an As-Built Plan shall be submitted to the Engineering Division in both digital format and in hard copy. The plan should show all utilities and final grades, any easements and final grading. *This note must be incorporated onto the site plan*.
- 8. All site work being completed before a Certificate of Occupancy is requested. *This note must be incorporated onto the site plan.*

Note: If the plans are updated it is the responsibility of the Applicant to provide all City Departments [Conservation Commission, ISD, and Engineering] involved in the permitting and approval process with complete and consistent plans.

If you have any questions or concerns please feel free to contact me @ 617-796-1023.

15 South Gate Park Page 6 of 6