

**CITY OF NEWTON
DEPARTMENT OF PUBLIC WORKS
ENGINEERING DIVISION**

MEMORANDUM

To: Alderman Mark Laredo, Land Use Committee Chairman

From: John Daghlian, Associate City Engineer

Re: Special Permit – #131-181 Needham Street

Date: February 6, 2015

CC: Lou Taverna, PE City Engineer
Linda Finucane, Associate City Clerk
Alexandria Ananth, Chief Planner
Stephen Pantalone, Sr. Planner

In reference to the above site, I have the following comments for a plan entitled:

*Site Development Plans
For
Newton Nexus
Newton, MA
Prepared by: Kelly Engineering Group
Dated: January 9, 2015*

Executive Summary:

This project involves the redevelopment of an 11 acre [multiple parcels] site that will include two new buildings and rehabilitation of a third building. The site improvements include on-site drainage system that will improve stormwater water quality and groundwater recharge as required by the Department of Environmental Protect (DEP) and the DPW. The proposed Drainage system is in conformance of the City's Stormwater Policy & incorporates best management practices recommended by the Massachusetts Stormwater Management Handbook.

As required for all new construction sanitary sewer service must be renewed from the building to the existing sanitary sewer mains. Since the third building is to be renovated and the existing service is 64 year old clay pipe, it needs to be updated to current City standards.

All utility work and curb, sidewalk and drive aprons need MassDOT approval, as Needham Street is a state road.

If the special permit is approved an Approval Not Required (ANR) plan will be needed in accordance to Massachusetts General Laws Chapter 41 Section 81P requiring the multiple separate lots be combined into one lot.

Prior to any construction a Preconstruction Closed Circuit Television (CCTV) inspection shall be performed on any City Drain or Sanitary Sewer Mains within any City Easement that is on these properties, and witnessed by the Engineering Division, the applicant shall retain a contractor that specializes in CCTV inspection. The applicant shall contact the Engineering Division 48 hours in advance to schedule an appointment. At the end of the inspection the video or CD shall be given to the inspector. Furthermore, upon completion of all construction a Post – Construction video inspection shall also take place and witnessed as described above. This is required regardless of the connection point, the intent is to ensure that there are no downstream blockages or damaged pipe so that the contractor of record is not held accountable for preexisting conditions.

Construction Management:

1. A construction management plan is needed for this project. At a minimum, it must address the following: staging site for construction equipment, construction materials, parking of construction worker's vehicles, phasing of the project with anticipated completion dates and milestones, safety precautions, emergency contact personnel of contractor. It shall also address any anticipated dewatering during construction, site safety & stability, and impact to abutting properties.
2. Stabilized driveway entrances are needed during construction which will provide a tire wash and mud removal to ensure City streets are kept clean.
3. A temporary construction safety fence is needed around the entire site for the duration of the project.

Drainage:

1. When a connection to the City's drainage system is proposed, prior to approval of the Building Permit a Closed Circuit Television (CCTV) inspection shall be performed and witnessed by the Engineering Division, the applicant shall retain a contractor that specializes in CCTV inspection. The applicant shall contact the Engineering Division 48 hours in advance to schedule an appointment. At the end of the inspection the video or CD shall be given to the inspector. Furthermore, upon completion of the connection to the drainage system a Post – Construction video inspection shall also take place and witnessed as described above. This is required regardless of the connection point, the intent is to ensure that there are no downstream blockages or damaged pipe so that the contractor of record is not held accountable for preexisting conditions.
2. The proposed Operations and Maintenance (O&M) plan for Stormwater Management Facilities is acceptable and needs to be adopted by applicant, incorporated into the deeds; and recorded at the Middlesex Registry of Deeds. A copy of the recording instrument shall be submitted to the Engineering Division.
3. It is imperative to note that the ownership, operation, and maintenance of the proposed drainage system and all appurtenances including but not limited to the drywells, catch basins, and pipes are the sole responsibility of the property owner(s).

Environmental:

1. Has a 21E investigation & report been performed on the site, if so copies of the report should be submitted the Newton Board of Health and the Engineering Division.
2. Are there any existing underground oil or fuel tanks, are they to be removed, if they have been evidence should be submitted to the Newton Fire Department, and Newton Board of Health.
3. As the total site disturbance is over an acre, a Phase II General Construction (NPDES) Permit will need to be filed with DEP & EPA. A Stormwater Pollution Prevention Plan (SWPPP) will need to be developed.

Sewer:

1. A detailed profile is needed which shows the existing water main, proposed water service(s), sewer main and proposed sewer service(s) with the slopes and inverts labeled to ensure that there are no conflicts between the sewer services and the water service. The minimum slope for a service is 2.0%, with a maximum of 10%. Pipe material shall be 6" diameter SDR 35 PVC pipe within 10' of the dwelling then 4" pipe per Massachusetts State Plumbing Code. In order to verify the slopes and inverts of the proposed service connection, two manholes of the existing sanitary sewer system need to be identified on the plan with rim & invert elevations. The crown of the service connection & the sewer man need to match.
2. The existing water & sewer services to the building shall be cut and capped at the main and be completely removed from the main and the site then properly back filled. The Engineering Division must inspect this work; failure to having this work inspected may result in the delay of issuance of the Utility Connection Permit.
3. With the exception of natural gas service(s), all utility trenches with the right of way shall be backfilled with Control Density Fill (CDF) Excavatable Type I-E, detail is available in the city of Newton Construction Standards Detail Book.
4. As Needham Street has been repaved within the last 2 years, the utility trenches and roadway the MassDOT may require the roadway to be milled 25' on both sides of the utility trenches from curb line to curb line; then paved with 1-1/2" of Type I-1 Bituminous Concrete, this will be finalized when the applicant applies for a Street Opening Permit with MassDOT.
5. All new sewer service and/or structures shall be pressure tested or videotaped after final installation is complete. Method of final inspection shall be determined solely by the construction inspector from the City Engineering Division. All sewer manholes shall be vacuum tested in accordance to the City's Construction Standards & Specifications. The sewer service will NOT be accepted until one of the two methods stated above is completed. All testing MUST be witnessed by a representative of the Engineering Division. A Certificate of Occupancy will not be recommended until this test is completed and a written report is received by the City Engineer. ***This note must be added to the final approved plans.***
6. All sewer manholes shall be vacuum tested in accordance to the City's Construction Standards & Specifications. The sewer service will NOT be accepted until one of the two methods stated above is completed. All testing MUST be witnessed by a representative of the Engineering Division. A Certificate of Occupancy will not be recommended until this test is completed and

a written report is received by the City Engineer. ***This note must be added to the final approved plans.***

Water:

1. Fire flow testing is required for the proposed fire suppression system. The applicant must coordinate this test with both the Newton Fire Department and the Utilities Division; representatives of each department shall witness the testing, test results shall be submitted in a write report. Hydraulic calculation shall be submitted to the Newton Fire Department for approval.
2. All water connections shall be chlorinated & pressure tested in accordance to AWWA and the City of Newton Construction Standards and Specifications prior to opening the connection to existing pipes.
3. Approval of the final configuration of the water service(s) shall be determined by the Utilities Division, the engineer of record should submit a plan to the Director of Utilities for approval

General:

1. All trench excavation contractors shall comply with Massachusetts General Laws Chapter 82A, Trench Excavation Safety Requirements, to protect the general public from unauthorized access to unattended trenches. Trench Excavation Permit required. This applies to all trenches on public and private property. *This note shall be incorporated onto the plans*
2. All tree removal shall comply with the City's Tree Ordinance.
3. The contractor is responsible for contacting the Engineering Division and scheduling an appointment 48 hours prior to the date when the utilities will be made available for an inspection of water services, sewer service, and drainage system installation. The utility in question shall be fully exposed for the inspector to view; backfilling shall only take place when the City's Inspector has given their approval. *This note should be incorporated onto the plans*
4. The applicant will have to apply for Street Opening, Sidewalk Crossing, and Utilities Connecting permits with the Department of Public Works prior to any construction. *This note must be incorporated onto the site plan.*

5. The applicant will have to apply for a Building Permits with the Department of Inspectional Service prior to any construction.
6. Prior to Occupancy Permit being issued, an As-Built Plan shall be submitted to the Engineering Division in both digital format and in hard copy. The plan should show all utilities and final grades, any easements and final grading. *This note must be incorporated onto the site plan.*
7. If a Certificate of Occupancy is requested prior to all site work being completed. *This note must be incorporated onto the site plan.*

Note: If the plans are updated it is the responsibility of the Applicant to provide all City Departments [Conservation Commission, ISD, and Engineering] involved in the permitting and approval process with complete and consistent plans.

If you have any questions or concerns please feel free to contact me @ 617-796-1023.